



Summary Report of All Sales for the Month of January 2005

Board Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clark	Pacific Cascade	76316	CAVEMAN	7,459	\$2,531,000.00
Cowlitz	Pacific Cascade	75738	THE OTHER SIDE	4,094	\$1,466,000.00
Grays Harbor	Olympic	76259	BURROW	5,921	\$1,417,000.00
Grays Harbor	Pacific Cascade	76379	POLYESTER PLAID	5,810	\$1,957,000.00
Jefferson	Olympic	74816	GOLDEN GOAT	2,385	\$667,000.00
Kitsap	South Puget	76004	SPARROW	2,189	\$692,000.00
Klickitat	Southeast	76130	WAHKIACUS THINNING	1,885	\$367,000.00
Mason	South Puget	76008	PUMA	2,107	\$646,000.00
Skagit	Northwest	76040	ROCKY RACCOON	6,927	\$2,332,000.00
Snohomish	Northwest	76496	ALTERED ATOM	3,690	\$1,347,000.00
Thurston	Pacific Cascade	74597	ZEBRA POLE	1,454	\$650,000.00
Thurston	Pacific Cascade	76113	QUICK GETAWAY	4,757	\$1,637,000.00
Thurston	Pacific Cascade	76344	VANILLA BEAN	7,471	\$2,519,000.00
Total				56,149	\$18,228,000.00

Region Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Kittitas	Southeast	72999	NANEUM HIGH	1,241	\$239,000.00
Klickitat	Southeast	71261	APPLE POLE	193	\$93,000.00
Total				1,434	\$332,000.00



TIMBER NOTICE OF SALE

SALE NAME: *CAVEMAN*

AGREEMENT NO: *30-076316*

AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Clark
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 21 miles east of Battle Ground, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber, including the trees marked with red paint along the property line, except leave trees tagged out with leave tree area boundary tags and leave trees marked with blue paint, bounded by timber sale boundary tags, property line, logged area, the L-1210, L-1100C, L-1120, and L-1100 roads in Unit #1; all timber, except leave trees tagged out with leave tree area boundary tags and leave trees marked with blue paint, bounded by timber sale boundary tags and the L-1100 road in Unit #2; #3; and #5; all timber, except leave trees tagged out with leave tree area boundary tags and leave trees marked with blue paint, bounded by timber sale boundary tags the L-1100 and L-1180 roads in Unit #4; within the sale area, no existing down woody debris greater than 36 inches in diameter shall be removed from the sale area, all snags that must be felled for safety reasons shall be left on site, and no red cedar shall be cut unless it is within the right-of-way on part(s) of Sections 34, 35 and 36 all in Township 4 North, Range 4 East, W.M., containing 262 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	17.4	6	7,210						3,984	2,764	462	
Red alder	12		224						34	51	139	
Silver fir	38		25						16	9		
Sale Total			7,459									

MINIMUM BID: \$2,531,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$253,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment may be used on the entire sale area throughout the year with tracked harvesting equipment (Tracked Skidder, Shovel, Processor, or Forwarder,) being restricted to slopes of 35% and less during dry soil conditions. Along the property line within Unit #1, Purchaser shall fall all timber up to and including the trees that are marked with red paint. Non-merchantable trees shall be left undamaged where harvest activities allow. Year round harvesting will be allowed during dry soil conditions on all units except Unit #1. Falling and yarding is not permitted in Unit #1 on any weekends or State recognized holidays from July 1 through Labor Day. Suspend the lead end of all logs during all types of harvesting. 400 well distributed plantable spots per acre shall remain after harvest activities on all areas of the sale. This shall include pulling and piling of brush and slash, where needed, into piles or windrows no larger than 10 feet in width.

ROADS: 87.57 stations of optional construction. 10.65 stations of pre-haul maintenance. Installation of a culvert at MP 3.07 on the L-1100 road. 98.22 stations of road abandonment. Rock is available at no charge from two State pits in Sections 1 and 2, Township 3 North, Range 4 East, W.M.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by GPS. Cruise was completed using variable plot cruise methods. Harvesting activities are estimated to be 100% ground based harvesting.

FEES: \$98,830.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: The gate on the L-1210 road will be open to purchasers. The gate on the L-1180 road is hard to open and requires a Master A786 key which is available at the Pacific Cascade Region Office at Castle Rock. Special conditions shall apply to the Tarbell Trail and day use area, see Clause H-140.


NOTE: THERE ARE APPROXIMATELY 6 (six) POLE TREES PER ACRE WITHIN THE SALE AREA.

TIMBER SALE MAP

SALE NAME: CAVEMAN
 AGREEMENT NO: 30-076316
 TRUST(S): Forest Board Transfer (01), School (03)

REGION: Pacific Cascade
 COUNTY(S): Clark

Township 4 North, Range 4 East, W.M.




Drawn By: Rich O.
 Date: April 29, 2004
 Scale: 1" = 1000'
 Elevation: 1450' to 2100'



TIMBER SALE MAP

SALE NAME: CAVEMAN
 AGREEMENT NO: 30-076316
 TRUST(S): Forest Board Transfer (01), School (03)

REGION: Pacific Cascade
 COUNTY(S): Clark



Legend

	Sale Area		Stream Type 1-5
	Leave Tree Area		Water Type
	RMZ / WMZ		Wetland
	Sale Boundary Tags		Existing Gate
	Leave Tree Area Tags		Tarbell Trail
	Marked Leave Trees		Day Use Area
	Marked Take Trees		Monumented Corner
	Logged Area Boundary		Rock Pit
	Existing Road		
	Optional Construction		
	Pre-haul Maintenance		

Drawn By: Rich O.
 Date: April 30, 2004



TIMBER NOTICE OF SALE

SALE NAME: THE OTHER SIDE

AGREEMENT NO: 30-075738

AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Cowlitz
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 15 miles northwest of Longview, WA

PRODUCTS SOLD AND SALE AREA: All timber, including all orange marked take trees, except leave trees tagged out with leave tree area boundary tags and leave trees marked with blue paint, bounded by timber sale boundary tags and property lines in Units #1A, #1B, #1C, and #2; all timber bounded by right-of-way boundary tags on part(s) of Sections 3 and 4 all in Township 8 North, Range 4 West, Sections 28 and 33 all in Township 9 North, Range 4 West, W.M., containing 119 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	25.3	7	3,207			6	200		2,021	925	55	
Red alder	14.9		804					7	216	353	228	
Hemlock	29.5		56						40	16		
Maple	14.5		16					5	3		8	
Red cedar	30.4		11								11	
Sale Total			4,094									

MINIMUM BID: \$1,466,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$146,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment, with tracked harvesting equipment (tracked skidder or shovel) being restricted to slopes of 35% and less during dry soil conditions. Tracked harvesting equipment shall operate on a mat of slash when operating within the units. Purchaser shall provide 350 well distributed plantable spots per acre on all areas with a slope of 35% and less. Falling and Yarding will not be permitted from December 1 to March 31 unless authorized in writing by the Contract Administrator to minimize soil damage and erosion potential.

ROADS: 70.76 stations of required construction. 95.23 stations of required reconstruction. 29.12 stations of optional construction. 29.12 stations of road abandonment. Rock is available at no cost from a State pit in Section 4, Township 9 North, Range 4 West, W.M. Road construction will not be permitted from October 1 to June 30 unless authorized in writing by the Contract Administrator on the S-300 road from the Spur 1A junction to the end, to minimize soil erosion and road damage potential. The hauling of forest products will not be permitted from October 1 to June 30 unless authorized in writing by the Contract Administrator on the S-300 road from the Spur 1A junction to the end, to minimize rock needs and road damage potential.

ACREAGE DETERMINATION

CRUISE METHOD: Acres were determined by hand compass, laser range finder with a minimum error of closure of 1:220, and the sale area was cruised by using a variable plot cruise method. Harvesting activities are estimated to be 15% ground based harvesting and 85% cable harvesting.

FEES: \$54,250.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: A maximum of three corridors up to 30 feet in width will be allowed through the RMZ of the type 3 stream in Unit #1A, to facilitate harvest.

TIMBER SALE MAP


SALE NAME: THE OTHER SIDE
AGREEMENT NO: 30-075738
TRUST(S): Forest Board Transfer (01), School (03), Scientific (10)

REGION: Pacific Cascade
COUNTY(S): Cowlitz


Legend

-  Sale Area
-  Leave Tree Area
-  RM
-  Sale Boundary Tags
-  Management Unit Boundary Tags
-  R/W Boundary Tags
-  Marked Leave Trees
-  Marked Take Trees
-  Existing Road
-  Required Construction
-  Required Reconstruction
-  Optional Construction
-  Stream Type 1-5
-  Water Type
-  Monumented Corner
-  Existing Gate

Township 8 & 9 North Range 4 West, W.M.



Vicinity Map



Drawn By: Rich O.
 Date: January 12, 2004
 Scale: 1" = 1000'
 Elevation: 260' to 750'

TIMBER NOTICE OF SALE
SALE NAME: BURROW

AGREEMENT NO: 30-076259

AUCTION: January 25, 2005 starting at 10:00 a.m., **COUNTY:** Grays Harbor
 South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 26 miles north of Hoquiam, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by sale area boundary tags, a logged area, property lines, special management area tags and right of way boundary tags, except leave trees marked with blue paint on part(s) of Sections 16 all in Township 21 North, Range 9 West, W.M., containing 96 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19.7	7	3,090				22		1,794	1,137	137	
Hemlock	15.3	6	2,831						1,152	1,491	188	
Sale Total			5,921									

MINIMUM BID: \$1,417,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: January 31, 2007 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$141,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and/or shovel. A portion of the sale contains a blind lead and will require logs to be decked with a shovel and yarded uphill. See sale map for location.

ROADS: 75.50 stations of required construction. 10.00 stations of required reconstruction. Purchaser maintenance on all construction and reconstruction. Designated maintenance on all other roads used. Road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION
CRUISE METHOD: Sale area was 100% ground traversed. Error of closure for northern portion is 1:88 and southern portion is 1:231. The sale area was cruised using a variable plot sample with a BAF of 71.11F on a 330 x 176 foot grid. The right of way was cruised using a variable plot sample with a BAF of 71.11F and plots @ 176 feet.

FEES: Purchaser must enter into a Road Use Permit with the US Forest Service. Purchaser must pay the US Forest Service \$13,855.14 prior to any timber haul. Purchaser will also be required to pay the US Forest Service \$5.19 per mbf for timber haul and \$1.30 per cubic yard for rock haul. Billing will take place after haul has been completed and Purchaser will be required to report actual haul volumes to the US Forest Service and provide the State with receipts of payments made. \$78,453.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: None.

TIMBER SALE MAP

SALE NAME: BURROW
 AGREEMENT NO: 30-076259
 TRUST(S): Common School


REGION: Olympic
 COUNTY(S): Grays Harbor

Section 16
 Township 21N
 Range 9W, W.M.



Elevation: 500 - 1000'

Scale: 1" = 1000'



Legend

	Cable		Sale Boundary Tags		Water Type Break
	Shovel		Special Management Boundary Tags		Water Type
	Shovel Bunching Area		Property Line (blazed and painted)		Streams
	RMZ		Existing Road		Survey Monuments
	Leave Tree Areas		Required Construction		Gate To Be Installed
			Required Reconstruction		



TIMBER NOTICE OF SALE

SALE NAME: POLYESTER PLAID

AGREEMENT NO: 30-076379

AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Grays Harbor
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 7 miles north of Oakville, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber bounded by Timber Sale Boundary tags, reproduction, and E-2000 road in Unit #1 except; bounded by Timber Sale Boundary tags and E-2100 road in Unit #2; bounded by Timber Sale Boundary tags, reproduction, E-2000 road, E-2004 road, and E-2300 road in Unit #3; except trees bounded by Leave Tree Area tags, reserve trees to be selected and marked by the Purchaser as designated in Schedule Z, snags, down wood existing five years prior to the day of sale, and existing stumps; all timber bounded by Right-of-Way Boundary tags; on part(s) of Sections 9, 16, 17, 18 and 20 all in Township 16 North, Range 4 West, W.M., containing 153 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19	8	5,098				156		3,378	1,493	71	
Red alder	15.5		514						170	206	138	
Hemlock	17	7	123						78	18	27	
Red cedar	12.7		75							29	46	
Sale Total			5,810									

MINIMUM BID: \$1,957,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$195,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel equipment and cable systems. A tracked skidder for the removal of poles only. Lead end suspension required on all cable settings. Approximately 30% of this sale may be harvested using cable systems and 70% may be harvested using ground-based systems. Shovel yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 16.39 stations of required construction. 5.25 stations of required reconstruction. 73.81 stations of optional construction. 32.00 stations of optional reconstruction. 13.44 stations of abandonment. See Road Plan for construction, reconstruction, and abandonment specifications. Purchaser shall not block the E-2000 road unless authority is granted in writing by the Contract Administrator. Rock for this proposal may come from the State's Vantage Quarry and Vantage Quarry Stockpile located in Section 22, Township 16 North, Range 04 West, W.M. The Purchaser may remove no more than 346 cubic yards of 1 1/2 inch minus crushed rock at no cost from the Vantage Quarry Stockpile. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage determined by GPS traverse. See Pre-Cruise and Cruise Narratives.
*Unit #1: Gross acres: 73 Acres deducted for existing reserve tree clumps: 3
Net Acres: 70
*Unit #2: Gross acres: 36 Acres deducted for existing reserve tree clumps: 1
Net Acres: 35
*Unit #3: Gross acres: 47 Acres deducted for existing reserve tree clumps: 1
Net Acres: 46
Right-of-way harvest acres: 2

*ACRES OF LEAVE TREES TO BE SELECTED AND MARKED BY THE PURCHASER WERE NOT DEDUCTED FROM UNITS #1, #2, AND #3. An estimated volume for reserve trees to be selected and marked by the Purchaser has been deducted from the total volume above.

FEES: \$76,980.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.



TIMBER NOTICE OF SALE

SPECIAL REMARKS: The Purchaser shall select, mark, and leave a total of 362 reserve trees within Unit #1. A total of 222 reserve trees already marked by the State within Unit #1 shall remain on site after the Purchaser has completed operations.

The Purchaser shall select, mark, and leave a total of 117 reserve trees within Unit #2. A total of 187 reserve trees already marked by the State within Unit #2 shall remain on site after the Purchaser has completed operations.

The Purchaser shall select, mark, and leave a total of 312 reserve trees within Unit #3. A total of 64 reserve trees already marked by the State within Unit #3 shall remain on site after the Purchaser has completed operations.

See Schedule Z for specific Reserve Tree Requirements.

This sale may contain pole quality timber.

TIMBER SALE MAP





WASHINGTON STATE DEPARTMENT OF
Natural Resources

SALE NAME: POLYESTER PLAID
AGREEMENT NO.: 76379
TRUST(S): Agricultural School, Common School and Idemity, Forest Board Repayment

REGION: Pacific Cascade
COUNTY(S): Grays Harbor

Township 16 North, Range 04 West, W.M.



Trust:	03, 04, 42
Volume:	5810 Mbf.
U#1:	Traversed Acres: 73 Acres of Leave Trees: 3 Net Acres: 70
U#2:	Traversed Acres: 36 Acres of Leave Trees: 1 Net Acres: 35
U#3:	Traversed Acres: 47 Acres of Leave Trees: 1 Net Acres: 46
R/W HARVEST:	2 ACRES
Elev.:	422-1107 feet
SCALE:	1" = 1000'

Drawn By: hal

Date: August 11, 2004



TIMBER NOTICE OF SALE

SALE NAME: GOLDEN GOAT

AGREEMENT NO: 30-074816

AUCTION: January 25, 2005 starting at 10:00 a.m., **COUNTY:** Jefferson
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 11 miles southeast of Chimacum, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by management lines, timber sale boundary tags, and special management unit boundary tags, and all timber marked with red paint in the wetland management zone (WMZ), except blue painted leave trees or leave tree clumps marked with Leave Tree Area tags on part(s) of Sections 33 all in Township 28 North, Range 1 West, W.M., containing 100 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19.4	6	1,861				67		1,128	563	103	
Red alder	12.6		430						30	127	273	
Red cedar	12.6		43							21	22	
Maple	13		36								36	
Hemlock	8.9		15							7	8	
Sale Total			2,385									

MINIMUM BID: \$667,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: February 28, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$66,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground and/or cable methods. No rubber tired skidders will be allowed. Ground method operations will not be permitted from November 1 to the end of February, unless authorized in writing by the Contract Administrator. Falling and Yarding will not be permitted from February 15 to May 15 unless authorized in writing by the Contract Administrator, this restriction is for that portion of the sale area south and east of the 12+59 landing on the C-900 due to Heron restrictions. See Clause H-140 (7) for further restriction details.

ROADS: 6.66 stations of required construction. 12.59 stations of required reconstruction. 17.65 stations of optional construction. Rock haul, construction, reconstruction and pre-haul maintenance will not be allowed from November 1 through April 30, unless granted in writing by the Contract Administrator. There is 2.7 miles of required pre-haul maintenance - see road plan for details. Designated maintenance on any roads used and not covered by purchaser maintenance. Purchaser maintenance on the T-1640, T-1642, C-900 and all newly constructed roads within the sale area.

ACREAGE DETERMINATION

CRUISE METHOD: This sale was 100% ground traversed and unit closure was 1:255. The area east of the C-900 Road was cruised using a variable plot sample with a BAF of 33.61F on a 330 x 248 foot grid. The area west of the C-900 Road was cruised using a variable plot sample with a BAF of 40.00F on a 330 x 248 foot grid.



FEES: Purchaser must enter into a Road Use Permit with William and Joan Ewbank at a cost of \$500.00, and with Pope Resources at a cost of \$13,800.00. \$31,601.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: This sale is located behind a locked gate. Contact the Olympic Region's Dispatch Center at 360-374-6131, to obtain a AA-1 key. This sale has an extreme hazard abatement requirement along a portion of the northwest boundary.

TIMBER SALE MAP

SALE NAME: GOLDEN GOAT
 AGREEMENT NO: 30-074816
 TRUST(S): Forest Board Transfer/Common School

REGION: Olympic
 COUNTY(S): Jefferson



Legend		
~~~~~	Sale Boundary Tags	* Water Type Break
~~~~~	Special Management Unit Boundary	3 Water Type
X—X	Management Line	► Streams
====	Existing Road	⌋ Forested Wetland
=====	Required Construction	▲ Leave Tree Areas
=====	Required Reconstruction	◆ Structures
=====	Pre-Haul Maintenance	
-----	Optional Construction	
////	Cable	
////	Shovel	
	Ground (Partial Cut)	
.....	RMZ/WMZ	
×	5 Take Trees in WMZ	
◆	Survey Monuments	



TIMBER NOTICE OF SALE

SALE NAME: SPARROW

AGREEMENT NO: 30-076004

AUCTION: January 25, 2005 starting at 10:00 a.m., **COUNTY:** Kitsap
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 15 miles northwest of Gorst.

**PRODUCTS SOLD
AND SALE AREA:**

All timber bounded by white timber sale boundary tags, except those trees painted with blue paint in Units #1 and #2; all timber bounded by white timber sale boundary tags, property line with yellow flagging and the GM-4 Road, except those trees marked with blue paint in Unit #3; all timber bounded by white timber sale boundary tags and the GM-41 Road, except those trees painted with blue paint in Unit #4; all timber bounded by orange right of way tags between Units #2 and #3 on part(s) of Sections 3, 4 and 10 all in Township 24 North, Range 1 West, Sections 33 all in Township 25 North, Range 1 West, W.M., containing 108 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	13.4	10	1,851				15		604	937	295	
Hemlock	11.5		212						22	90	100	
Red alder	12.9		80						5	7	68	
Maple	13.9		23							5	18	
White pine	13.2		17							13	4	
Red cedar	14.3		6							4	2	
Sale Total			2,189									

MINIMUM BID: \$692,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2005 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$69,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Harvest Methods are required as follows: rubber or tracked skidder in Units #1 and #4, shovel in Unit #2 and shovel and cable in Unit #3. Shovel logging shall be done in accordance with the Shovel Logging specifications in Schedule A which is part of the contract. Falling and yarding in Unit #1 and the hauling of forest products from Unit #1 will not be permitted from 5 p.m. to 7 a.m., nor at all on weekends or state recognized holidays.

ROADS: 38.48 stations of optional construction. 77.45 stations of required pre-haul maintenance. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions. In addition, the operation of road equipment will not be permitted weekdays from 5 p.m. to 7 a.m., nor at all on weekends or state recognized holidays on the BB-13, BB-14 Roads and Spur 1. Purchaser Maintenance on the GM-3, GM-4, GM-41, GM-6, BB-1 and BB-13 roads and all constructed roads.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined for all units by traversing boundaries with GPS. All units were cruised using a variable plot sample with a BAF of 33.61 on a 330x250 foot grid.

FEES: \$29,000.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS:

TIMBER SALE MAP

SALE NAME: SPARROW
 AGREEMENT NO: 30-076004
 TRUST(S): FOREST BOARD TRANSFER

REGION: SOUTH PUGET SOUND
 COUNTY(S): KITSAP


TOWNSHIP 24 & 25 NORTH, RANGE 1 WEST, W.M.



LEGEND

- ~~~~~ White Timber Sale Boundary Tags
- ~~~~~ Orange Right of Way Boundary Tags
- ~~~~~ Property line marked with yellow flagging
- [Hatched Box] Cable
- [Hatched Box] Shovel
- [Hatched Box] Rubber or Tracked Skidder
- [Dotted Box] RMZ
- [Double Line] Existing Road
- [Single Line] Required Pre-haul Maintenance
- [Dashed Line] Optional Construction
- ◆ Survey Monument
- ⊥ Wetlands
- ⊗ Rock Pit
- [3] Water Type
- Streams

VICINITY MAP Not to Scale





TIMBER NOTICE OF SALE

SALE NAME: WAHKIACUS THINNING

AGREEMENT NO: 30-076130

AUCTION: January 25, 2005 starting at 10:00 a.m.,
Southeast Region Office, Ellensburg, WA

COUNTY: Klickitat

SALE LOCATION: Sale located approximately 21 miles northeast of Lyle

**PRODUCTS SOLD
AND SALE AREA:**

All live timber on Unit #1, Unit #2, Unit #3, Unit #4 and Unit #5 NOT marked with orange paint bounded by white timber sale boundary tags except for timber bounded by blue Special Management tags on part(s) of Sections 36 all in Township 5 North, Range 13 East, W.M., containing 394 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg Ring DBH Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade									
					1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	11.4	1,781	12,784	\$27.60						72	1,474	236		
Species	Avg Ring DBH Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade									
					#1	#2	#3	#4	#5	#6				
Ponderosa pine	9.9	104	525	\$27.60			104							
Sale Total		1,885	13,309											

MINIMUM BID: \$27.6/ton (est. value \$367,000.00)

BID METHOD: Sealed Bids

PERFORMANCE

SECURITY: \$73,400.00

SALE TYPE: Tonnage Scale

EXPIRATION DATE: October 31, 2006

ALLOCATION: Export Restricted

BIDDABLE SPECIES: Bidding to be allowed on all species combined.

BID DEPOSIT: \$36,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Rubber tired skidder or tractor no larger than a D-5 cat or equivalent. Falling and Yarding will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator in order to protect the soil from compaction and the water quality from degradation due to wet weather conditions.

ROADS: 3.30 stations of required construction. 4.90 stations of required reconstruction. 25.80 stations of required abandonment. Prospective purchasers should review the road plan in detail. Rock may be obtained at no charge from an existing pit on State land in the NW 1/4 NE 1/4 Section 23, Township 5 North, Range 13 East. Road construction will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions. The hauling of forest products will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Acres were determined using a GPS.

FEES: \$24,980.00 is due on day of sale. \$1.27 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Units #2, #3, #4 and #5 are regeneration cuts. No trees tagged with/or within the Special Management tags are to be cut. Purchaser must submit a written Extreme Hazard Abatement plan, to be approved by the Contract Administrator, for that portion of the sale within 100 feet on both sides of the Wahkiacus county road and within 500' of residences as shown on the timber sale map. Harvest operations are restricted during the breeding season for Western Gray Squirrels. See Clause H-140 of the contract for more details and other special requirements. There are 30' Equipment Limitation Zones on all Type 5 streams. The streambeds are identified by yellow and florescent pink flagging. Adjacent to the county road for 100 feet on both sides the leave trees are marked on the backside of the tree opposite to the road.


TIMBER SALE MAP

SALE NAME: **Wahkiacus Thinning**
 AGREEMENT NO.: **76130**
 GRANT: **Common School**

REGION: **Southeast**
 COUNTY: **Klickitat**



Township 05 North, Range 13 East, W.M.



- | | | | |
|--|-------------------------------------|--|--|
| | Sale Boundary | | Required Abandonment |
| | Stream - labeled with water type | | Required Construction |
| | Equipment Limitation Zone - 30 feet | | Required Reconstruction |
| | County Road | | Fence |
| | Existing Road | | Squirrel Nest Site bounded by Special Management Zone tags |

Elevation Range 2047 to 2253 feet.


TIMBER SALE MAP

SALE NAME: *Wahkiacus Thinning*
 AGREEMENT NO.: 76130
 GRANT: *Common School*

REGION: Southeast
 COUNTY: Klickitat



Township 05 North, Range 13 East, W.M.



- | | | | |
|--|-------------------------------------|--|--|
| | Sale Boundary | | Required Abandonment |
| | Stream - labeled with water type | | Required Construction |
| | Equipment Limitation Zone - 30 feet | | Required Reconstruction |
| | County Road | | Fence |
| | Existing Road | | Squirrel Nest Site bounded by Special Management Zone tags |

Elevation Range 2047 to 2253 feet.

VICINITY MAP


Sale Name: Wahkiacus Thinning

Region: Southeast

Agreement Number: 76130

County(s): Klickitat

Trust(s): Common School





TIMBER NOTICE OF SALE

SALE NAME: PUMA

AGREEMENT NO: 30-076008

AUCTION: January 25, 2005 starting at 10:00 a.m., **COUNTY:** Mason
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 9 miles northwest of Tahuya.

PRODUCTS SOLD AND SALE AREA: All timber bounded by white timber sale boundary tags and property line marked with yellow flagging, except those trees marked with blue paint in Unit #1; all timber bounded by white timber sale boundary tags except those trees marked with blue paint in Unit #2; all timber bounded by orange right of way tags on part(s) of Sections 8 and 17 all in Township 22 North, Range 3 West, W.M., containing 117 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	13.2	10	2,008				32		684	1,057	235		
Hemlock	12.4		68						17	31	20		
White pine	7.6		14									14	
Red cedar	14.1		12							7	5		
Red alder	10.6		5									5	
Sale Total			2,107										

MINIMUM BID: \$646,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2005 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$64,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based equipment. If Purchaser elects to shovel log, shovel logging shall be in accordance with the attached Schedule A, which is part of this contract. Yarding may be restricted during wet weather conditions if excessive rutting occurs in the opinion of the Contract Administrator.

ROADS: 11.70 stations of required construction. 39.76 stations of optional construction. 39.76 stations of abandonment, if built. Purchaser maintenance on the Cougar road south of the Cougar gate, Puma Road, Panther Road and Spurs 1-3. Designated maintenance on all other roads used. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by traversing boundaries using GPS. Units were cruised using variable plot sampling with a BAF of 33.61 on a 330x275 foot grid.

FEES: \$27,918.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Purchaser shall provide three signs that read "Caution Truck Traffic" to post during operations. Abandonment includes grass seeding and fertilizing per the road plan.

TIMBER SALE MAP

SALE NAME: PUMA
 AGREEMENT NO: 30-076008
 TRUST(S): FOREST BOARD TRANSFER

REGION: SOUTH PUGET SOUND
 COUNTY(S): MASON

TOWNSHIP 22 NORTH, RANGE 3 WEST, W.M.




LEGEND

- ~~~~~ White Timber Sale Boundary Tags
- ~~~~~ Orange Right of Way Boundary Tags
- ~~~~~ Property line: marked with yellow flagging
- Sale Area
- RMZ/WMZ
- Existing Road
- ==== Required Construction
- Optional Construction
- Streams
- Wetlands
- Rock Pit
- Water Type
- ◆ Survey Corner

Drawn By: A. Stuart
 Date: August 10, 2004

VICINITY MAP Not to Scale



TIMBER NOTICE OF SALE

SALE NAME: ROCKY RACCOON

AGREEMENT NO: 30-076040

AUCTION: January 24, 2005 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 13 miles north of Arlington

**PRODUCTS SOLD
AND SALE AREA:**

All timber, except trees marked with a ring of blue paint, cedar snags, and in Unit #2 the dead and down cedar trees, logs and stumps, bounded as follows: by white timber sale boundary tags, yellow leave tree area tags, and the BR-ML Road in Unit #1; by white timber sale boundary tags, yellow leave tree area tags, the BR-ML Road, and logged areas in Unit #2; by white timber sale boundary tags, yellow leave tree area tags, and logged areas in Unit #3; all timber bounded by orange right of way boundary tags including dead and down cedar on part(s) of Sections 18 all in Township 33 North, Range 6 East, Sections 13 and 14 all in Township 33 North, Range 5 East, W.M., containing 160 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19	7	3,566				318		2,067	984	197	
Hemlock	15	8	1,457						721	593	143	
Red alder	14		944						231	329	384	
Red cedar	16		847							717	130	
Cottonwood	27		57					52	4		1	
Maple	13		47							33	14	
Birch	16		9							9		
Sale Total			6,927									

MINIMUM BID: \$2,332,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$233,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less except as noted in H-140. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (this pertains to falling and yarding with ground-based equipment only) to reduce soil damage and erosion.

ROADS: 61.56 stations of required construction. 51.67 stations of optional construction. 51.67 stations of new road to be abandoned if built. Development of an existing hardrock source (Rocky Raccoon Hardrock Pit, BR-2402-01) at station 6+50 of the BR-2402 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 622 cubic yards of rip rap and approximately 12,580 cubic yards of 3-inch-minus ballast. This rock is available at no cost on State land in Section 14, Township 33 North, Range 5 East, W.M. Road construction will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator, also the hauling of rock will not be permitted during this time period, to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 168.3 acres gross. 8.6 acres deducted for leave tree areas. 159.7 acres net. Cruised using variable plot method. Expansion factor used is 54.45. Sighting height is 4.5 feet. Grid size plot spacing is 400 x 240 feet for Units #1, 2, and 3, and 300 feet apart for right of way. Plot ratio cruise count is 1:1 in Units #1, 2 and 3; all in right of way. 27 plots were taken in Unit #1, 24 plots taken in Unit #2, 14 plots taken in Unit #3, and 3 plots taken in right of way, for a total of 68 plots.

FEES: \$91,782.75 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: (1) Recommended timing restriction for nesting wildlife near the type 2 water north of the proposed BR-2401 road. Proposed timing to voluntarily restrict rock pit blasting,


TIMBER NOTICE OF SALE

road building, and harvest activities in the vicinity of this local area only is between March 1 through May 30. (2) There is an existing ORV bridge on the BR-02 road in the location of the proposed log stringer bridge installation. The ORV bridge will need to be removed intact, set aside, and reinstalled after harvest activities as part of this sale.

TIMBER SALE MAP

SALE NAME: Rocky Raccoon
AGREEMENT NO: 30-76040
TRUST(S): Forest Board Transfer (01)

REGION: Northwest
COUNTY(S): Skagit
Elevation: 900-1800



The Legend


- Roads**
 - Existing Road
 - Required Construction
 - Optional Construction
 - Public Road
- Streams**
 - Type 1-5
 - RMZ
 - Water Type
- Units**
 - Sale Boundary Tags
 - RMZ Boundary Tags
 - Logged Area Boundary
- Symbols**
 - Marked Trees
 - Rock Pit
 - Landing
 - Water Type Break
 - Gate
 - Survey Corner
 - Trails
 - Sale Area

Drawn By: K. Egtvedt
 Date: March 22, 2004
 Scale: 1" = 1000'
 500 0 500 Feet

TIMBER SALE MAP

SALE NAME: Rocky Raccoon
 AGREEMENT NO: 30-76040
 TRUST(S): 01

REGION: Northwest
 COUNTY(S): Skagit



Drawn By: K. Egtvedt
 Date: March 23, 2004



TIMBER NOTICE OF SALE

SALE NAME: ALTERED ATOM

AGREEMENT NO: 30-076496

AUCTION: January 24, 2005 starting at 10:00 a.m.,
Northwest Region Office, Sedro Woolley, WA

COUNTY: Snohomish

SALE LOCATION: Sale located approximately 4 miles southeast of Granite Falls

**PRODUCTS SOLD
AND SALE AREA:**

All timber, except trees marked with blue paint, dead and down cedar trees, logs, stumps and snags, and other blow down trees, logs and snags that do not have needles or small limbs, bounded as follows: by white timber sale boundary tags, yellow leave tree area tags, young stands, and the MZ-ML Road in Unit #1; white timber sale boundary tags, yellow leave tree area tags, logged areas, young stands, and the MZ-ML Road in Unit #2; all timber bounded by orange right of way boundary tags on part(s) of Sections 2 and 3 all in Township 29 North, Range 7 East, Sections 34 all in Township 30 North, Range 7 East, W.M., containing 72 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	20	8	2,806			104	569			1,302	713	118	
Hemlock	12	8	397							101	195	101	
Red alder	14		265							87	86	92	
Red cedar	13		200								157	43	
Cottonwood	29		22					20	2				
Sale Total			3,690										

MINIMUM BID: \$1,347,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$134,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel and Cable. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (this pertains to falling and yarding with ground-based equipment only) to reduce soil damage and erosion.

ROADS: 12.92 stations of required construction. 65.00 stations of required reconstruction. 29.13 stations of optional construction. 3.15 stations of optional reconstruction. 6.15 stations of existing road to be abandoned. 29.13 stations of new road to be abandoned if built. Development of an existing hardrock source (MZ-21 Hardrock Pit) at station 111+50 of the MZ-ML Road will involve drilling, shooting, and processing rock to generate approximately 55 cubic yards of rip rap and approximately 5,025 cubic yards of 3-inch-minus ballast. This rock is available at no cost on State land in Section 3, Township 29 North, Range 7 East, W.M. Road construction, road reconstruction, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 75.73 acres gross. 3.31 acres deducted for leave tree areas. 72.42 acres net. Cruised using variable plot method. Expansion factor used is 54.45. Sighting height is 4.5 feet. Grid size plot spacing is 320 x 200 feet for Units #1 and 2. Plot ratio cruise count is 1:1 in Units #1 and 2. 25 plots were taken in Unit #1, and 21 plots taken in Unit #2, for a total of 46 plots.



FEES: \$48,892.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Intermediate supports may be necessary to obtain adequate deflection for cable-yarded portions of the sale on Unit # 1.

TIMBER SALE MAP

SALE NAME: Altered Atom
AGREEMENT NO: 30-076496
TRUST(S): 06, 01

REGION: Northwest
COUNTY(S): Snohomish
ELEVATION: 1,000'-1350'



Legend

Units

- ~~~~~ Sale Boundary Tags
- ~~~~~ Management Unit Boundary Tags
- ~~~~~ R/W Boundary Tags
- Logged Area Boundary

Logging Methods

- ////// Cable
- ////// Shovel

Roads

- ===== Existing Road
- ===== Required Construction
- ===== Required Reconstruction
- Optional Construction
- Optional Reconstruction

Streams

- Type 1-5
- Wetland Boundary
- RMZ / WMZ

Survey Monuments


- ◆ Survey Monument

Symbols

- * Water Type Break
- ⊗ Rock Pit
- ♣ Tagged Leave Tree Areas
- Landing
- ⊕ Wetlands
- ③ Water Type

VICINITY MAP

NOT TO SCALE



Drawn By: Aaron Fox
 Date: August 4th, 2004



TIMBER NOTICE OF SALE

SALE NAME: ZEBRA POLE

AGREEMENT NO: 30-074597

AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Thurston
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 10 miles northwest of Littlerock, WA.

PRODUCTS SOLD AND SALE AREA: Approximately 1,505 Douglas-fir pole trees selected and marked with orange paint by the Purchaser as designated in Schedules A and B, bounded by Timber Sale Boundary tags, red ribbon indicating timber type change, and the C-9200 Road; all timber bounded by Right-of-Way Boundary tags; all timber within skid trails, cable corridors, and landings as approved by the Contract Administrator, located on part(s) of Section 3 in Township 17 North, Range 3 West, Section 34 in Township 18 North, Range 3 West W.M., containing 90 acres, more or less.

NON-POLE VOLUMES AND QUALITY:

Species	Avg Ring DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	17.9		787	\$323.00			7	79		478	203	20	
Hemlock	15.9		22	\$323.00						9	9	4	
Maple	14.5		6	\$140.00							3	3	
Red cedar	15.8		3	\$323.00							3		
Red alder	14.6		1	\$140.00									1
Non-Pole Total			819										

POLE DIAMETER DISTRIBUTION:

Species	MBF	\$/MBF	DGL/PCS	DGL/PCS	DGL/PCS	DGL/PCS	DGL/PCS
Douglas fir	635	\$609.45	12/10	13/95	14/135	15/155	16/120
			17/135	18/140	19/130	20/120	21/105
			22/125	23/95	24/55	25/50	26/35
Pole Total	635						
Sale Total	1,454						

LUMP SUM MINIMUM BID: \$650,000 (poles only) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum--Poles
MBF Scale—NON-POLE WOOD

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas-fir poles only

BID DEPOSIT: \$65,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Tracked equipment and cable systems. Tracked equipment use will not be permitted from October 1 to November 30 and March 2 to May 1 unless authorized by the Contract Administrator. Tracked equipment use will not be permitted from December 1 to March 1. Yarding corridors and landings must be marked and pre-approved by the Contract Administrator. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Intermediate supports may be required to prevent soil rutting off the Spur 1 Road. The maximum log length hauled from the sale area shall not exceed 125 feet unless otherwise approved in writing by the Contract Administrator.

ROADS: 38.41 stations of required construction. See Road Plan for construction specifications. Rock for this sale may be obtained from the State's Timberline Quarry located in Section 4, Township 17 North, Range 03 West, W.M. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator on the C-9200 Road.



TIMBER NOTICE OF SALE

ACREAGE DETERMINATION

CRUISE METHOD: Acreage determined by photo traverse. See Pre-Cruise Narrative and Pole Summary. Approximately five acres of the 90 total acres shall be harvested as right-of-way.

FEES: \$19,270.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: This contract is designed to sell approximately 1,505 poles as a lump sum sale. All other non-pole volume must be paid for on a scale basis per prices set in this contract. Sawlog volume includes but is not limited to, wood removed from merchantable top or long butt portions of pole trees, yarding corridors, skid trails, landings, and road right-of-way, except poles within right-of-way limits.

All merchantable sawlog volume manufactured from a pole tree will be paid for at sawlog prices. Any long butts greater than 12 feet in length will be required to be removed and paid for at sawlog prices.

At the Purchaser's request the Contract Administrator will scale a pole that has broken as the result of Purchaser's falling or yarding operations, so long as no pole product can be manufactured from the pieces and the broken pieces of the pole have not been yarded from the site of the breakage. Broken pieces of pole so described, that are documented by the Contract Administrator, will have the corresponding volume deducted from scaled sawlog volume and will not be billed to the Purchaser. Felled pole trees with defect(s) that prevent any pole products being produced shall be subject to the same process.

Volume includes an estimated 540 Mbf. to be removed as skid trails and yarding corridors. Approximately 61 poles are located within the right-of-way.

The Purchaser must select poles as required in Schedule A and poles must be marked with orange paint as described in Schedule B.


See vicinity map for gate locations. Gate keys may be obtained from the region office.



TIMBER SALE MAP

SALE NAME: ZEBRA POLE REGION: Pacific Cascade
 AGREEMENT NO.: 74597 COUNTY(S): Thurston
 TRUST(S): Forest Board Repayment, State Forest Board Purchase,
 State Forest Board Transfer


TOWNSHIP 18 NORTH, RANGE 03 WEST, W.M.
 TOWNSHIP 17 NORTH, RANGE 03 WEST, W.M.



VICINITY MAP

NOT TO SCALE.

ALL DISTANCES IN MILES.



TIMBER NOTICE OF SALE
SALE NAME: QUICK GETAWAY
AGREEMENT NO: 30-076113
AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Thurston
 Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 7 miles west of Littlerock, WA

**PRODUCTS SOLD
 AND SALE AREA:**

All timber bounded by Timber Sale Boundary tags, E-7000 road, reproduction, Cedar Creek Correction Camp, and E-7110 road in Unit #1; bounded by E-3000 road and reproduction in Unit #2; except trees bounded by Leave Tree Area tags, reserve trees marked with blue paint, a minimum of 224 trees within Unit #1 to be selected and marked by the Purchaser as designated in Schedule Z, snags, down wood existing two years prior to the day of sale, and existing stumps; all timber bounded by Right-of-Way Boundary tags; on part(s) of Sections 11, 12, 13 and 14 all in Township 16 North, Range 4 West, W.M., containing 92 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	25.4	7	4,702				95		3,775	783	49	
Red cedar	18		42						19	15	8	
Red alder	19		13						10		3	
Sale Total			4,757									

MINIMUM BID: \$1,637,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$163,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel equipment and cable systems. Lead end suspension required on all cable settings. Landing locations are restricted to those shown on road plan maps unless otherwise authorized in writing by the Contract Administrator. No harvest operations will be permitted, including cable lines, under or over utility lines. Utility lines will only be crossed at locations approved by the Contract Administrator. Any damage to utilities as a result of operations must be repaired and paid for by the Purchaser. Approximately 30% of this sale may be harvested using cable systems and 70% may be harvested using ground-based systems. Shovel yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

Purchaser shall provide a written Extreme Hazard Abatement plan that meets the requirements of WAC 332-24 prior to the beginning of logging operations within Unit #1. The plan must be acceptable to the Contract Administrator.

ROADS: 80.44 stations of required construction. 14.60 stations of required reconstruction. 4.50 stations of optional construction. 22.40 stations of temporary optional construction (abandoned if constructed). 0.50 stations of pre-haul maintenance. 1.35 stations of endhaul. 68.04 stations of abandonment. Road construction will not be permitted from September 30 to April 1 unless authorized in writing by the Contract Administrator. See Road Plan for pre-haul maintenance, construction, reconstruction, and abandonment specifications. Two existing gates will be removed during road abandonment. One gate will be installed at station 0+50 of the Spur 1A road. Purchaser shall not block the E-Line, E-3000, E-5100, E-7000, E-7110, Spur Y, and Spur Z roads unless authority is granted in writing by the Contract Administrator. Rock for this proposal is available from the State's Vantage Quarry and Vantage Quarry Stockpile located in Section 22, Township 16 North, Range 04 West, W.M. The Purchaser may remove no more than 5,516 cubic yards of four inch minus rock and 3,422 cubic yards of three inch minus crushed rock at no cost from the Vantage Quarry Stockpile. Additional rock may be purchased at a cost of \$8.00 per cubic yard as approved by the Contract Administrator.

ACREAGE DETERMINATION
CRUISE METHOD: Unit #1 acreage determined by GPS traverse. Unit #2 acreage determined by photo traverse. See Pre-cruise and Cruise Narratives.

 Unit #1*: Gross acres: 42 Acres deducted for existing reserve trees: 1.1
 Net Acres: 40.9

Unit #2: Gross acres: 52 Acres deducted for existing reserve trees: 4.6

TIMBER NOTICE OF SALE

Net Acres: 47.4
Right-of-Way harvest: 3.3 acres

*ACRES OF RESERVE TREES TO BE SELECTED AND MARKED BY THE PURCHASER WERE NOT DEDUCTED FROM UNIT #1. An estimated volume for reserve trees to be selected and marked by the Purchaser has been deducted from the total volume above.

FEES: \$63,030.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: The Purchaser shall prepare a reserve tree plan for Unit #1 to be approved by the Contract Administrator. In addition, the Purchaser shall select, mark, and leave a minimum of 224 reserve trees within Unit #1. Of the 224 reserve trees, 54 trees must be within the largest diameter class, with a minimum diameter at breast height (dbh) of 30 inches; and 170 trees must be greater than 14 inches dbh and have an average dbh of 22 inches. See Schedule Z for additional information.

Within Unit #1, a total of 112 reserve trees already marked by the State shall remain on site after the Purchaser has completed operations.

Reserve trees within Unit #2 are bounded by Leave Tree Area tags.

See timber sale map and vicinity map for gate locations. Gate keys may be obtained from the region office in Castle Rock, WA.



TIMBER SALE MAP


SALE NAME: QUICK GETAWAY REGION: Pacific Cascade
 AGREEMENT NO.: 76113 COUNTY(S): Thurston
 TRUST(S): Forest Board Repayment, State Forest Board Purchase

Township 16 North, Range 04 West, W.M.

LEGEND

- ~ ~ ~ TIMBER SALE BOUNDARY TAGS
- TIMBER SALE BOUNDARY--NO TAGS
- ~ · ~ RIGHT-OF-WAY BOUNDARY TAGS
- ==== REQUIRED ROAD CONSTRUCTION
- - - - OPTIONAL ROAD CONSTRUCTION
- ===== REQUIRED ROAD RECONSTRUCTION
- ◻ RIPARIAN MANAGEMENT ZONE
- ▨ SALE AREA
- ⊗ ROCK SOURCE
- GATE
- STREAM
- ⊠ STREAM TYPE
- ===== EXISTING ROAD

SEE ROAD PLAN FOR ROAD PRE-HAUL MAINTENANCE, CONSTRUCTION, RECONSTRUCTION, AND ABANDONMENT SPECIFICATIONS.




Trust: 02, 42
Volume: 4757 Mbf.
U#1: Traversed Acres: 42
Acres of Leave Trees: 1.1
Net Acres: 40.9
U#2: Traversed Acres: 52
Acres of Leave Trees: 4.6
Net Acres: 47.4
RW HARVEST: 3.3 ACRES
Elev.: 670-1047 feet
SCALE: 1" = 1000'



TIMBER SALE VICINITY MAP

SALE NAME: QUICK GETAWAY REGION: Pacific Cascade
 AGREEMENT NO.: 76113 COUNTY(S): Thurston
 TRUST(S): Forest Board Repayment, State Forest Board Purchase





TIMBER NOTICE OF SALE

SALE NAME: VANILLA BEAN

AGREEMENT NO: 30-076344

AUCTION: January 27, 2005 starting at 10:00 a.m., **COUNTY:** Thurston
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 11 miles northwest of Olympia, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber, bounded by Timber Sale Boundary tags and B-6000 road in Unit #1; bounded by Timber Sale Boundary tags in Units #2, #4, and #5; bounded by Timber Sale Boundary tags and S-1000 road in Unit #3 and Unit #6; bounded by Timber Sale Boundary tags and reproduction in Unit #7 and Unit #9; bounded by Timber Sale Boundary tags and powerline right-of-way in Unit #8; except trees bounded by Leave Tree Area tags, trees marked with blue paint, reserve trees to be selected and marked by the Purchaser as designated in Schedule Z, snags, down wood existing two years prior to the day of sale, and existing stumps; and all timber bounded by Right-of-Way Boundary tags on part(s) of Sections 3, 4, 5, 8 and 18 all in Township 18 North, Range 3 West, Sections 24 all in Township 18 North, Range 4 West, W.M., containing 246 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	17.8	8	5,405				96		3,056	2,036	217	
Red alder	14		1,328					115	350	435	428	
Maple	16.3		496						155	223	118	
Hemlock	19.1		154						104	50		
Red cedar	14.8		76							54	22	
Grand fir	11		12							8	4	
Sale Total			7,471									

MINIMUM BID: \$2,519,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2006 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$251,900.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel equipment and cable systems. Lead end suspension required on all cable settings. Landings shall be marked by Purchaser and approved by the Contract Administrator prior to construction. The use of unmuffled compression brakes ("jake brakes") will not be permitted on site. Approximately 35% of this sale may be harvested using cable systems and 65% may be harvested using ground-based systems. Shovel yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 99.54 stations of required construction. 26.08 stations of abandonment. 10.06 stations of deactivation. Rock for this proposal may come from the State's Five Forks Quarry located in Section 22, T18N, R04W, W.M., State 8 Quarry located in Section 16, T18N, R03W, W.M., and Spur 8 (15+69 to 17+11) Section 5, T18N, R03W, W.M. No more than 493 cubic yards of 4 inch minus rock may be obtained from the State's Five Forks Quarry Stockpile located in Section 22, T18N, R04W, W.M. at no charge. Additional rock may be purchased at a cost of \$8.00 per cubic yard subject to written approval of the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage determined by laser traverse on Unit #2, Unit #4, Unit #5, and Unit #6. Error of closure: Unit #2=1:160; Unit #4=1:107; Unit #5=1:186; Unit #6=1:162. Acreage determined by GPS on Unit #1, Unit #3, Unit #7, Unit #8, and Unit #9. See Pre-Cruise and Cruise Narratives.

*ACRES OF RESERVE TREES TO BE SELECTED AND MARKED BY THE PURCHASER AND TREES ALREADY MARKED BY THE STATE WERE NOT DEDUCTED FROM THE UNITS. An estimated volume for reserve trees to be selected and marked by the Purchaser has been deducted from the total volume above.

TIMBER NOTICE OF SALE

FEES: \$98,990.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Gate keys may be obtained from the region office. See vicinity map for gate locations.

The Purchaser shall select, mark, and leave a total of 100 reserve trees within Unit #1.

Reserve trees within Unit #2 are bounded by Leave Tree Area tags.

The Purchaser shall select, mark, and leave a total of 50 reserve trees within Unit #3. A total of 50 reserve trees already marked by the State within Unit #3 shall remain on site after the Purchaser has completed operations.

The Purchaser shall select, mark, and leave a total of 150 reserve trees within Unit #4.

The Purchaser shall select, mark, and leave a total of 48 reserve trees within Unit #5.

The Purchaser shall select, mark, and leave a total of 108 reserve trees within Unit #6. A total of 126 reserve trees already marked by the State within Unit #6 shall remain on site after the Purchaser has completed operations.

Reserve trees within Unit #7 are bounded by Leave Tree Area tags and/or marked with blue paint.

The Purchaser shall select, mark, and leave a total of 496 reserve trees within Unit #8.

The Purchaser shall select, mark, and leave a total of 279 reserve trees within Unit #9. A total of 279 reserve trees already marked by the State within Unit #9 shall remain on site after the Purchaser has completed operations.

See Schedule Z for specific Reserve Tree Requirements.

Any timber harvest within two tree lengths of the BPA right-of-way will require at least one-week advance notice to the BPA Line Maintenance office in Olympia.

Gas line will only be crossed at locations approved by the Contract Administrator.




TIMBER SALE MAP

SALE NAME: VANILLA BEAN
AGREEMENT NO.: 76344

REGION: Pacific Cascade
COUNTY(S): Thurston


TRUST(S): Capitol Grant, Charitable/Educational/ Penal & Reformatory Institute, Common School and Indemnity, Forest Board Repayment, State Forest Board Transfer

Township 18 North, Range 03 West, W.M.



Trust: 01, 03, 06, 07, 42
Volume: 7471 Mbf.
UNIT #1: 10 ACRES
UNIT #2: 29 ACRES
UNIT #3: 10 ACRES
UNIT #4: 15 ACRES
UNIT #5: 6 ACRES
UNIT #6: 25 ACRES
UNIT #7: 25 ACRES
UNIT #8: 62 ACRES
UNIT #9: 62 ACRES
RIGHT-OF-WAY: 2.5 ACRES
Elev.: 170-1139 feet
SCALE: 1" = 1000'

Township 18 North, Range 04 West, W.M.



LEGEND

- TIMBER SALE BOUNDARY TAGS
- TIMBER SALE BOUNDARY—NO TAGS
- RIGHT-OF-WAY BOUNDARY TAGS
- SALE AREA
- REQUIRED ROAD CONSTRUCTION
- EXISTING ROAD
- STATE HIGHWAY
- GATE
- ROCK SOURCE
- STREAM
- STREAM TYPE
- POWERLINE
- WETLAND
- PROPERTY LINE
- GAS LINE
- RIPARIAN MANAGEMENT ZONE/ WETLAND MANAGEMENT ZONE




TIMBER SALE MAP

SALE NAME: VANILLA BEAN REGION: Pacific Cascade
 AGREEMENT NO.: 76344 COUNTY(S): Thurston
 TRUST(S): Capitol Grant, Charitable/Educational/Penal & Reformatory Institute, Common School and Idem nity, Forest Board Repeym ent, State Forest Board Transfer

Township 18 North, Range 03 West, W.M.

Township 18 North, Range 03 West, W.M.



Trust: 01, 03, 06, 07, 42
 Volume: 7471 Mb. f.
 UNIT #1: 10 ACRES
 UNIT #2: 29 ACRES
 UNIT #3: 10 ACRES
 UNIT #4: 15 ACRES
 UNIT #5: 6 ACRES
 UNIT #6: 25 ACRES
 UNIT #7: 25 ACRES
 UNIT #8: 62 ACRES
 UNIT #9: 62 ACRES
 RIGHT-OF-WAY: 2.5 ACRES
 Elev.: 170-1139 feet
 SCALE: 1" = 1000'

LEGEND

- TIMBER SALE BOUNDARY TAGS
- TIMBER SALE BOUNDARY—NO TAGS
- RIGHT-OF-WAY BOUNDARY TAGS
- SALE AREA
- REQUIRED ROAD CONSTRUCTION
- EXISTING ROAD
- STATE HIGHWAY
- GATE
- ROCK SOURCE
- STREAM
- STREAM TYPE
- POWERLINE
- WETLAND
- PROPERTY LINE
- GAS LINE
- RIPIARIAN MANAGEMENT ZONE/ WETLAND MANAGEMENT ZONE


SEE ROAD PLAN FOR ROAD CONSTRUCTION, ABANDONMENT, AND DEACTIVATION SPECIFICATIONS.



VICINITY MAP

SALE NAME: VANILLA BEAN
AGREEMENT NO.: 76344
TRUST(S): Capitol Grant, Charitable/Educational/Penal & Reformatory Institute, Common School and Idemnity, Forest Board Repayment, State Forest Board Transfer

REGION: Pacific Cascade
COUNTY(S): Thurston





TIMBER NOTICE OF SALE

SALE NAME: NANEUM HIGH

AGREEMENT NO: 30-072999

AUCTION: January 25, 2005 starting at 10:00 a.m.,
Southeast Region Office, Ellensburg, WA

COUNTY: Kittitas

SALE LOCATION: Sale located approximately 16 miles northeast of Ellensburg

**PRODUCTS SOLD
AND SALE AREA:**

All live standing timber Douglas fir and white fir NOT marked with orange paint, all live standing ponderosa pine and larch greater than 31 inches in circumference measured outside the bark twelve inches above the ground NOT marked with orange paint bounded by white timber sale area boundary tags on Unit #1; all live standing timber NOT marked with orange paint bounded by white timber sale area boundary tags on Unit #2; and in addition, all timber bounded by orange right of way boundary tags on part(s) of Sections 34 all in Township 20 North, Range 19 East, W.M., containing 115 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade					
				#1	#2	#3	#4	#5	#6
Douglas fir	13.6	12	680	150	145	385			
Ponderosa pine	14.8		536			140	370	26	
Larch	11.2		16				16		
White fir	10.3		9			2	7		
Sale Total			1,241						

MINIMUM BID: \$239,000.00

BID METHOD: Sealed Bids

PERFORMANCE

SECURITY: \$47,800.00

SALE TYPE: Lump Sum

EXPIRATION DATE: May 31, 2006

ALLOCATION: Export Restricted

BID DEPOSIT: \$23,900.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Rubber tired skidder or tractor no larger than a D-6 cat or equivalent and cable yarding equipment. Falling and Yarding will not be permitted from November 1 to May 1 unless authorized in writing by the Contract Administrator in order to protect the soil from compaction and the water quality from degradation due to wet weather conditions.

ROADS: 4.35 stations of required construction. 57.10 stations of required pre-haul maintenance. 4.35 stations of required abandonment. Prospective purchasers should review the road plan in detail. Road construction will not be permitted from November 1 to May 1 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions. The hauling of forest products will not be permitted from November 1 to May 1 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions.

ACREAGE DETERMINATION

CRUISE METHOD: Sale acres were determined using GPS. Cruise was done using a variable plot method and cruised in 16' log grades.

FEES: \$16,445.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: There is a combination lock on the gate. Contact Region office for information on how to access the locked gate. Sale has nice pine and fir. Need snowmobiles to access during winter months. This is a marked leave tree sale. Unit #1 also has an 8 inch diameter limit on the ponderosa pine and larch to protect established regeneration. No existing down woody material may be removed.

TIMBER SALE MAP

SALE NAME: NANEUM HIGH
 AGREEMENT NO.: 72999
 GRANT: Indemnity

REGION: Southeast
 COUNTY: Kittitas

TOWNSHIP 20 NORTH RANGE 19 EAST, W.M.



SCALE 1:12,000

SCALE IN MILES

~~~~~	SALE AREA BOUNDARY
-----	EXISTING ROAD
-----	REQUIRED CONSTRUCTION
-----	REQUIRED PRE-HAUL MAINTENANCE
←	STREAM W/ WATER TYPE
.....	RIPARIAN MANAGEMENT ZONE (Bounded by blue SMZ tags and blue flagging)
////	CABLE YARDING
●	SPRING




September 16, 2004

# TIMBER SALE VICINITY MAP

SALE NAME: NANEUM HIGH  
AGREEMENT NO.: 72999  
GRANT: Indemnity

REGION: Southeast  
COUNTY: Kittitas



**TIMBER NOTICE OF SALE**

**SALE NAME:** APPLE POLE

**AGREEMENT NO:** 30-071261

**AUCTION:** January 25, 2005 starting at 10:00 a.m.,  
Southeast Region Office, Ellensburg, WA

**COUNTY:** Klickitat

**SALE LOCATION:** Sale located approximately 15 miles north of White Salmon

**PRODUCTS SOLD**

**AND SALE AREA:** All timber marked with an orange painted double ring at DBH (474 poles) on Unit #1; all timber on Unit #2 to be marked by Purchaser (875 poles) and that is further described in Schedule A of the contract; all bounded by white timber sale area boundary tags on part(s) of Sections 4, 6 and 7 all in Township 4 North, Range 11 East, W.M., containing 215 acres, more or less.

**NON-POLE VOLUMES AND QUALITY:**

Species	Avg Ring DBH Count	Total MBF	MBF by Grade									
			1P	2P	3P	SM	1S	2S	3S	4S	UT	
Non-Pole Total		None										

**POLE DIAMETER DISTRIBUTION:**

Species	MBF	\$/MBF	DGL/PCS	DGL/PCS	DGL/PCS	DGL/PCS	DGL/PCS
Douglas fir	193	\$482.00	12/435	14/573	16/293	18/48	
Pole Total	193						
Sale Total	193						

**MINIMUM BID:** \$93,000.00

**BID METHOD:** Sealed Bids

**PERFORMANCE**

**SECURITY:** \$18,600.00

**SALE TYPE:** Lump Sum

**EXPIRATION DATE:** October 31, 2005

**ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$9,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Rubber tired skidder or tractor no larger than a D-6 cat or equivalent. Falling and Yarding will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator in order to protect the soil from compaction and the water quality from degradation due to wet weather conditions.

**ROADS:** All roads are existing. The hauling of forest products will not be permitted from November 1 to April 1 unless authorized in writing by the Contract Administrator in order to protect the road surface and subgrade from damage due to wet weather conditions.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres were determined using a GPS system. Cruise was a 100% cruise on Unit #1 and a 20% strip cruise on Unit #2.

**FEES:** On the day of sale, Purchaser must provide a check in the amount of \$500.00 made payable to Longview Fibre Co. for a road use permit. \$2,560.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


**SPECIAL REMARKS:** Good quality distribution poles. Unit #1 has 474 marked poles that are marked with an orange painted double ring at DBH. Unit #2 poles are to be selected and marked by the Purchaser -- 875 poles (see Schedule A of the contract for details). There is a locked gate with a combination lock on it. Contact the region office for the combination.

# TIMBER SALE MAP


Sale Name: Apple Pole  
 Agreement Number: 71261  
 Trust(s): State Forest Board - Transfer

Region: Southeast  
 County(s): Klickitat

## Township 04 North, Range 11 East, W.M.




Scale 1:12,000



- ~~~~~ Timber Sale Boundary
- County Road
- Existing Road
- Equipment Limitation Zone
- Power Lines
- * Fence
- Stream
- Voids
- Gate

Elevation Range: 1360 - 2320




VICINITY MAP

# TIMBER SALE MAP


**Sale Name:** Apple Pole  
**Agreement Number:** 71261  
**Trust(s):** State Forest Board - Transfer

**Region:** Southeast  
**County(s):** Klickitat

## Township 04 North, Range 11 East, W.M.



Scale 1:12,000



- ~~~~~ Timber Sale Boundary
- Existing Road
- >— Stream
- XXXXXX Equipment Limitation Zone
- XXXXXX Riparian Management Zone
- Voids