

Washington State Department of Natural Resources (DNR)

Bidder's/Purchaser's Inspection of Sale Area and Forest Products

Acreage estimates and volume estimates contained within each timber notice of sale and each timber sale contract are made only for administrative and identification purposes. Except as expressly provided by the timber sale contract, the purchaser shall be responsible for paying the entire purchase price, even if the actual acreage or timber volume varies from the estimated quantity or volume shown.

All prospective bidders have the opportunity and are expected to inspect the sale area and the forest products located thereon. Bidders shall not rely on any representations by the State including, but not limited to, acreage estimates, volume estimates, appraisal or pre-bid documentation. The successful bidder/purchaser will further warrant that they have entered the timber sale contract without any reliance upon the DNR's volume estimates, acreage estimates, appraisals, pre-bid documentation, or any other representation by the DNR.

Any timber sale contract arising out of these public auctions will require the successful purchaser to warrant that they are entering the timber sale contract based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold.

Exclusion and Disclaimer of Warranties

The PARTIES AGREE that the IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, and ALL OTHER WARRANTIES EXPRESS OR IMPLIED, ARE EXCLUDED from this transaction, and shall not apply to the goods sold. For example, THE FOLLOWING SPECIFIC MATTERS ARE NOT WARRANTED, and are EXCLUDED from this transaction:

a. ***The merchantability of the forest products.*** The use of the term “merchantable” in any document is not intended to vary the foregoing.

b. ***The condition of the forest products.*** All forest products will be conveyed “AS IS.”

c. ***The acreage contained within any sale area.*** Any acreage descriptions appearing in the timber notices of sale, timber sale contract, timber sale map or other documents are estimates only, provided solely for administrative and identification purposes.

d. ***The volume, quality, or grade of the forest products.*** The descriptions of the forest products to be conveyed are estimates only, made solely for administrative and identification purposes.

e. ***The correctness of any soil or surface conditions, presale construction appraisals, investigations, and all other pre-bid documents prepared by or for the State.*** These documents have been prepared for the State’s appraisal purposes only.

f. ***That the sale area is free from threatened or endangered species, or their habitat.*** The State is not responsible for any interferences with forestry operations that result from the presence of any threatened or endangered species, or the presence of their habitat, within the sale area.

g. ***That the forestry operations to be performed under this contract will be free from regulatory actions by governmental agencies.*** The State is not responsible for actions to enforce regulatory laws, such as the Washington Forest Practices Act (Chapter 76.09 RCW), taken by the Department of Natural Resources or any other agency that may affect the operability of these timber sales.

h. Items contained in any other documents prepared for or by the State.

Please also see timber sale contract clause G-060 for further information.

BIDDING PROCEDURES FOR TIMBER AUCTIONS

The general requirements that follow are a part of all Timber Notices of Sale to be auctioned by the Department of Natural Resources (DNR).

General Information

The State reserves the right to waive minor irregularities and the right to reject any or all bids.

A. This book contains the timber notices of sale and maps for each timber sale scheduled to be auctioned. More specific information can be obtained by contacting the appropriate region office at the number listed on the back cover of this book.

B. The timber notice of sale is a summary of sale information. For more specific information, interested parties are encouraged to view the Appraisal Packets on the DNR Internet Site @ www.dnr.wa.gov, this will take you directly to the Product Sales Section. The Appraisal Packets contain **DRAFT** copies of the timber notice of sale, map, contract, road plan, cruise data, precruise and cruise narrative, Forest Practices Application (FPA), Hydraulics Project Approval (HPA).

C. The sale preview packets may be obtained at no charge for individual sales by visiting the appropriate region office.

D. Timber sale contracts contain extensive terms and conditions that will be binding upon successful high bidders. Each bidder should carefully review all terms contained in the appropriate **DRAFT** timber sale contract prior to bidding on a sale, and should review the final contract prior to signing. **DRAFT** timber sale contracts are contained in the preview and presales packets and are available upon request at the respective region office.

E. Sales advertised in this book have not been approved by the Board of Natural Resources and are subject to the Board's approval before they will be sold. The Board meets and approves sales approximately six weeks prior to auction. All sales are subject to confirmation by the DNR under RCW 79.15.120.

F. The State does not guarantee the accuracy of any information contained herein pertaining to particular sales. Therefore, all prospective purchasers are expected to make their own independent inspections and appraisals prior to bidding.

G. If any conflict exists between the information in the Timber Notice of Sale, timber sale map, sale preview packets and that in the timber sale contract, the signed contract will prevail.

H. Timber sales are subject to the Washington State Forest Excise Tax (RCW Chapter 84.33).

I. Within 30 days of sale confirmation, the apparent high bidder will provide to the State the Performance Security specified on each Notice of Sale.

J. Each DNR region office has information about sales offered in that region. For further information, contact the respective DNR region office. Region office addresses and telephone numbers appear on the back cover of this booklet.

K. The purchaser assumes the responsibility for any costs associated with extra maintenance or repair levied by a county for any county road used by the purchaser.

BIDDING PROCEDURES FOR TIMBER AUCTIONS (Continued)

Bidding Process

- A. All timber will be auctioned using the sealed bid method.
- B. Bids submitted on day of auction must be in the bid box at the specified auction location before 10:00 a.m. The respective DNR region office must receive mailed bids by 4:30 p.m., on the last business day before the auction. Bidders assume all risk for the method of delivery.
- C. The DNR has the right to reject bid forms that are completed incorrectly. *All bid forms must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. Revised documents are not permissible.* Bidding instructions are on the back of the Sealed Bid Form. A bid deposit must be included in the sealed bid envelope unless using a Timber Sale Statewide Bid Bond.
- D. All bids must include the completed Sealed Bid Form and bid deposit.
- E. Bids will be opened in each respective region in the order in which sales appear in the Public Auction Sale of Timber book (alphabetically by county and by agreement number).
- F. If a tie bid occurs, the names of the tie bidders will be placed in a hat and the successful bidder will be determined by a drawing.
- G. The apparent high bidder on a particular sale will have the option of withdrawing additional sealed bids submitted for any remaining sales to be auctioned. The apparent high bidder must exercise this option within two minutes after the apparent high bidder is announced.

Auction Time and Location

Auctions will start at 10:00 a.m. and close at 4:00 p.m. on the date and at the location specified in each Timber Notice of Sale.

Bid Deposits

- A. Required bid deposits are listed on each Timber Notice of Sale.
- B. Bid deposits must be in the form of cash, certified check, cashiers' check, money order or bid bond.
- C. Bid bonds may be either a Timber Sale Statewide Bid Bond or a Timber Sale Per Sale Bid Bond.
- D. All bid deposits shall be submitted by the person or entity submitting the bid and made payable to the Department of Natural Resources. **Third party deposits will not be accepted.**

Timber Sale Per Sale Bid Bonds

- A. The Per Sale Bid Bond shall guarantee payment of the bid deposit **within ten days of auction.**
- B. The balance between the bid bond and the Initial Deposit payment is due by 4:30 p.m., **on the day of auction.**
- C. Additional forms and instructions for a Per sale Bid Bond are available at any DNR region office.

Timber Sale Statewide Bid Bond

- A. Statewide Bid Bonds shall guarantee payment of the Initial Deposit on any statewide timber sale while the bond is in effect.
- B. The Statewide Bid Bond must be received by the Department of Natural Resources, Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction date. The bond shall be in the amount of \$150,000.00.
- C. The bidder must supply a list of persons authorized to bid using the bond. Bid bonds are subject to approval by the Department of Natural Resources.
- D. Successful bidders using a Statewide Bid Bond must pay the total Initial Deposit payment (10 percent of the total bid price) **by 4:30 p.m. on the day of auction.**
- E. A Statewide Bid Bond cannot be used to secure the Initial Deposit payment due the day of auction.
- F. Additional forms and instructions for a statewide bid bond are available at any DNR region office.

Payments

The initial deposit for a sale is 10% of the total bid value as submitted by the apparent high bidder (25% if the bidder is a defaulter as defined under WAC 332-140-300) and never less than \$5,000.00 for lump sum sales. For Lump Sum sales appraised at less than \$5,000.00, the entire bid value is due on day of auction.

- a. Apparent high bidders using cash, certified check, cashiers' check or money order as a bid deposit must pay the total Initial Deposit amount by 4:30 p.m. on auction day.
- b. Apparent high bidders using a Timber Sale Per Sale Bid Bond as a bid deposit must pay the difference between the bid deposit and the total initial deposit by 4:30 p.m., on the day of auction. The bid bond amount must be replaced with a certified check, cashier's check, bank draft, cash, money order, or wire transfer within ten days of the auction.
- c. Apparent high bidders using a Timber Sale Statewide Bid Bond must pay the entire Initial Deposit amount by 4:30 p.m. on the day of auction.

Fees due on the day of sale must be paid by 4:30 p.m.

All payments must be in the form of a certified check, cashier's check, bank draft, cash, money order or wire transfer.

Eligibility to Bid

In order to bid on State timber sales you must be:

- 18 years of age (or have a co-signer who meets the eligibility requirements),
- Licensed to do business in the State of Washington,
- Eligible to bid on Export Restricted timber, and
- Capable of meeting all contract obligations.

Authorized Representatives

Companies may only use authorized representatives or company officers to bid on State sales, sign State documents or sign checks. A list of authorized representatives and their specific authorities must be submitted in writing to the Department of Natural Resources Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction. A company owner or officer must sign this submittal.

State of Washington
Department of Natural Resources
Doug Sutherland, Commissioner of Public Lands

SEALED BID FORM

Sale Name _____ Agreement Number _____

_____ hereby submits the following bid for timber.
(Print full, legal company name)

(Street address, City, State, Zip Code)

(Phone Number)

Lump Sum Bid (Not Including Fees) \$ _____ **For Total Sale**

Weight Scale Sale Bid (Not Including Fees) \$ _____ / **Ton**

Scribner Scale Sale Bid (Not Including Fees) \$ _____ / **MBF**

BID DEPOSIT

Bid Deposit Amount: \$ _____

Bid Deposit Type:

- Cash, certified check, cashiers check, or money order
 Per Sale Bid Bond
 Statewide Bid Bond, Number _____

The Successful Bidder agrees to furnish, **within 30 days of confirmation date**, Performance Security acceptable to the State in the amount specified on the Notice of Sale. Performance Security must guarantee performance of all provisions of the contract and payment of any damages caused by operations under the contract or resulting from the successful bidders noncompliance with any rule or law.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as an offer to purchaser forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based upon their own judgments of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, appraisals, pre-bid documentation, or any other representation by the Washington State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid) Date _____

(Print name and title of Authorized Representative submitting this bid)

Note: all sales are subject to confirmation by the Commissioner of Public Lands (Refer to RCW 79.15.120)

Instructions For Completing Sealed Bid Form

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks on bid form must be completed including the bid bond number if the bidder is relying upon a bid bond for bid deposit.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box before 10:00 a.m. on the day of auction at the location specified in the Timber Notice of Sale.
 - B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be on the bid bond and timber sale contract. The bid form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Mailed Bids

- A. Bids that are mailed are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED". The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The Sealed Bid Form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope.
 - B. Bids that are mailed will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery. The DNR assumes no responsibility for any delays caused by any delivery service.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Initial Deposit:

Lump Sum Sales - Initial Deposit must equal 10% of the total bid submitted.
(25% if the bidder is a defaulter as defined under WAC 332-140-300)

Weight Scale Sales - Initial Deposit must equal 10% of the bid per ton multiplied by the total sale estimated tonnage. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

Scribner MBF Scale Sales - Initial Deposit must equal 10% of the bid per MBF multiplied by the total sale MBF. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

State of Washington
Department of Natural resources
Doug Sutherland, Commissioner of Public Lands

STATEWIDE BID BOND

Bond Number _____

_____ of _____
(Principal's Name) (City, State)

hereinafter called PRINCIPAL, and _____ hereinafter called SURETY,

a corporation organized under the laws of the State of _____, and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$150,000.00 Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, a venue shall be proper only in Thurston County Superior Court.

Signed, sealed and dated this ____ day of _____, _____.
(month) (year)

This statewide bid bond may be used for bidding between the following dates:

Starting: _____

Ending: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is an apparent high bidder, PRINCIPAL shall before 4:30 p.m., on day of sale, pay to the STATE the amount of the initial deposit in the form of a certified check, cashier's check, bank draft, cash or money order, then this agreement shall be void for the sale on which the payment is made; otherwise, it will remain in force.

SURETY will make payment to the STATE within ten days after demand by the STATE if the PRINCIPAL shall fail to make timely payment as described above.

The SURETY may cancel this bond by sending a written notice to the STATE, not less than forty-five days before a cancellation date; liability shall terminate as to acts or omissions of the PRINCIPAL that occur after the cancellation date.

The PRINCIPAL and the SURETY executed this bond on the date first mentioned.

Principal: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip Code

Surety: (Local Office of Authorized agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

Above

State & Zip

Notary or Company Seal in Space

Instructions For Completing Timber Sale Statewide Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Statewide Bid Bond may be used as bid guaranty on more than one timber sale.
- C. The full legal name and business address of the PRINCIPAL must be inserted where indicated and must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and title must be shown.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as SURETY, it may leave this signature block blank.
- F. This form must be received by the Department of Natural Resources, Product Sales and Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction.
- G. The PRINCIPAL must submit a list of authorized bidders with the Statewide Bid Bond Form.
- H. **The State reserves the right to reject *incomplete* or *incorrect* bid bond forms, making such forms unacceptable as bid guaranty.**

**State of Washington
 Department of Natural Resources
 Doug Sutherland, Commissioner Of Public Lands**

Timber Sale Per Sale Bid Bond

Bond Number _____

_____ of _____, hereinafter called PRINCIPAL, and _____, hereinafter called SURETY, a corporation organized under the laws of the State of _____ and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$ _____ Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, venue shall be proper only in Thurston County Superior Court.

Signed, sealed, and dated this _____ day of _____, 20____.

BID IDENTIFICATION:

SALES NAME(S)	REQUIRED DEPOSIT	AGREEMENT NUMBER(S)

DATE OF BID: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is the high bidder on the sale(s) identified above and, within ten (10) days of the day of sale, transmits cash, certified check, cashier=s check, bank draft or money order, payable to the STATE, in the amount of the bid guaranty required by the terms of the Notice of Sale, *then* this obligation shall be void; *otherwise*, it shall remain in force.

SURETY will make payment to the STATE within ten (10) days after demand by the STATE whenever the PRINCIPAL shall fail to make timely payment as described above.

IN WITNESS WHEREOF: the PRINCIPAL and the SURETY have caused this bond to be executed on the date first mentioned.

SECOND OFFICER:

Signature: _____

Name: _____

Title: _____

PRINCIPAL: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

SURETY: (Local Office of Authorized Agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

City: _____

State & Zip: _____

SURETY: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

NOTARY OR COMPANY SEAL IN THE SPACE ABOVE

Instructions For Completing Timber Sale PerSale (s) Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Timber Sale Per Sale Bid Bond may be used as bid guaranty on more than one timber sale auction held the same date at the same location.
- C. The full legal name and business address of the PRINCIPAL must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person, the name typed or printed, and title shown. If PRINCIPAL is a corporation, a second officer must sign in the space to the left of the signature of the officer executing for the PRINCIPAL.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown. If this person is not an officer of the corporation, evidence of authority must be submitted.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as Surety, it may leave the local office signature block blank.
- F. The date of the bid bond must not be later than the auction date.
- G. **The State reserves the right to reject *incomplete or incorrect* bid bond forms, making such forms unacceptable as guaranty.**

**STATE OF WASHINGTON
DEPARTMENT OF NATURAL RESOURCES
Doug Sutherland, Commissioner of Public Lands**

LOG SORT SEALED BID FORM

Sale Name _____ Agreement Number _____ Date _____.

_____ hereby submits the following bid for delivered logs.
(Print Company Name)

_____ Telephone Number _____
(Print Name Authorized Company Representative) (Contact for bid result notification)

(Street Address)

(City, State and Zip)

Agreement Number	Sort Number	Delivered Logs Bid Amount (fill in one only)	
		\$ / MBF	\$ / ton

Bid Deposit Amount \$ _____

Bid Deposit Type: Cash, Certified Check, Cashiers Check, or Money Order
 Per Sale Bid Bond
 Statewide Bid Bond, Number _____

The successful bidder agrees to furnish payment security acceptable to the State in the amount as described in clause P-041 of the Purchaser's contract prior to log delivery and at a date to be determined by the State.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as offer to purchase forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, estimates, appraisals, pre-bid documentation, or any other representation by the State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid)

(Date of Signature)

(Print name and title of Authorized Representative submitting this bid)

NOTES: A separate bid form is required for each log sort bid and must be delivered in a separate envelope. Photocopies of this bid form may be used. Each photocopy must have original signatures. All sales are subject to confirmation by the Commissioner of Public Lands as per RCW 79.15.100.

SUPPLEMENTAL INFORMATION FORM

Sale Name _____

Agreement Number _____

Sort # _____

Provide the following information for log manufacturing specifications, delivery locations, weigh and scaling locations.

Log Manufacturing Specifications:

Enter one or more preferred log lengths for each log length range below.	Bidder's Preferred Log Lengths (Log lengths exclude trim)		
	1	2	3
12 ft. through 18 ft.			
20 ft. through 28 ft.			
30 ft. through 40 ft.			

Minimum log trim: _____ inches.

Additional Log or Pole Length Information:

To provide additional preferred cutting information you may attach a separate sheet or "Cutting card".

Log Delivery Specifications:

Designate the point of delivery and address (must be a street address)

(Location Name)

(Street Address)

(City, State and Zip)

Weigh and Scaling Facilities:

Designate the state approved Weigh and Scaling facility closest to the point of delivery.

State approved Weighing and scaling facility address:

(Location Name)

(Street Address)

(City, State and Zip)

Final contract award is contingent upon the State's haul cost analysis. Actual haul route may vary and is subject to change at the State's discretion.

Instructions for Completing the Log Sort Sealed Bid and Supplemental Information Forms.

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form(s) provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks including Agreement Number, Sort Number, Bid amount (per mbf or ton as appropriate for the sort), Bid deposit amount and type. Signatures and date on bid form must be completed including the bid bond number if bidder is relying upon a bid bond for bid deposit.

Bids may not be accepted if the Supplemental Information Form is not included with the approved Log Sort Sealed Bid form or is incomplete.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box or auction envelope before 10:00 a.m. on the day of sale at the location specified in the notice of sale.
- B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same as the name on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope, please.
- C. Sealed bid envelopes must contain the following:
 1. A completed Log Sort Sealed Bid form;
 2. A completed Supplemental Information form; and
 3. A bid deposit

Mailed Bids

- A. Mail-in bid envelopes are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED." The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope, please.
- B. Mail-in or otherwise delivered bids will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery they chose. The DNR assumes no responsibility for any delays caused by any delivery service.
- C. Sealed bid envelopes must contain the following:
 1. A completed Log Sort Sealed Bid form;
 2. A completed Supplemental Information form; and
 3. A bid deposit

Summary Report of All Sales for the Month of March 2007

Board Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	79362	LAMBASTED	5,324	\$810,000.00
Clark Skamania	Pacific Cascade	79893	CLOUDS REST THIN & CC	2,566	\$384,000.00
Lewis	Pacific Cascade	79478	OLD RED	5,125	\$1,501,000.00
Lincoln	Northeast	79656	LILIENTHAL FI SORTS	2,973	\$918,864.00
Mason	South Puget	78568	SPLIT SADDLE	6,226	\$2,083,000.00
Pacific	Pacific Cascade	79711	RADAR LOVE	3,074	\$500,000.00
Pacific	Pacific Cascade	79717	JAMMED RADAR THINNING	2,718	\$294,000.00
Skagit	Northwest	79377	THE SKIPPER	6,231	\$2,578,000.00
Skagit	Northwest	79426	RED FAWN	5,006	\$1,788,000.00
Snohomish	Northwest	79338	ENGLISH BREAKFAST	4,015	\$1,337,000.00
Snohomish	Northwest	79378	CRITTER	6,898	\$2,692,000.00
Whatcom	Northwest	78597	FORKED HORN	2,907	\$806,000.00
Total				50,028	\$15,691,864.00

Region Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	79280	THUNDERDOME THINNING	1,924	\$114,000.00
Clallam	Olympic	80570	SEKIU CLUB CEDAR SALVAGE	72	\$9,000.00
Total				1,996	\$123,000.00

TIMBER NOTICE OF SALE

SALE NAME: LAMBASTED

AGREEMENT NO: 30-079362

AUCTION: March 27, 2007 starting at 10:00 a.m., **COUNTY:** Clallam
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 3 miles west of Clallam Bay, WA for Unit #1 and 10 miles west of Clallam Bay, WA for Unit #2

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags and a logged area, except leave trees marked with blue paint or bounded by leave tree area boundary tags in Unit #1; all timber bounded by timber sale boundary tags, the P-3000 road, logged areas, and the P-1000 Road, except leave trees marked with blue paint or bounded by leave tree area boundary tags in Unit #2 on part(s) of Sections 14 all in Township 31 North, Range 13 West, Sections 30 and 31 all in Township 32 North, Range 12 West, W.M., containing 154 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	14.6	6	3,887						1,250	2,314	323		
Douglas fir	17.8	6	572						237	295	40		
Spruce	14.8	6	481						250	190	41		
White fir	16.4		217						33	174	10		
Red cedar	12.9		88							52	36		
Red alder	12		79							39	40		
Sale Total			5,324										

MINIMUM BID: \$810,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$81,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and shovel methods. No rubber tired skidders or cats will be allowed and no shovel operations on slopes over 30%. Shovel yarding will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ROADS: 33.71 stations of optional construction. 229.59 stations of required pre-haul maintenance, which includes 190.08 stations of resurfacing of the P-1000 Road. Purchaser maintenance on the P-1300 and P-1380 roads, all new construction and the pre-haul maintenance on the P-1000 road and the 18+96 spur. Designated maintenance on all other roads used. There is a 1/2 acre of stripping required in the Box Car Pit. Rock haul, pre-haul maintenance and road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd. Sale units were cruised using a variable plot sample with a BAF of 46.94F on a 330 x 330 foot grid for Unit #1 and a BAF of 71.11F on a 330 x 330 foot grid for Unit #2.




FEES: \$70,543.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There is a locked gate on the Mary Clark Pit. Contact the Olympic Region Dispatch Center at 360-374-6131, to obtain a AA-1 key.

TIMBER SALE MAP

SALE NAME: LAMBASTED
 AGREEMENT NO: 30-079362
 TRUST(S): Forest Board Transfer

REGION: Olympic
 COUNTY(S): Clallam



See Road Plan for Pre-Haul Maintenance Locations and Requirements




Drawn By: M. Helms
 Date: December 1, 2006
 Scale: 1" = 1000'

Elevation: 1-2000'
Map 1 of 2

TIMBER SALE MAP

SALE NAME: LAMBASTED
AGREEMENT NO: 30-079362
TRUST(S): Forest Board Transfer

REGION: Olympic
COUNTY(S): Clallam



TIMBER NOTICE OF SALE

SALE NAME: CLOUDS REST THIN & CC

AGREEMENT NO: 30-079893

AUCTION: March 29, 2007 starting at 10:00 a.m., **COUNTY:** Clark, Skamania
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 3 miles east of Cougar, WA

PRODUCTS SOLD AND SALE AREA:

All timber as described in Schedule A, except leave trees tagged out with leave tree area boundary tags, snags and down timber greater than 30 inches Diameter at Breast Height, bounded by the following: timber sale boundary tags and the 10, S-6000 and S-6100 roads in Units #1 and #2; timber sale boundary tags and the S-6300 road in Unit #3; all timber, except conifers, trees tagged out with leave tree area boundary tags and/or leave trees marked with blue paint, snags and down timber greater than 30 inches Diameter at Breast Height, bounded by timber sale boundary tags, reprod and the S-5000 road in Units #4 and #5; all timber bounded by right-of-way boundary tags on part(s) of Sections 1, 2, 10, 11, 14, 15, 21, 22, 25 and 26 all in Township 6 North, Range 4 East, Sections 35 and 36 all in Township 7 North, Range 4 East, W.M., containing 227 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade									
					1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	13	9	1,810	\$166.06						233	1,285	292		
Hemlock	16.7	10	376	\$80.23						194	163	19		
Maple	15		242	\$15.51					12	67	65	98		
Red alder	16.2		127	\$381.57					13	22	68	24		
Silver fir	14.3		12	\$68.68								12		
Sale Total			2,567											

MINIMUM BID: \$167.00/MBF (est. value \$384,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY:

\$76,800.00

SALE TYPE: MBF Scale

EXPIRATION DATE: October 31, 2008

ALLOCATION: Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$38,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel and tracked harvesting equipment being restricted to slopes of 40% and less. See clause H-140 for further harvest requirements. Intermediate support will/may be required to prevent soil rutting in Unit #3 off Spur J and the S-6050 Extension road. A designated skid trail has been flagged in with orange, pink and blue flagging, in southwest portion of Unit #3. Purchaser shall post a sign, at the junction of the 10 and S-6000 roads, warning the public of logging activities and truck traffic. Falling and Yarding will not be permitted from March 1 to August 31 unless authorized in writing by the Contract Administrator for Units #1, #2, and #3.

ROADS: 66.29 stations of required construction. 19.95 stations of required reconstruction. 60.34 stations of optional construction. 14.26 stations of optional reconstruction. 697.49 stations of Required Pre-haul Maintenance. 122.88 stations of road abandonment. Rock is available at no charge from two State pits, the S-6300 Road pit in Section 1 and the S-5000 Road pit in Section 22, Township 06 North, Range 04 East, W.M. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 50% ground based and 50% cable harvesting.

FEES: \$33,999.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS: Purchaser shall comply with terms and conditions of the Cutting Line Agreement entered into between the State and Pacific Power and Light for Unit #5 dated 11-06-2006. In Units #4 and #5, purchaser shall leave all conifer where operationally feasible.

TIMBER SALE MAP

SALE NAME: CLOUDS REST THINNING & CC
AGREEMENT NO: 30-079893
TRUST(S): State Forest Board Transfer (01), State Forest Board Purchase (02), Common School (03), &

REGION: Pacific Cascade
COUNTY(S): Clark
 Normal School (08)

Township 07 North, Range 04 East, W.M.




Drawn By: Shawn B.
 Date: January 9, 2007
 Scale: 1" = 1000'
 Elevation: 550ft. - 2,800ft.

TIMBER SALE MAP

SALE NAME: CLOUDS REST THINNING & CC
AGREEMENT NO: 30-079893
TRUST(S): State Forest Board Transfer (01), State Forest Board Purchase (02), Common School (03), &


REGION: Pacific Cascade
COUNTY(S): Clark
 Normal School (08)

Township 06 & 07 North, Range 04 East, W.M.




Legend

- Regeneration Harvest Area
- Thinning Area
- Leave Tree Area
- RMZ
- Sale Boundary Tags (White)
- Leave Tree Tags (Yellow)
- Right of Way Boundary Tags (Orange)
- Highway
- Existing Roads
- Pre-haul Maintenance
- Required Construction
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Streams
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit



Drawn By: Shawn B.
 Date: January 9, 2007
 Scale: 1" = 1000'
 Elevation: 550ft. - 2,800ft.



TIMBER NOTICE OF SALE

SALE NAME: OLD RED

AGREEMENT NO: 30-079478

AUCTION: March 29, 2007 starting at 10:00 a.m., **COUNTY:** Lewis
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 23 miles west of Chehalis, WA

PRODUCTS SOLD AND SALE AREA: All timber, except pre-existing stumps, leave trees tagged out with yellow leave tree area boundary tags and individual leave trees marked with blue paint, bounded by the following: timber sale boundary tags, reprod and the N-1000 road in Unit #1; timber sale boundary tags, and the N-8100 and N-8180 roads in Unit #2 on part(s) of Sections 18, 19 and 20 all in Township 13 North, Range 5 West, W.M., containing 160 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	20.1	8	3,024				91		2,166	668	99	
Hemlock	17.1	7	1,628						774	756	98	
Red alder	14		302						36	131	135	
Maple	13.8		162						29	24	109	
Red cedar	34		9								9	
Sale Total			5,125									

MINIMUM BID: \$1,501,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$150,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel harvesting equipment restricted to slopes of 40% and less during dry soil conditions. 400 uniformly distributed plantable spots per acre shall remain after harvest activities on all ground within the sale area that is on slopes of 40% or less. This shall be done by piling brush and slash in piles no larger than 10 feet in diameter. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. See Clause H-140 for additional harvesting specifications. Yarding and hauling restrictions will be followed from March 31 through August 31 for a portion of Unit #2 bound out with Special Management Unit boundary tags that face away from the SMU. Falling and Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator for all other portions of the sale.

ROADS: 2.10 stations of required reconstruction. 8.83 stations of optional construction. 14.30 stations of Required Pre-haul Maintenance. 8.83 stations of abandonment, of optional road construction. Rock is available at no charge from the State's Mullinex Pit in Section 19, Township 13 North, Range 05 West, W.M. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1, without Contract Administrators approval. Road reconstruction and pre-haul maintenance will be restricted from September 30 to August 31 on the N-8100 and N-8180 roads.

ACREAGE DETERMINATION

CRUISE METHOD: Unit acres were determined by GPS and the sale was cruised using a variable plot method. Harvesting activities are estimated to be 50% cable and 50% ground based harvesting.

FEES: \$50,000.00 is due on day of sale. \$12.37 per MBF is due upon removal. These are in addition to the bid price.





SPECIAL REMARKS: See vicinity map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: OLD RED
 AGREEMENT NO: 30-079478
 TRUST(S): State Forest Board Transfer (01)

REGION: Pacific Cascade
 COUNTY(S): Lewis County

Township 13 North, Range 05 West, W.M.



Drawn By: Shawn B.
 Date: January 2, 2007
 Scale: 1" = 1000'
 Elevation: 560ft. - 1,520ft.



Timber Sale Map

SALE NAME: Lilienthal FI Sorts
 AGREEMENT NO.: 30-079656
 TRUST(S): Agricultural, CEP&RI

REGION: NORTHEAST
 COUNTY: Lincoln

Township 28 North, Range 36 East, W. M.

(Map 1 of 3)




Timber Sale Map

SALE NAME: Lilienthal FI Sorts
 AGREEMENT NO.: 30-079656
 TRUST(S): CEP & RI

REGION: NORTHEAST
 COUNTY: Lincoln


Township 28 North, Range 36 East, W. M.
 (Map 2 of 3)



	Ground Skidding
	Timber Sale Boundary Tags
	Existing Road
	Required Construction
	Required Reconstruction
	Pre-Haul Maintenance
	Stream
	Section/Property Line

**Note: Road details can
 Be found in the
 Road plan in
 The timber sale
 Contract.**

Acres = Net Acres
Elevation = 2160' - 2920'




Scale: 1" = 1000'
 Drawn By: S. M.
 DATE: 09/26/2006

Timber Sale Map

SALE NAME: Lilienthal FI Sorts
 AGREEMENT NO.: 30-079656
 TRUST(S): School

REGION: NORTHEAST
 COUNTY: Lincoln


Township 27 North, Range 37 East, W. M.
 (Map 3 of 3)



Note: Road details can Be found in the Road plan in The timber sale Contract.

Acres = Net Acres

Elevation = 1620' - 2500'



Vicinity Map
 (not to scale)

	Ground Skidding
	Timber Sale Boundary Tags
	Existing Road
	Section/Property Line
	Stream

Scale: 1" = 1000'
 Drawn By: S. M.
 DATE: 09/26/2006

TIMBER NOTICE OF SALE

SALE NAME: SPLIT SADDLE

AGREEMENT NO: 30-078568

AUCTION: March 27, 2007 starting at 10:00 a.m., **COUNTY:** Mason
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 11 miles north of Hoodspport.

PRODUCTS SOLD AND SALE AREA: All timber bounded by white timber sale boundary tags, logged areas and the 1100 Road, except those trees marked with blue paint in Unit #1; all timber bounded by white timber sale boundary tags and the 1280 Road, except those trees marked with blue paint in Unit #2; all timber bounded by white timber sale boundary tags and existing rock pit in Unit #3; all timber bounded by orange right of way tags on part(s) of Sections 14, 15, 16, 21 and 28 all in Township 23 North, Range 4 West, W.M., containing 178 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	14	12	5,704				80		1,899	2,985	740		
Hemlock	11.6		366						116	151	99		
Red cedar	11.5		89							62	27		
Maple	17.6		55							19	36		
Red alder	17.3		12							9	3		
Sale Total			6,226										

MINIMUM BID: \$2,083,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$208,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Ground based equipment on slopes less than 35 percent and cable equipment on slopes greater than 35 percent. Cable yarding is required to have lateral yarding capabilities. In Unit #2, ground based yarding will be by shovel only, unless authority to use other equipment is granted in writing by the State. Shovel logging shall be in accordance with the attached Schedule A, which is part of this contract. Falling and Yarding will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator.

ROADS: 38.23 stations of required construction. 11.83 stations of optional construction. .05 stations of required pre-haul maintenance. 11.83 stations of abandonment, if constructed. Purchaser maintenance on the 1100, 1100 Ext., 1103, 1200 (at the end of the pavement), 1263, 1263 Ext., 1265, 1266, 1280, 1280 Ext., and 1300 Roads. Designated maintenance on the 1000 (until the junction at the 1300 Road), and 1200 (until the end of the pavement) Roads. Road construction will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator, nor at all on weekends or state recognized holidays, unless approved in writing by the Contract Administrator. The hauling of forest products will not be permitted from October 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by traversing boundaries with a GPS in Unit #1, traversing boundaries with hand compass and laser in Unit #2 and the rock pit, and traversing boundaries with hand compass and chain in the right of way. Unit #1 was cruised using a variable plot sample with a BAF of 40 on a 330 x 300 foot grid, Unit #2 was cruised using a variable plot sample with a BAF of 40 on a 330 x 330 foot grid and the right of way was cruised using a variable plot sample with a BAF of 40 every 1,100 feet.

FEES: \$82,495.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS: Purchaser is required to pull vine maple in ground based areas.

TIMBER SALE MAP

SALE NAME: SPLIT SADDLE
 AGREEMENT NO: 30-078568
 TRUST(S): COMMON SCHOOL & CAPITOL

REGION: SOUTH PUGET SOUND
 COUNTY(S): MASON

MAP 1 OF 2 TOWNSHIP 23 NORTH, RANGE 4 WEST, W.M.



LEGEND


- | | | | | | |
|-------|-----------------------------------|--|--|--|----------------------------|
| ~~~~~ | White Timber Sale Boundary Tags | | Wetland Management Zone | | Wetlands |
| ~~~~~ | Orange Right of Way Boundary Tags | | Sale Area | | Waste Area |
| ==== | Existing Road | | Ground based on slopes < 35%,
Cable harvest on slopes > 35% | | Water Type |
| ===== | Required Construction | | *****
Estimated 40% sale area ground based, 60% cable | | Survey Corner |
| ----- | Optional Construction | | Drawn By: A. Mainwaring
Date: October 19, 2006 | | Stream |
| | | | | | Locked Gate:
Master 786 |

TIMBER SALE MAP

SALE NAME: SPLIT SADDLE
AGREEMENT NO: 30-078768
TRUST(S): COMMON SCHOOL & CAPITOL

REGION: SOUTH PUGET SOUND
COUNTY(S): MASON

MAP 2 OF 2



TIMBER NOTICE OF SALE

SALE NAME: RADAR LOVE

AGREEMENT NO: 30-079711

AUCTION: March 29, 2007 starting at 10:00 a.m., **COUNTY:** Pacific
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 3 miles north of Naselle

PRODUCTS SOLD AND SALE AREA: All timber, except stumps, snags, pre-existing down timber existing three years prior to the day of sale, trees tagged out with yellow leave tree area boundary tags, and leave trees marked with blue paint, bounded by the following: timber sale boundary tags in Units #1 and #2; timber sale boundary tags, the H-2400 road, and powerline right-of-way in Unit #3; the D-Line and powerline right-of-way for Units #4, #5 and #6; all timber bounded by right-of-way boundary tags on part(s) of Sections 21, 27, 28 and 33 all in Township 11 North, Range 9 West, W.M., containing 95 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Hemlock	14.9	5	1,849						570	1,124	155		
Douglas fir	13.2	5	942						203	602	137		
White fir	20.4		132						89	40	3		
Red alder	11.1		115						2	26	87		
Spruce	27.3	4	34						5	6	23		
Red cedar	14.4		2							1	1		
Sale Total			3,074										

MINIMUM BID: \$500,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$50,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable harvesting equipment with shovel harvesting equipment being restricted to dry soil conditions and to slopes of 35% and less. See Schedule L for further Harvest Specifications. Shovel yarding will not be permitted from September 1 to March 31 unless authorized in writing by the Contract Administrator.

ROADS: 119.45 stations of required reconstruction. 18.07 stations of optional construction. 195.60 stations of Required Pre-haul Maintenance. 35.16 stations of road abandonment. Rock is available at no charge from the State's Schoolhouse Quarry pit located in Section 33, Township 11 North, Range 09 West, W.M. Rock may also be obtained from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by GPS for Units #3 - #6 and determined by laser range finder and hand compass with a maximum error of closure of 1:3319 for Units #1 and #2. The sale was cruised using a variable plot method. Harvesting activities are estimated to be 40% cable and 60% shovel harvesting.

FEES: \$40,730.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Intermediate support will/may be required to prevent soil rutting in Unit #3 off the H-2, H-2100, H-2200, H-2400 and H-2600 Roads. See vicinity map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: RADAR LOVE
AGREEMENT NO: 30-079711
TRUST(S): University Transferred (05) & CEP&RI (06)


REGION: Pacific Cascade
COUNTY(S): Pacific

Township 11 North, Range 09 West, W.M.




Legend

- Sale Area
- RMZ
- Sale Boundary Tags (White)
- Right of Way Boundary Tags (Orange)
- Existing Roads
- Pre-haul Maintenance
- Required Reconstruction
- Optional Construction
- Optional Reconstruction
- Required Abandonment
- Streams
- Bridge
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit
- Gate (786 Master)



Drawn By: Shawn B.
 Date: January 4, 2007
 Scale: 1" = 1000'
 Elevation: 800ft. - 1,360ft.



TIMBER NOTICE OF SALE

SALE NAME: JAMMED RADAR THINNING

AGREEMENT NO: 30-079717

AUCTION: March 29, 2007 starting at 10:00 a.m., **COUNTY:** Pacific
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 4 miles north of Naselle, WA

**PRODUCTS SOLD
AND SALE AREA:**

All timber, as described in Schedule A for Units #1 through #10, except pre-existing stumps, pre-existing down timber existing 3 years prior to the day of sale, and snags, bounded by the following: timber sale boundary tags in Unit #1, #5 and #8; timber sale boundary tags and the E-Line road in Unit #2; timber sale boundary tags and the D-Line road in Unit #3; timber sale boundary tags, the C-1300, D-3750, and D-Line roads in Unit #4; timber sale boundary tags, the C-Line, C-800 and D-Line roads in Unit #6; timber sale boundary tags, the C-Line, C-700 and C-800 roads in Unit #7; timber sale boundary tags and the C-2050 road in Unit #9; timber sale boundary tags and the C-2000 road in Unit #10 on part(s) of Sections 6, 7, 17, 18, 19 and 20 all in Township 11 North, Range 9 West, W.M., containing 284 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	10.5	4	1,268	8,408	\$24.20							1,025	243	
Hemlock	10.2	5	1,153	8,385	\$9.00							829	324	
Spruce	9.9		297	1,727	\$9.00							187	110	
Sale Total			2,718	18,520										

MINIMUM BID: \$24.2/ton (est. value \$294,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$58,800.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: August 31, 2010 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$29,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Forwarder, Cable and Track skidder. Cable harvesting equipment with possible intermediate support and tracked harvesting equipment (forwarder, tracked skidder or processor), being restricted to dry soil conditions. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Yarding will not be permitted from September 30 to March 1 unless authorized in writing by the Contract Administrator.

ROADS: 14.66 stations of required construction. 43.14 stations of required reconstruction. 34.84 stations of optional reconstruction. 107.24 stations of required pre-haul maintenance. 163.21 stations of optional pre-haul maintenance. 169.86 stations of road abandonment. Rock is available at no charge from the State's Radar Ridge Quarry Pit in Section 17, Township 11 North, Range 09 West, W.M. Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 1 to May 30 unless authorized in writing by the Contract Administrator on the following: E-500, Spur-C, C-700, C-800, C-850, C-900, C-1000, C-1100, C-1200, C-1320, C-2050, C-2055, D-3700, D-3750 and D-3900 roads.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage was determined by aerial photo dot grid count, and the sale area was cruised by using a variable plot cruise method adjusted for volume removals. Harvesting activities are estimated to be approximately 70% ground based and 30% cable harvesting.

FEES: \$36,015.00 is due on day of sale. \$1.32 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: Intermediate support may be required to prevent soil rutting in Units #1, #2, #4, #5, #6, #7, #9 and off the E-435, E-Line, E-500, C-1320, C-1200, C-1000, C-900, C-800, C-Line, and C-2020 roads. In Units #1 and #9, cut a 30 foot opening around 2 western hemlock or Sitka spruce trees per acre over 16 inches DBH. In Units #2 and #4, cut a 25 foot opening around 5 western hemlock or Sitka spruce trees per acre over 16 inches DBH. Timing restrictions for Units #3, #4, #6, and the C-Line road from station 0+00 to



TIMBER NOTICE OF SALE


station 80+00, are described as no harvest or road construction activities within the critical nesting season (April 1 to August 31) during the daily peak activity periods (one hour before official sunrise to two hours after official sunrise and one hour before official sunset to one hour after official sunset).

TIMBER SALE MAP

SALE NAME: JAMMED RADAR THINNING
AGREEMENT NO: 30-079717
TRUST(S): Common School (03) & University Transferred (05)



REGION: Pacific Cascade
COUNTY(S): Pacific

Township 11 North, Range 09 West, W.M.



Legend

- Thinning Area
- RMZ
- Sale Boundary Tags (White)
- Existing Roads
- Pre-haul Maintenance
- Required Construction
- Required Reconstruction
- Optional Reconstruction
- Old Grade / Trail
- Streams
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit




Drawn By: Shawn B.
 Date: January 4, 2007
 Scale: 1" = 1000'
 Elevation: 160ft. - 1,160ft.

TIMBER SALE MAP

SALE NAME: JAMMED RADAR THINNING
 AGREEMENT NO: 30-079717
 TRUST(S): Common School (03) & University Transferred (05)


REGION: Pacific Cascade
 COUNTY(S): Pacific

Township 11 North, Range 09 West, W.M.




Legend

- Thinning Area
- RMZ
- Sale Boundary Tags (White)
- Existing Roads
- Pre-haul Maintenance
- Required Construction
- Required Reconstruction
- Optional Reconstruction
- Old Grade / Trail
- Streams
- Water Type 1 - 5
- Monumented Corner
- Leave Trees
- Existing Rock Pit



Drawn By: Shawn B.
 Date: January 4, 2007
 Scale: 1" = 1000'
 Elevation: 160ft. - 1,160ft.



TIMBER NOTICE OF SALE

SALE NAME: THE SKIPPER

AGREEMENT NO: 30-079377

AUCTION: March 26, 2007 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 3 miles southeast of Sedro-Woolley

PRODUCTS SOLD AND SALE AREA:

All timber including trees tagged with blue special management tags in Unit 3, except trees marked with blue paint at DBH and root collar, forest products tagged out with yellow leave tree tags, bounded as follows: by white timber sale boundary tags, adjacent plantation, and property line, in Unit #1; by adjacent plantation and CM-35 Road, in Unit #2; by white timber sale boundary tags, adjacent plantation, and the CM-ML Road, in Unit #3. All timber bound by orange right of way tags. The above described products on part(s) of Sections 4 and 9 all in Township 34 North, Range 5 East, W.M., containing 93 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	20	8	4,556			102	1,109		1,811	1,361	173	
Red cedar	15		850							706	144	
Hemlock	14	8	631						192	342	97	
Red alder	19		113						59	20	34	
Cottonwood	32		66					63			3	
Maple	18		15							12	3	
Sale Total			6,231									

MINIMUM BID: \$2,578,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$257,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 26.35 stations of required construction. 46.44 stations of required reconstruction. 46.30 stations of optional construction. 54.76 stations of existing road to be abandoned. 46.30 stations of road to be abandoned if built.

Development of an existing hardrock source (MU-43 Hard Rock Pit) at milepost 4.3 of the Mundt Creek Mainline (MU-ML) Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 842 cubic yards of riprap and approximately 7,450 cubic yards of 3-inch-minus ballast rock. This rock is available at no cost on State land in Section 16, Township 34 North, Range 5 East, W.M.

Road construction, reconstruction, abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 94.5 acres gross. 2.4 acres deducted for green tree retention clumps. 92.1 acres net. Cruised using variable plot method. Expansion factor used is 62.50. Sighting height is 4.5 feet. Grid size plot spacing is 320 x 200 feet in Unit #1; 400 x 200 in Unit #2 and #3/R/W. Plot ratio cruise count is 1:1 in Units #2 and #3/R/W; cruised minor species on all plots and cruised DF on every 3rd plot in Unit #1. 26 plots were taken in Unit #1, and 7 plots taken in Unit #2, and 19 plots taken in Unit #3 for a total of 52 plots.

FEES: \$56,079.00 is due on day of sale. \$13.25 per MBF is due upon removal. These are in addition to the bid price.





TIMBER NOTICE OF SALE

SPECIAL REMARKS: Blue Special Management tags between the two leave tree areas mentioned above demarcate a yarding break. The trees below the line must be taken to the CM-ML with a shovel and not yarded up the slope. The shovel cannot go beyond the line of tags. All tagged trees are to be cut.

TIMBER SALE MAP


SALE NAME: The Skipper
 AGREEMENT NO: 30-079377
 TRUST(S): Forest Board Transfer (01), Common School (03)

REGION: Northwest
 COUNTY(S): Skagit
 Elevation: 1000-2100 feet



To Sedro-Woolley
2.6 mi.

Vicinity Map -Not to Scale-



Legend	
Symbols	Units
✱ Leave Tree Areas	~ ~ ~ Sale Boundary Tags
⊙ Landing	~ ~ ~ Management Unit Boundary Tags
✱ Water Break	~ ~ ~ R/W Boundary Tags
☐ Water Type	— Logged Area Boundary
⊗ Rock Pit	Logging Methods
⊙ Waste Area	▨ Cable
◆ Survey Corner	▨ Shovel
Roads	▨ RMZ
— Existing Road	Streams
- - - Optional Construction	→ Type 1-5
= = = Required Construction	
□ □ □ □ Required Reconstruction	

TIMBER NOTICE OF SALE

SALE NAME: RED FAWN

AGREEMENT NO: 30-079426

AUCTION: March 26, 2007 starting at 10:00 a.m., **COUNTY:** Skagit
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 3 miles southeast of Clear Lake

PRODUCTS SOLD AND SALE AREA:

All timber, except trees marked with blue paint at DBH and root collar, forest products tagged out with yellow leave tree tags, bounded as follows: by white timber sale boundary tags, adjacent plantation, MU-44 Road, MU-ML Road, and property line, in Unit #1; by white timber sale boundary tags and CM-ML Road, in Unit #2; by white timber sale boundary tags, property line, and the CM-ML Road, in Unit #3. All trees with blaze marks along the eastern boundary of Unit #3 (along property line). All timber bounded by orange right of way tags. The above described products on part(s) of Sections 9, 16 and 21 all in Township 34 North, Range 5 East, W.M., containing 106 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	19	6	2,449			3,324			1,458	532	135	
Hemlock	13	6	1,233						409	593	231	
Red alder	13		920						273	143	504	
Red cedar	17		329							279	5	
Cottonwood	31		54					42	8		4	
Maple	16		21						6		15	
Sale Total			5,006									

MINIMUM BID: \$1,788,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$178,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less. Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 20.35 stations of required construction. 6.80 stations of required reconstruction. 18.09 stations of optional construction. 15.00 stations of optional reconstruction. 33.09 stations of road to be abandoned if built.

Development of an existing hardrock source (MU-43 Hard Rock Pit) at milepost 4.3 of the Mundt Creek Mainline (MU-ML) Road will involve clearing, stripping, drilling, shooting, and processing rock to generate riprap and 3-inch-minus ballast rock. This rock is available at no cost on State land in Section 16, Township 34 North, Range 5 East, W.M.

Development of an existing hardrock source (MU-54 Hard Rock Pit) at milepost 5.4 of the MU-ML Road will involve clearing, stripping, drilling, shooting, and processing rock to generate riprap and 3-inch-minus ballast rock. This rock is available at no cost on State land in Section 21, Township 34 North, Range 5 East, W.M.

Total project estimated to need approximately 1,049 cubic yards of riprap and approximately 5,140 cubic yards of 3-inch-minus ballast rock.

Road construction and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 108 acres gross. 3.5 acres deducted for green tree retention clumps and 1.5 acres added for two right-of-ways (in Units 1 and 3). 106 acres

TIMBER NOTICE OF SALE

net. Cruised using variable plot method. Expansion factor used is 54.45. Sighting height is 4.5 feet. Grid size plot spacing was 320 X 200 feet in Units 1-A,C,D,E, 200 X 200 feet in Unit 1-B, 300 X 300 feet in Unit 2, and 400 X 200 feet in Unit 3. Plot ratio cruise count is 1:1 in Units 1 and 3 and all were cruised in Unit 2. 33 plots were taken in Unit 1-A, C, D, E, 4 plots were taken in 1-B, 3 plots were taken in Unit 2 and 26 plots were taken in Unit 3 for a total of 66 plots.

FEES: \$66,329.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: (1) Unit 1: There is a band of cliffs in the eastern parcel of the unit that may create challenging yarding. Timber above the cliffs will be downhill yarded over the cliffs. The topography below the cliffs provides good deflection and has good run out, there are good tail holds above the cliffs, and the road location provides for good options for yarding angles. The structural integrity of these cliffs must be maintained for habitat reasons. Logs should be fully suspended where possible over the cliffs to minimize impact. This may require intermediate supports. There is a small fissure in the cliff face that is protected by a few blue painted trees. These trees will not be traded. The CA must approve a logging plan for this parcel before yarding begins. (2) Unit 2: Primarily a blowdown salvage unit with some standing timber adjacent to the stream buffers.

TIMBER SALE MAP


SALE NAME: Red Fawn
AGREEMENT NO: 30-079426
TRUST(S): 01, Forest Board Transfer
 03, Common School

REGION: Northwest Elevation: 1000-2400 ft
COUNTY(S): Skagit
 Township 34 North Range 5 East Sec. 16&21

1000 0 1000 Feet



Legend	
Symbols	Streams
◆ Survey Corner	→ Type 1-5
* Water Type Break	⋯ RMZ
⊗ Rock Pit	~ Sale Boundary Tags
⊙ Landing	~ R/W Boundary Tags
⊕ Leave Trees	— Logged Area Boundary
⊠ Water Type	
● Gate	Logging Methods
⋯ Cliffs	▨ Cable
Roads	▨ Shovel
— Existing Road	
- - - Optional Construction	
⊠ Optional Reconstruction	
⊠ Required Construction	
⊠ Required Reconstruction	



Drawn By: D. Klingbiel
 Date: May 22, 2006
 Scale: 1" = 1000'

TIMBER NOTICE OF SALE

SALE NAME: ENGLISH BREAKFAST

AGREEMENT NO: 30-079338

AUCTION: March 26, 2007 starting at 10:00 a.m.,
Northwest Region Office, Sedro Woolley, WA

COUNTY: Snohomish

SALE LOCATION: Sale located approximately 16 miles south of Granite Falls

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint at DBH and root collar, trees bounded by yellow leave tree area tags, cedar snags, dead and down cedar trees, logs and stumps, bounded as follows: by white timber sale boundary tags, blue special management tags, young conifer stands, and the PD34 road; all timber marked with orange paint at DBH and butt spot located behind blue special management tags in the WMZ on part(s) of Sections 2 and 11 all in Township 29 North, Range 7 East, W.M., containing 68 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	23	8	2,144			55	372		1,150	505	62	
Hemlock	16	8	1,345				55		476	712	102	
Red cedar	13		376							312	64	
Cottonwood	22		122					63	50		9	
Maple	13		28							8	20	
Sale Total			4,015									

MINIMUM BID: \$1,337,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY: \$100,000.00

SALE TYPE: Lump Sum

EXPIRATION DATE: September 30, 2008

ALLOCATION: Export Restricted

BID DEPOSIT: \$133,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Shovel and Cable. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 26.26 stations of optional construction. 26.26 stations of road to be abandoned if built.

Development of an existing hardrock source (PD-35 Hardrock Pit) at station 185+00 of the PD-ML will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 34 cubic yards of rip rap and approximately 1892 cubic yards of 3-inch-minus ballast rock. This rock is available at no cost on State land in Section 2, Township 29 North, Range 07 East, W.M.

Road construction and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 74.2 acres gross. 6.1 acres deducted for green tree retention clumps. 68.1 acres net. Cruised using variable plot method. Expansion factor used is 62.50. Sighting height is 4.5 feet. Grid size plot spacing is 400 X 200 feet. Plot ratio cruise count is 1:1. A total of 42 plots were taken.

FEES: \$53,207.75 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: None.

TIMBER SALE MAP

SALE NAME: English Breakfast
AGREEMENT NO: 30-079338
TRUST(S): Forest Board Transfer (01)

REGION: Northwest
COUNTY(S): Snohomish
Elevation: 500 -1,500 Feet

Township 29 North, Range 07 East, W.M.




Legend

Symbols		
Water Type	Gate	
Cliff	Roads	Streams
Survey Corner	Existing Road	Type 1-5
Wetland	Optional Construction	Logging Methods
Landing	Units	Cable
Leave Tree Area	Sale Boundary Tags	Shovel
Marked Take Trees	Management Unit Boundary Tags	RMZ
	Logged Area Boundary	

Vicinity Map

Not To Scale



Drawn By: Michael Finlay
Date: April 4, 2006
Scale: 1" = 1000'
Version: 1.3

TIMBER NOTICE OF SALE

SALE NAME: CRITTER

AGREEMENT NO: 30-079378

AUCTION: March 26, 2007 starting at 10:00 a.m., **COUNTY:** Snohomish
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 5 miles east of Arlington

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint at DBH and root collar, dead and downed cedar stumps, logs and snags, and forest products tagged out by yellow leave tree area tags, bounded as follows: by white timber sale tags, in Unit #1; by white timber sale tags and adjacent plantation, in Unit #2; by white timber sale tags, JC-34 Road, powerline right of way, and adjacent plantation, in Unit #3. All timber bounded by orange right of way tags.. The above described products on part(s) of Sections 2 all in Township 31 North, Range 6 East, W.M., containing 121 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade									
				1P	2P	3P	SM	1S	2S	3S	4S	UT	
Douglas fir	29	6	4,260			29	1,054			2,596	521	60	
Hemlock	14	6	1,629				59			706	626	238	
Red cedar	17		830								704	126	
Maple	16		82								39	43	
Cottonwood	36		65					61				4	
Red alder	10		24									24	
Spruce	50		8								6	2	
Sale Total			6,898										

MINIMUM BID: \$2,692,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$269,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 12.01 stations of required construction. 0.80 stations of required reconstruction. 81.71 stations of optional construction. 81.71 stations of road to be abandoned if built. Installation of a 14'0" span x 7'3" rise x 40' length structural plate bottomless arch.

Development of a proposed hardrock source (JC-2928-06 Hardrock Pit) at station 33+55 of the JC-2928 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate riprap, shot rock, and 3-inch-minus ballast rock. This rock is available at no cost on State land..

Development of an existing gravel source (HM-21 Gravel Pit) at milepost 2.1 of the HM-ML Road will involve processing rock to generate streambed gravel for use with the installation of a fish passage culvert. This rock is available at no cost on State land.

Acquisition of 1 1/4-inch-minus crushed rock from a commercial rock source for use as a surfacing rock and as a leveling course for the pre-cast concrete footings.

Road construction, reconstruction, abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by GPS traverse. 127.8 acres gross. 7.2 acres deducted for green tree retention clumps. 120.6 acres net. Cruised using variable plot method. Expansion factor used is 54.45. Sighting height is 4.5 feet. Grid size plot spacing is 400 X 200 feet in Units #1, #2 and #3. Plot ratio cruise count: VP cruised all minor species; WH and DF on



TIMBER NOTICE OF SALE

every 3rd plot. 6 plots were taken in Unit #1, 22 plots were taken on Unit #2/R/W, and 32 plots taken in Unit #3, for a total of 60 plots.

FEES:

(1) Purchaser shall furnish a check to the State made payable to Jim Creek Tree Farm in the amount of \$500.00, on the day of sale for permit #55-079758. (2) \$62,082.00 is due on day of sale. \$13.25 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS:

(1) All right of way logs on the JC-2904 Road from Station 0+00 to 4+58 are not part of the products sold. (2) Blue special management boundary tags demarcate an equipment exclusion area.


TIMBER SALE MAP

SALE NAME: Critter
AGREEMENT NO: 30-79378
TRUST(S): 01 Forest Board Trust

REGION: Northwest
COUNTY(S): Snohomish
Elevation: 400' to 800'




Township 31 North, Range 06 East, Section 2



Legend

- | | | |
|------------------------|--------------|--|
| Symbols | | |
| | | |
| | | |
| | | |
| | | |
| Streams | | |
| | | |
| Logging Methods | | |
| | | |
| Roads | | |
| | | |
| | Units | |
| | | |
| | | |

* See Road Plan for LM-04 rock pit location.



Drawn By: Bryan Bernhagen
Date: July 11, 2006
Version: 1.3

Vicinity Map
Not To Scale

TIMBER NOTICE OF SALE

SALE NAME: FORKED HORN

AGREEMENT NO: 30-078597

AUCTION: March 26, 2007 starting at 10:00 a.m., **COUNTY:** Whatcom
Northwest Region Office, Sedro Woolley, WA

SALE LOCATION: Sale located approximately 7 miles northwest of Deming

PRODUCTS SOLD AND SALE AREA: All timber, except trees marked with blue paint at DBH and root collar, dead and downed cedar stumps, logs and snags, and forest products tagged out by yellow leave tree area tags, bounded as follows: by white timber sale tags, in Unit #1; by white timber sale tags and blue special management tags, in Unit #2. All trees marked with red paint bounded by blue special management tags and white timber sale boundary tags within Unit 2. All timber bounded by orange right of way tags. The above described products on part(s) of Sections 25, 26, 35 and 36 all in Township 40 North, Range 4 East, W.M., containing 122 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Douglas fir	20	8	2,180				262		1,223	564	131	
Birch	11		216						9	74	133	
Hemlock	14	8	212						97	64	51	
Red alder	14		185						58	61	66	
Maple	16		79							51	28	
Cottonwood	31		21					12	3		6	
Spruce	24		9							8	1	
Red cedar	48		5							5		
Sale Total			2,907									

MINIMUM BID: \$806,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: September 30, 2008 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$80,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and Shovel. Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

ROADS: 74.51 stations of required construction. 22.43 stations of required reconstruction. 43.92 stations of optional construction. 43.92 stations of road to be abandoned if built. Transportation of and installation of a gate and lockbox.

Development of an existing hardrock source (Good N' Gas Pit) at milepost 1.7 of the L-1000 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 192 cubic yards of riprap, approximately 13,224 cubic yards of 3-inch-minus ballast rock, and approximately 493 cubic yards 1 1/2 -inch-minus crushed surfacing. This rock is available at no cost on State land in Section 15, Township 39 North, Range 4 East, W.M.

Road construction, reconstruction, abandonment and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

ACREAGE DETERMINATION

CRUISE METHOD: Acres determined by Hand traverse. 130.1 acres gross. 9.2 acres deducted for green tree retention clumps, exclusion area, and private right of way. 120.9 acres net. Cruised using variable plot method. Expansion factor used is 54.45 for DF and 40.00 for all other species. Sighting height is 4.5 feet. Grid size plot spacing is 300 X 200 feet in Unit #1 and 320 X 200 in Unit #2. Plot ratio cruise count is grade all in Unit #1; and 1:1 in Unit #2. 46 plots were taken in Unit #1, and 40 plots taken in Unit #2, for a total of 86 plots. Note: 1.6 acres of State right of way was added to Unit #2.



TIMBER NOTICE OF SALE

FEES:

(1) Purchaser shall furnish a check to the State made payable to Theodore J. Hahn, Dana D. Johnson and Diana L. Johnson and Brandon J. Johnson in the amount of \$9,390.00 for timber, on the day of sale for permit #55-079416/50-079414. (2) Purchaser shall furnish a check to the State made payable to Dana D. Johnson and Diana L. Johnson in the amount of \$4,126.00 for timber, on the day of sale for permit #55-079416/50-079414. (3) Purchaser shall furnish a check to the State made payable to David Bellinger in the amount of \$7,977.00 for timber, on the day of sale for permit #55-079415. (4) \$38,517.75 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS:


The purchaser will cooperate with Mr. Johnson, the private landowner during the reconstruction of the existing CS-1000 road from the South Pass road (0+00) to the beginning of new construction (Station 22+43). Mr. Johnson wishes to provide power to his property and do it at the same time as the road reconstruction to save on installation costs and damage to the road. Mr. Johnson agrees to compensate the purchaser a reasonable rate based on industry standards for work completed. Mr. Johnson will secure all necessary permits and approvals if needed, so as not to delay road reconstruction. Should Mr. Johnson not desire to install power during road reconstruction the purchaser will no longer be obligated to cooperate in this project.

TIMBER SALE MAP

SALE NAME: Forked Horn
AGREEMENT NO: 30-078597
TRUST(S): Forest Board Transfer 01, School 03

REGION: Northwest
COUNTY(S): Whatcom
ELEVATION: 797 feet - 1,549 feet

Township 40 North, Range 4 East, W.M.



Legend

Units

- ~~~~~ Sale Boundary Tags
- ~~~~~ Management Unit Boundary Tags
- ~~~~~ R/W Boundary Tags

Logging Methods

- //// Sale Area

Roads

- ==== Existing Road
- ==== Required Construction
- ==== Required Reconstruction
- Optional Construction

Streams


- Type 1-5
- RMZ

Symbols

- X Take Trees
- * Water Type Break
- ✱ Marked Leave Trees
- ⊕ Landing
- ⊠ Water Type
- Gate
- ◆ Residence
- ◆ Survey Corner
- ⊙ Waste Area

Vicinity Map

- not to scale -



Drawn By: Mark Arneson
Date: October 9, 2006
Version: 1.2

TIMBER NOTICE OF SALE

SALE NAME: THUNDERDOME THINNING

AGREEMENT NO: 30-079280

AUCTION: March 28, 2007 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Clallam

SALE LOCATION: Sale located approximately 16 miles north of Forks, WA

PRODUCTS SOLD AND SALE AREA:

All timber bounded by timber sale boundary tags, the D-2900 road, a property line, and logged areas as defined in Schedule B, except leave trees as defined in Schedule A; all right of way timber bounded by right of way boundary tags, except that title to the timber within the right of way boundary tags of the 7+22 spur, the 9+86 spur, and the 28+10 spur is not conveyed to the Purchaser unless the road segments are actually constructed, on part(s) of Sections 36 all in Township 30 North, Range 14 West, W.M., containing 228 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								
						1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	12.3	6	1,924	16,970	\$6.74							1,193	731	
Sale Total			1,924	16,970										

MINIMUM BID: \$6.74/ton (est. value \$114,000.00)

BID METHOD: Sealed Bids

PERFORMANCE SECURITY:

\$22,800.00

SALE TYPE: Tonnage Scale

EXPIRATION DATE: October 31, 2009

ALLOCATION: Export Restricted

BIDDABLE SPECIES: Bidding to be allowed on all species combined.

BID DEPOSIT: \$11,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and processor/forwarder.

ROADS: 45.18 stations of optional construction. 111.40 stations of optional pre-haul maintenance. Purchaser maintenance on the D-2900, D-2900.15, and all new construction. Designated maintenance on all other roads used. Rock hauling, pre-haul maintenance and Road construction will not be permitted from October 15 to June 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd.


FEES: \$25,500.00 is due on day of sale. \$1.02 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: None.

TIMBER SALE MAP

SALE NAME: THUNDERDOME THINNING
 AGREEMENT NO: 30-079280
 TRUST(S): Common School (03)


REGION: Olympic
 COUNTY(S): Clallam



See Road Plan For Pre-Haul Maintenance Requirements and Locations

Legend

- ~~~~~ Timber Sale Boundary Tags
- ~~~~~ R/W Boundary Tags
- X-X- Property Line
- [Diagonal Hatching] Cable
- [Vertical Hatching] Processor/Forwarder
- [Dotted Pattern] RMZ
- Existing Road
- - - Optional Construction
- ▶ Streams
- * Stream Type Break
- [3] Stream Type
- ⊗ Rock Pit
- ◆ Survey Monument



Drawn By: M. Helms
 Date: October 10, 2006
 Scale: 1" = 1000'
 Elevation: 0 - 500'

TIMBER NOTICE OF SALE

SALE NAME: SEKIU CLUB CEDAR SALVAGE

AGREEMENT NO: 30-080570

AUCTION: March 28, 2007 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Clallam

SALE LOCATION: Sale located approximately 14 miles west of Clallam Bay, WA

PRODUCTS SOLD

AND SALE AREA: All downed cedar bounded by timber sale boundary tags and the FR-S-1250 road, and one stump and one downed log marked with orange paint located outside of the eastern edge of the sale area on part(s) of Sections 17, 18 and 19 all in Township 32 North, Range 13 West, W.M., containing 71 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg Ring DBH Count	Total MBF	MBF by Grade									
			1P	2P	3P	SM	1S	2S	3S	4S	UT	
Red cedar		72									72	
Sale Total		72										

MINIMUM BID: \$9,000.00

BID METHOD: Sealed Bids

PERFORMANCE

SECURITY: \$1,800.00

SALE TYPE: Lump Sum

EXPIRATION DATE: October 31, 2007

ALLOCATION: Export Restricted

BID DEPOSIT: \$900.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Hand and aerial

ROADS: Purchaser maintenance on the S-1250 road, and on the S-1000 road between the S-1018 and S-1250 junctions. Designated maintenance on all other roads used.

ACREAGE DETERMINATION

CRUISE METHOD: Sale was traversed using 95% photo and 5% GPS.




FEES: \$954.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: The DNR's standard conversion factor is 600 board feet per cord (cord = 128 cubic feet).

TIMBER SALE MAP

SALE NAME: SEKIU CLUB CEDAR SALVAGE
 AGREEMENT NO: 30-080570
 TRUST(S): Agricultural School (04)

REGION: Olympic
 COUNTY(S): Clallam



Drawn By: M. Helms
 Date: December 18, 2006
 Scale: 1" = 1000'

Elevation: 500-1000'

Legend			
~~~~~	Timber Sale Boundary Tags	→	Streams
	Hand/Aerial	3	Stream Type
.....	RMZ/WMZ	*	Stream Type Change
====	Existing Road	◆	Survey Monument
	Old Grades (non-driveable)	⊗	Rock Pit
	Forested Wetland	▲	Marked Take Log/Stump