

SPECIAL NOTICE:

Due to the of volume proposed for the months of March and April 2008, the follow is a summary of that volume.

Volume and auction months are subject to change.

Please call the Pacific Cascade Office at 360-577-2025 for additional information.

Summary Report of All Sales for the Month of March 2008

Board Sales					
County	Region	Agree #	Sale Name	Volume	Value
Clark	Pacific Cascade	81454	TOP HALF THIN & CC	1,961	\$0.00
Clark	Pacific Cascade	81603	ATTABOY	4,265	\$0.00
Grays Harbor Thurston	Pacific Cascade	81620	DR. PEPPER	7,683	\$0.00
Lewis	Pacific Cascade	81058	SHOWTIME	10,303	\$0.00
Lewis	Pacific Cascade	81630	SOLID GOLD	2,827	\$0.00
Pacific	Pacific Cascade	80968	SO FAR SO GOOD	6,979	\$0.00
Pacific	Pacific Cascade	81238	WHEATIES	4,330	\$0.00
Pacific	Pacific Cascade	81311	TYPO	4,368	\$0.00
Wahkiakum	Pacific Cascade	81338	NAGASAWA PASS	5,839	\$0.00
Total				48,555	
Region Sales					
County	Region	Agree #	Sale Name	Volume	Value
Wahkiakum	Pacific Cascade	81631	FRENCH TOAST BD	508	\$0.00
Total				508	\$0.00

Summary Report of All Sales for the Month of April 2008

Board Sales					
County	Region	Agree #	Sale Name	Volume	Value
Cowlitz	Pacific Cascade	81440	BARNES A BURNIN CC & THIN	4,101	\$0.00
Grays Harbor	Pacific Cascade	81718	KNOT	5,542	\$0.00
Lewis	Pacific Cascade	81724	EASTWOOD	3,530	\$0.00
Skamania	Pacific Cascade	81275	KANAKA	3,376	\$0.00
Thurston	Pacific Cascade	81283	MCLANE 2008	713	\$0.00
Wahkiakum	Pacific Cascade	81441	JIBBER JABBER	4,661	\$0.00
Wahkiakum	Pacific Cascade	81833	CLUTCH BLOWDOWN		\$0.00
Total				21,923	\$0.00

Washington State Department of Natural Resources (DNR)

Bidder's/Purchaser's Inspection of Sale Area and Forest Products

Acreage estimates and volume estimates contained within each timber notice of sale and each timber sale contract are made only for administrative and identification purposes. Except as expressly provided by the timber sale contract, the purchaser shall be responsible for paying the entire purchase price, even if the actual acreage or timber volume varies from the estimated quantity or volume shown.

All prospective bidders have the opportunity and are expected to inspect the sale area and the forest products located thereon. Bidders shall not rely on any representations by the State including, but not limited to, acreage estimates, volume estimates, appraisal or pre-bid documentation. The successful bidder/purchaser will further warrant that they have entered the timber sale contract without any reliance upon the DNR's volume estimates, acreage estimates, appraisals, pre-bid documentation, or any other representation by the DNR.

Any timber sale contract arising out of these public auctions will require the successful purchaser to warrant that they are entering the timber sale contract based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold.

Exclusion and Disclaimer of Warranties

The PARTIES AGREE that the IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, and ALL OTHER WARRANTIES EXPRESS OR IMPLIED, ARE EXCLUDED from this transaction, and shall not apply to the goods sold. For example, THE FOLLOWING SPECIFIC MATTERS ARE NOT WARRANTED, and are EXCLUDED from this transaction:

- a. ***The merchantability of the forest products.*** The use of the term “merchantable” in any document is not intended to vary the foregoing.
- b. ***The condition of the forest products.*** All forest products will be conveyed “AS IS.”
- c. ***The acreage contained within any sale area.*** Any acreage descriptions appearing in the timber notices of sale, timber sale contract, timber sale map or other documents are estimates only, provided solely for administrative and identification purposes.
- d. ***The volume, quality, or grade of the forest products.*** The descriptions of the forest products to be conveyed are estimates only, made solely for administrative and identification purposes.
- e. ***The correctness of any soil or surface conditions, presale construction appraisals, investigations, and all other pre-bid documents prepared by or for the State.*** These documents have been prepared for the State’s appraisal purposes only.
- f. ***That the sale area is free from threatened or endangered species, or their habitat.*** The State is not responsible for any interferences with forestry operations that result from the presence of any threatened or endangered species, or the presence of their habitat, within the sale area.
- g. ***That the forestry operations to be performed under this contract will be free from regulatory actions by governmental agencies.*** The State is not responsible for actions to enforce regulatory laws, such as the Washington Forest Practices Act (Chapter 76.09 RCW), taken by the Department of Natural Resources or any other agency that may affect the operability of these timber sales.

- h. Items contained in any other documents prepared for or by the State.

Please also see timber sale contract clause G-060 for further information.

BIDDING PROCEDURES FOR TIMBER AUCTIONS

The general requirements that follow are a part of all Timber Notices of Sale to be auctioned by the Department of Natural Resources (DNR).

General Information

The State reserves the right to waive minor irregularities and the right to reject any or all bids.

A. This book contains the timber notices of sale and maps for each timber sale scheduled to be auctioned. More specific information can be obtained by contacting the appropriate region office at the number listed on the back cover of this book.

B. The timber notice of sale is a summary of sale information. For more specific information, interested parties are encouraged to view the Appraisal Packets on the DNR Internet Site @ www.dnr.wa.gov, this will take you directly to the Product Sales Section. The Appraisal Packets contain **DRAFT** copies of the timber notice of sale, map, contract, road plan, cruise data, precruise and cruise narrative, Forest Practices Application (FPA), Hydraulics Project Approval (HPA).

C. The sale preview packets may be obtained at no charge for individual sales by visiting the appropriate region office.

D. Timber sale contracts contain extensive terms and conditions that will be binding upon successful high bidders. Each bidder should carefully review all terms contained in the appropriate **DRAFT** timber sale contract prior to bidding on a sale, and should review the final contract prior to signing. **DRAFT** timber sale contracts are contained in the preview and presales packets and are available upon request at the respective region office.

E. Sales advertised in this book have not been approved by the Board of Natural Resources and are subject to the Board's approval before they will be sold. The Board meets and approves sales approximately six weeks prior to auction. All sales are subject to confirmation by the DNR under RCW 79.15.120.

F. The State does not guarantee the accuracy of any information contained herein pertaining to particular sales. Therefore, all prospective purchasers are expected to make their own independent inspections and appraisals prior to bidding.

G. If any conflict exists between the information in the Timber Notice of Sale, timber sale map, sale preview packets and that in the timber sale contract, the signed contract will prevail.

H. Timber sales are subject to the Washington State Forest Excise Tax (RCW Chapter 84.33).

I. Within 30 days of sale confirmation, the apparent high bidder will provide to the State the Performance Security specified on each Notice of Sale.

J. Each DNR region office has information about sales offered in that region. For further information, contact the respective DNR region office. Region office addresses and telephone numbers appear on the back cover of this booklet.

K. The purchaser assumes the responsibility for any costs associated with extra maintenance or repair levied by a county for any county road used by the purchaser.

BIDDING PROCEDURES FOR TIMBER AUCTIONS (Continued)

Bidding Process

- A. All timber will be auctioned using the sealed bid method.
- B. Bids submitted on day of auction must be in the bid box at the specified auction location before 10:00 a.m. The respective DNR region office must receive mailed bids by 4:30 p.m., on the last business day before the auction. Bidders assume all risk for the method of delivery.
- C. The DNR has the right to reject bid forms that are completed incorrectly. *All bid forms must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. Revised documents are not permissible.* Bidding instructions are on the back of the Sealed Bid Form. A bid deposit must be included in the sealed bid envelope unless using a Timber Sale Statewide Bid Bond.
- D. All bids must include the completed Sealed Bid Form and bid deposit.
- E. Bids will be opened in each respective region in the order in which sales appear in the Public Auction Sale of Timber book (alphabetically by county and by agreement number).
- F. If a tie bid occurs, the names of the tie bidders will be placed in a hat and the successful bidder will be determined by a drawing.
- G. The apparent high bidder on a particular sale will have the option of withdrawing additional sealed bids submitted for any remaining sales to be auctioned. The apparent high bidder must exercise this option within two minutes after the apparent high bidder is announced.

Auction Time and Location

Auctions will start at 10:00 a.m. and close at 4:00 p.m. on the date and at the location specified in each Timber Notice of Sale.

Bid Deposits

- A. Required bid deposits are listed on each Timber Notice of Sale.
- B. Bid deposits must be in the form of cash, certified check, cashiers' check, money order or bid bond.
- C. Bid bonds may be either a Timber Sale Statewide Bid Bond or a Timber Sale Per Sale Bid Bond.
- D. All bid deposits shall be submitted by the person or entity submitting the bid and made payable to the Department of Natural Resources. **Third party deposits will not be accepted.**

Timber Sale Per Sale Bid Bonds

- A. The Per Sale Bid Bond shall guarantee payment of the bid deposit **within ten days of auction.**
- B. The balance between the bid bond and the Initial Deposit payment is due by 4:30 p.m., **on the day of auction.**
- C. Additional forms and instructions for a Per sale Bid Bond are available at any DNR region office.

Timber Sale Statewide Bid Bond

- A. Statewide Bid Bonds shall guarantee payment of the Initial Deposit on any statewide timber sale while the bond is in effect.
- B. The Statewide Bid Bond must be received by the Department of Natural Resources, Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction date. The bond shall be in the amount of \$150,000.00.
- C. The bidder must supply a list of persons authorized to bid using the bond. Bid bonds are subject to approval by the Department of Natural Resources.
- D. Successful bidders using a Statewide Bid Bond must pay the total Initial Deposit payment (10 percent of the total bid price) **by 4:30 p.m. on the day of auction.**
- E. A Statewide Bid Bond cannot be used to secure the Initial Deposit payment due the day of auction.
- F. Additional forms and instructions for a statewide bid bond are available at any DNR region office.

Payments

The initial deposit for a sale is 10% of the total bid value as submitted by the apparent high bidder (25% if the bidder is a defaulter as defined under WAC 332-140-300) and never less than \$5,000.00 for lump sum sales. For Lump Sum sales appraised at less than \$5,000.00, the entire bid value is due on day of auction.

- a. Apparent high bidders using cash, certified check, cashiers' check or money order as a bid deposit must pay the total Initial Deposit amount by 4:30 p.m. on auction day.
- b. Apparent high bidders using a Timber Sale Per Sale Bid Bond as a bid deposit must pay the difference between the bid deposit and the total initial deposit by 4:30 p.m., on the day of auction. The bid bond amount must be replaced with a certified check, cashier's check, bank draft, cash, money order, or wire transfer within ten days of the auction.
- c. Apparent high bidders using a Timber Sale Statewide Bid Bond must pay the entire Initial Deposit amount by 4:30 p.m. on the day of auction.

Fees due on the day of sale must be paid by 4:30 p.m.

All payments must be in the form of a certified check, cashier's check, bank draft, cash, money order or wire transfer.

Eligibility to Bid

In order to bid on State timber sales you must be:

- 18 years of age (or have a co-signer who meets the eligibility requirements),
- Licensed to do business in the State of Washington,
- Eligible to bid on Export Restricted timber, and
- Capable of meeting all contract obligations.

Authorized Representatives

Companies may only use authorized representatives or company officers to bid on State sales, sign State documents or sign checks. A list of authorized representatives and their specific authorities must be submitted in writing to the Department of Natural Resources Product Sales & Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction. A company owner or officer must sign this submittal.

State of Washington
Department of Natural Resources
Doug Sutherland, Commissioner of Public Lands

SEALED BID FORM

Sale Name _____ Agreement Number _____

_____ hereby submits the following bid for timber.
(Print full, legal company name)

(Street address, City, State, Zip Code)

(Phone Number)

Lump Sum Bid (Not Including Fees) \$_____ **For Total Sale**

Weight Scale Sale Bid (Not Including Fees) \$_____ / **Ton**

Scribner Scale Sale Bid (Not Including Fees) \$_____ / **MBF**

BID DEPOSIT

Bid Deposit Amount: \$_____

Bid Deposit Type:

- ☐ Cash, certified check, cashiers check, or money order
☐ Per Sale Bid Bond
☐ Statewide Bid Bond, Number _____

The Successful Bidder agrees to furnish, **within 30 days of confirmation date**, Performance Security acceptable to the State in the amount specified on the Notice of Sale. Performance Security must guarantee performance of all provisions of the contract and payment of any damages caused by operations under the contract or resulting from the successful bidders noncompliance with any rule or law.

Bidder's Warranty and Bid Signature

By signing and submitting this bid as an offer to purchaser forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based upon their own judgments of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, appraisals, pre-bid documentation, or any other representation by the Washington State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid)

Date _____

(Print **name and title** of Authorized Representative submitting this bid)

Note: all sales are subject to confirmation by the Commissioner of Public Lands (Refer to RCW 79.15.120)

Instructions For Completing Sealed Bid Form

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks on bid form must be completed including the bid bond number if the bidder is relying upon a bid bond for bid deposit.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box before 10:00 a.m. on the day of auction at the location specified in the Timber Notice of Sale.
 - B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be on the bid bond and timber sale contract. The bid form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Mailed Bids

- A. Bids that are mailed are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED". The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The Sealed Bid Form must be signed by an authorized representative. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope.
 - B. Bids that are mailed will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery. The DNR assumes no responsibility for any delays caused by any delivery service.
 - C. Sealed bid envelopes **must** contain a completed bid form and a bid deposit.
 - D. Sealed bid envelopes **may** contain a check for the Initial Deposit amount and a check for fees.
-

Initial Deposit:

Lump Sum Sales - Initial Deposit must equal 10% of the total bid submitted.
(25% if the bidder is a defaulter as defined under WAC 332-140-300)

Weight Scale Sales - Initial Deposit must equal 10% of the bid per ton multiplied by the total sale estimated tonnage. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

Scribner MBF Scale Sales - Initial Deposit must equal 10% of the bid per MBF multiplied by the total sale MBF. (25% if the bidder is a defaulter as defined under WAC 332-140-300)

State of Washington
Department of Natural resources
Doug Sutherland, Commissioner of Public Lands

STATEWIDE BID BOND

Bond Number _____

_____ of _____,
(Principal's Name) (City, State)

hereinafter called PRINCIPAL, and _____ hereinafter called SURETY,

a corporation organized under the laws of the State of _____, and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$150,000.00 Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, a venue shall be proper only in Thurston County Superior Court.

Signed, sealed and dated this _____ day of _____, _____.
(month) (year)

This statewide bid bond may be used for bidding between the following dates:

Starting: _____

Ending: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is an apparent high bidder, PRINCIPAL shall before 4:30 p.m., on day of sale, pay to the STATE the amount of the initial deposit in the form of a certified check, cashier's check, bank draft, cash or money order, then this agreement shall be void for the sale on which the payment is made; otherwise, it will remain in force.

SURETY will make payment to the STATE within ten days after demand by the STATE if the PRINCIPAL shall fail to make timely payment as described above.

The SURETY may cancel this bond by sending a written notice to the STATE, not less than forty-five days before a cancellation date; liability shall terminate as to acts or omissions of the PRINCIPAL that occur after the cancellation date.

The PRINCIPAL and the SURETY executed this bond on the date first mentioned.

Principal: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____
State & Zip Code

Surety: (Above named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____
State & Zip Code

Surety: (Local Office of Authorized agent)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____
Above
State & Zip

Notary or Company Seal in Space

Instructions For Completing Timber Sale Statewide Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Statewide Bid Bond may be used as bid guaranty on more than one timber sale.
- C. The full legal name and business address of the PRINCIPAL must be inserted where indicated and must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and title must be shown.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as SURETY, it may leave this signature block blank.
- F. This form must be received by the Department of Natural Resources, Product Sales and Leasing Division, PO BOX 47016, Olympia, Washington, 98504-7016, ten days in advance of the auction.
- G. The PRINCIPAL must submit a list of authorized bidders with the Statewide Bid Bond Form.
- H. **The State reserves the right to reject *incomplete* or *incorrect* bid bond forms, making such forms unacceptable as bid guaranty.**

State of Washington

Department of Natural Resources

Doug Sutherland, Commissioner Of Public Lands

Timber Sale Per Sale Bid Bond

Bond Number_____

_____ of _____, hereinafter called PRINCIPAL, and _____, hereinafter called SURETY, a corporation organized under the laws of the State of _____ and authorized to transact surety business in the State of Washington, as SURETY, are held and firmly bound jointly and severally to the State of Washington, Department of Natural Resources, hereinafter called the STATE, in the sum of \$_____Dollars, lawful money of the United States of America. The PRINCIPAL binds itself, its heirs, executors, administrators, successors, and assigns, and the SURETY binds itself, its successors, and assigns, all jointly and severally.

This bond shall be governed by the laws of the State of Washington. In the event of a lawsuit involving this bond, venue shall be proper only in Thurston County Superior Court.

Signed, sealed, and dated this____day of _____, 20_____.

BID IDENTIFICATION:

SALES NAME(S)	REQUIRED DEPOSIT	AGREEMENT NUMBER(S)

DATE OF BID: _____

It Is Hereby Understood and Agreed:

If PRINCIPAL is the high bidder on the sale(s) identified above and, within ten (10) days of the day of sale, transmits cash, certified check, cashier=s check, bank draft or money order, payable to the STATE, in the amount of the bid guaranty required by the terms of the Notice of Sale, *then* this obligation shall be void; *otherwise*, it shall remain in force.

SURETY will make payment to the STATE within ten (10) days after demand by the STATE whenever the PRINCIPAL shall fail to make timely payment as described above.

IN WITNESS WHEREOF: the PRINCIPAL and the SURETY have caused this bond to be executed on the date first mentioned.

SECOND OFFICER:

Signature: _____

Name: _____

Title: _____

PRINCIPAL: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

SURETY: (Local Office of Authorized Agent)

Signature:_____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip: _____

City: _____

State & Zip: _____

SURETY: (Above Named)

Signature: _____

Name: _____

Title: _____

Address: _____

City: _____

State & Zip_____

NOTARY OR COMPANY SEAL IN THE SPACE ABOVE

Instructions For Completing Timber Sale PerSale (s) Bid Bond

- A. This form is authorized for use as bid guaranty to qualify for bidding on Washington State Department of Natural Resources timber sales.
- B. The Timber Sale Per Sale Bid Bond may be used as bid guaranty on more than one timber sale auction held the same date at the same location.
- C. The full legal name and business address of the PRINCIPAL must be the same as will appear on the bidding record and timber sale contract. The bond must be signed by an authorized person, the name typed or printed, and title shown. If PRINCIPAL is a corporation, a second officer must sign in the space to the left of the signature of the officer executing for the PRINCIPAL.
- D. The full legal name and business address of the SURETY must be inserted where indicated. The bond must be signed by an authorized person. Additionally, the name must be typed or printed below the signature and the title must be shown. If this person is not an officer of the corporation, evidence of authority must be submitted.
- E. If the SURETY does not have a Washington State office or resident agent, but is authorized to transact surety business in the State of Washington as Surety, it may leave the local office signature block blank.
- F. The date of the bid bond must not be later than the auction date.
- G. **The State reserves the right to reject *incomplete or incorrect* bid bond forms, making such forms unacceptable as guaranty.**

STATE OF WASHINGTON
DEPARTMENT OF NATURAL RESOURCES
Doug Sutherland, Commissioner of Public Lands

LOG SORT SEALED BID FORM

Sale Name _____ Agreement Number _____ Date _____.

_____ hereby submits the following bid for delivered logs.
(Print Company Name)

_____ Telephone Number _____
(Print Name Authorized Company Representative) (Contact for bid result notification)

(Street Address)

(City, State and Zip)

Agreement Number	Sort Number	Delivered Logs Bid Amount (fill in one only)	
		\$ / MBF	\$ / ton

Bid Deposit Amount \$_____

Bid Deposit Type: ☐ Cash, Certified Check, Cashiers Check, or Money Order
☐ Per Sale Bid Bond
☐ Statewide Bid Bond, Number _____

The successful bidder agrees to furnish payment security acceptable to the State in the amount as described in clause P-041 of the Purchaser’s contract prior to log delivery and at a date to be determined by the State.

Bidder’s Warranty and Bid Signature

By signing and submitting this bid as offer to purchase forest products from the State, the Bidder hereby warrants to the State that they have had an opportunity to fully inspect the sale area and the forest products being sold. Bidder further warrants to the State that they enter this bid based solely upon their own judgment of the value of the forest products, formed after their own examination and inspection of both the timber sale area and the forest products being sold. Bidder also warrants to the State that they enter this bid without any reliance upon the volume estimates, acreage, estimates, appraisals, pre-bid documentation, or any other representation by the State Department of Natural Resources.

(Signature of Authorized Representative submitting this bid) (Date of Signature)

(Print name and title of Authorized Representative submitting this bid)

NOTES: A separate bid form is required for each log sort bid and must be delivered in a separate envelope. Photocopies of this bid form may be used. Each photocopy must have original signatures. Final contract award is contingent upon the State’s haul cost analysis. Actual haul route may vary and is subject to change at the State’s discretion. All sales are subject to confirmation by the Commissioner of Public Lands as per RCW 79.15.100.

LOG SORT SEALED BID SUPPLEMENTAL INFORMATION FORM

(Print Company Name)

(Sale Name)

(Agreement Number)

(Sort Number)

Log Manufacturing Specifications:

Enter one or more preferred log lengths for each log length range below. For Ponderosa Pine saw log sorts, enter one or more preferred log lengths for at least two log length ranges listed below.	Bidder’s Preferred Log Lengths (Log lengths exclude trim)
12 ft. through 18 ft.	
20 ft. through 28 ft.	
30 ft. through 40 ft.	

Minimum log trim: inches.

Additional Log or Pole Length Information:

To provide additional preferred cutting information you may attach a separate sheet or “Cutting card”.

Log Delivery Information:

1) Designate the point of delivery and address (must be a street address)

(Location Name)

(Street Address)

(City, State and Zip)

2) Designate the state approved Weighing and Scaling facility closest to the point of delivery.

(Location Name)

(Street Address)

(City, State and Zip)

3) Driving instructions:

Write a brief driving instruction narrative describing the most likely or usual and accustomed Haul Route used by trucks delivering logs from this sale area to your designated point of delivery above: (i.e. hwy 12 west, to I-5 north, to hwy 6 west, to Boistfort Rd. south)

Final contract award is contingent upon the State’s haul cost analysis. Actual haul route may vary and is subject to change at the State’s discretion. Additional terms or conditions requested by the bidder on or attached to the Log Sort Sealed Bid or Supplemental Information Forms are informational only and non-binding.

Instructions for Completing the Log Sort Sealed Bid and Supplemental Information Forms.

All bids submitted for the purchase of forest products being sold by the Washington State Department of Natural Resources must have an original signature on behalf of the person or entity submitting the bid, and must be on the form(s) provided in this booklet or a photocopy thereof. The DNR will not accept bids that are not signed, and will not accept bids that are not on the current, approved bid form. All appropriate blanks including Agreement Number, Sort Number, Bid amount (per mbf or ton as appropriate for the sort), Bid deposit amount and type. Signatures and date on bid form must be completed including the bid bond number if bidder is relying upon a bid bond for bid deposit.

Bids may not be accepted if a completed '**Log Sort Sealed Bid Supplemental Information Form**' is not included with the approved '**Log Sort Sealed Bid Form**'.

For more specific information, contact the appropriate region office.

In-Person Bids

- A. Sealed bids must be in auction box or auction envelope before 10:00 a.m. on the day of sale at the location specified in the notice of sale.
- B. Sealed bids must be submitted in an envelope with the name of the sale, the bidder's name and the contract agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same as the name on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Sealed bid envelopes are available at all region offices. One bid per envelope, please.
- C. Sealed bid envelopes must contain the following:
 - 1. A completed Log Sort Sealed Bid form;
 - 2. A completed Supplemental Information form; and
 - 3. A bid deposit

Mailed Bids

- A. Mail-in bid envelopes are required to have printed on the outside: "DO NOT OPEN UNTIL SALE DATE. SEALED BID ENCLOSED." The sealed bid envelope(s) will be enclosed inside the mailed-in envelope. Mailed bids must be submitted in an envelope with the name of the sale, the bidder's name and the agreement number clearly written on the outside of the envelope. The full legal name and business address of the bidder must be inserted where indicated on the form, and must be the same on the bid bond and timber sale contract. The bid form must be signed by an authorized person. When a bidder has more than one person authorized to bid, then documentation of those persons with signature authority for bidding must accompany the bid or be on file at the region office. Mail-in envelopes are available at all region offices. One bid per mailed-in envelope, please.
- B. Mail-in or otherwise delivered bids will be accepted up to 4:30 p.m. the last business day before the auction by the region office in which the sale is located. Bidders assume the risk for the method of delivery they chose. The DNR assumes no responsibility for any delays caused by any delivery service.
- C. Sealed bid envelopes must contain the following:
 - 1. A completed '**Log Sort Sealed Bid Form**';
 - 2. A completed '**Log Sort Sealed Bid Supplemental Information Form**' and;
 - 3. A bid deposit

Summary Report of All Sales for the Month of February 2008

Board Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	81654	SUSIE MIX	5,969	\$1,225,000.00
Clallam	Olympic	81663	PALO ALTO SUBSTITUTE	7,392	\$1,598,000.00
Cowlitz	Pacific Cascade	81310	RIFF RAFF	5,236	\$1,152,000.00
Grays Harbor	Olympic	74836	GREEN POLSON	2,005	\$290,000.00
Grays Harbor Lewis	Pacific Cascade	81298	DOS	3,953	\$918,000.00
Lewis	Pacific Cascade	81457	AMERICAN IDOL	2,672	\$578,000.00
Mason	South Puget	80614	BELFAIR FI SORTS	1,380	\$615,440.00
Pacific	Pacific Cascade	81272	NORTHSIDER II	10,411	\$392,000.00
Pacific	Pacific Cascade	81559	P&E RIDGE BLOWDOWN	4,420	\$534,000.00
Pierce	South Puget	77633	WHISKERS PC	5,260	\$847,000.00
Skagit	Northwest	80592	MEDIAN	5,885	\$1,310,000.00
Skagit	Northwest	80593	GINGERBREAD HARDWOOD	1,184	\$481,000.00
Snohomish	Northwest	80575	TREMBLE HARDWOOD	3,449	\$1,117,000.00
Snohomish	Northwest	81416	WHITEHORSE FLATS PC	2,316	\$405,000.00
Snohomish	Northwest	81682	EQUINOX	4,867	\$1,390,000.00
Thurston	Pacific Cascade	81509	WIGTOWN	2,766	\$537,000.00
Wahkiakum	Pacific Cascade	81336	HANGING CHAD BLOWDOWN	3,820	\$373,000.00
Whatcom	Northwest	80579	APPLE PIE	3,302	\$977,000.00
Whatcom	Northwest	80923	LOOK NORTH	2,474	\$678,000.00
Total				=====78,761	=====15,417,440.00

Region Sales

<u>County</u>	<u>Region</u>	<u>Agree #</u>	<u>Sale Name</u>	<u>Volume</u>	<u>Value</u>
Clallam	Olympic	79364	READE MY LIPS THINNING	1,839	\$111,000.00
Clallam	Olympic	81047	HAPPE MAX	1,990	\$206,000.00
Clallam	Olympic	81049	LYRE RAIL COMMERCIAL THINNING	1,050	\$84,000.00
Clallam	Olympic	81556	SCOTCH	1,619	\$211,000.00
Lewis	Pacific Cascade	81414	INSTANT KARMA BD	730	\$191,000.00
Okanogan	Northeast	80956	PALMER VIEW	1,413	\$153,000.00
Total				=====8,641	=====956,000.00

TIMBER NOTICE OF SALE

SALE NAME: *SUSIE MIX*

AGREEMENT NO: *30-081654*

AUCTION: February 27, 2008 starting at 10:00 a.m., **COUNTY:** Clallam
Olympic Region Office, Forks, WA

SALE LOCATION: Sale located approximately 10 miles west and southwest of Joyce, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags, and logged areas, except trees marked with red paint or bounded by leave tree area tags in Unit #1; all timber bounded by timber sale boundary tags, special management unit boundary tags, logged areas, the PA-S-1000 and PA-S-1200 Roads, and the 15+35 and 12+21 spurs, except trees marked with blue paint or bounded by leave tree area tags in Unit #2; all timber bounded by timber sale boundary tags, the PA-S-1000 Road and a logged area, except trees marked with blue paint or bounded by leave tree area tags in Unit #3; all timber bounded by timber sale boundary tags and the PA-S-1050 Road, except trees marked with blue paint or bounded by leave tree area tags in Unit #4; all timber painted with yellow bands and bounded out by special management unit boundary tags in Units #5 and #6; all timber painted with red bands and bounded by special management unit boundary tags and bounded by timber sale boundary tags in Unit #7 on part(s) of Sections 5 and 6 all in Township 30 North, Range 9 West, Sections 30 and 31 all in Township 31 North, Range 9 West, W.M., containing 205 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								
				1P	2P	3P	SM	1S	2S	3S	4S	UT
Red alder	14.8		2,276						506	497	1,046	227
Douglas fir	20.3	3	1,751						1,252	388	61	50
Hemlock	15.3	4	1,221						685	327	142	67
Red cedar	14.2		721							502	214	5
Sale Total			5,969									

MINIMUM BID: \$1,225,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$122,500.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable, shovel and tracked skidder as shown on the timber sale map. The tracked skidder shall be limited to a D-6 or less. Feller buncher will be allowed when operations are not otherwise restricted and when weather permits. During restriction periods only hand falling will be allowed as long as it does not interfere with marbled murrelet timing restrictions.

Unit #1, #2, #4, and #7 - Tracked skidder, shovel or cable.
Unit #3 - Tracked skidder, cable, and shovel, with shovel only areas
Unit #5 and #6 - No heavy equipment allowed in unit - hand falling only. Trees will be felled toward the special management unit boundary tagged boundary and can be pulled out with cable if necessary. Ground Based Yarding will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator. Only hand falling will be allowed during this restricted period. Unit #3 Only - Daily timing restrictions will apply to harvest operations (cutting, yarding, and loading) from one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31.

ROADS: 63.05 stations of required construction. 23.03 stations of optional construction. 13.24 stations of optional reconstruction. 404.15 stations of required pre-haul maintenance. Purchaser maintenance on the PA-S-1000, PA-S-1200 and PA-S-2600 Roads, all new construction, and pre/post haul maintenance roads. Designated maintainer on all other roads used. Marbled murrelet timing restrictions apply to the PA-S-1000 Road, between stations 46+65 and 68+70, the 4+19 Spur and the Place Pit. The restrictions are from one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31. Rock haul, pre-haul maintenance, reconstruction and road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION


TIMBER NOTICE OF SALE

- CRUISE METHOD:** Sale acreage was 71% GPS'd and 29% photo traversed. Sale area was cruised using a variable plot sample on a 330 x 330 foot grid for Units 1 - 4. Units 5, 6 and 7 were 100% cruised.
- FEES:** \$79,103.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.
- SPECIAL REMARKS:** There are locked gates on the PA-S-1000 and PA-S-1200 Roads and the Place Pit - contact the Olympic Region Dispatch Center at 360-374-6131 to obtain a AA-1 key.

TIMBER SALE MAP

SALE NAME: SUSIE MIX
AGREEMENT NO: 30-081654
TRUST(S): Forest Board


REGION: Olympic
COUNTY(S): Clallam



Legend

- | | | | |
|-------|-----------------------------------------------------|--------|-------------------------|
| ~~~~~ | Timber Sale Boundary Tags | ===== | Existing Road |
| ~~~~~ | Special Management Unit Boundary Tags | ===== | Required Construction |
| | Shovel | ----- | Optional Construction |
| | Shovel or Cable | +++++ | Optional Reconstruction |
| | Tracked Skidder, Shovel, Cable | —————▶ | Jeep Trail in Unit #1 |
| | RMZ | —▶ | Streams |
| | Leave Tree Area
(bounded by LeaveTree Area Tags) | | Stream Type |
| ●—● | Gate | * | Stream Type Break |
| | | ◆ | Survey Monument |
| | | | Wetland |
| | | | Rock Pit |



Drawn By: M. Helms
Date: December 12, 2007
Scale: 1" = 1000'
500 0 500 Feet
Elevation: 500 - 1000'




TIMBER SALE MAP

SALE NAME: SUSIE MIX
AGREEMENT NO: 30-081654
TRUST(S): Forest Board

REGION: Olympic
COUNTY(S): Clallam



Drawn By: M. Helms
Date: December 12, 2007
Scale: 1" = 1000'
500 0 500 Feet
Elevation: 500 - 1000"



TIMBER NOTICE OF SALE

SALE NAME: PALO ALTO SUBSTITUTE

AGREEMENT NO: 30-081663

AUCTION: March 26, 2008 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Clallam

SALE LOCATION: Sale located approximately 6 miles southwest of Sequim, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags and logged areas, except trees marked with blue paint or bounded by leave tree area tags in Unit #1; all timber bounded by timber sale boundary tags, logged areas, the J-1600 Road, the J-1620 Road and the J-1621 road, except trees marked with blue paint or bounded out by leave tree area tags in Unit #2; all timber bounded by timber sale boundary tags, except trees marked with blue paint or bounded by leave tree area tags in Unit #3; all timber bounded by timber sale boundary tags, special management unit boundary tags, the Palo Alto Road, and the J-1800 Road, except trees marked with blue paint or bounded by leave tree area tags in Unit #4; take trees banded and butt spotted with red paint and bounded by timber sale boundary tags and special management unit boundary tags in Unit #5, Unit #6, and Unit #7; take trees banded and butt spotted with red paint and bounded by timber sale boundary tags and the Jimmycomelately Road in Unit #8; all timber bounded by right of way boundary tags in Unit #9; all timber bounded by the J-1200 and timber sale boundary tags, except that title to the timber is not conveyed if the Purchaser elects not to use the Palo Alto Pit in Unit #10; all timber bounded by right of way boundary tags except that title to the timber is not conveyed if the Purchaser elects not to build the 21+53 Spur in Unit 11 on part(s) of Sections all in Township 29 North, Range 4 West, Sections 10, 11, 14 and 21 all in Township 29 North, Range 3 West, W.M., containing 225 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	16.8	8	4,285			32	483		1,871	1,498	401	
Red cedar	15		1,370							1,064	306	
Hemlock	13.9	10	784				27		219	394	144	
Grand fir	19.3		744						539	189	16	
Red alder	11.1		157							29	128	
Cottonwood	14.3		29						27		2	
Maple	19.4		23						8	12	3	
Sale Total			7,392									

MINIMUM BID: \$1,598,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY: \$100,000.00

SALE TYPE: Lump Sum

EXPIRATION DATE: October 31, 2009

ALLOCATION: Export Restricted

BID DEPOSIT: \$159,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable (19%) and Ground (81%) methods as follows: Unit #1 - shovel only, with no falling or yarding permitted from December 1st through February 28th; Unit #2 - cable or shovel as shown on the prospectus map, feller buncher allowed on slopes under 40%; Unit 3 - cable or shovel as shown on the timber sale map, feller buncher allowed on slopes under 40%; Units #4 through #7 - shovel or tracked skidder, tracked skidder allowed only on designated skid trails and restricted from December 1st through March 31st; Unit #8 - shovel or tracked skidder, tracked skidder allowed only on designated skid trails, no falling or yarding permitted from December 1st through March 31st; Units #9 through #11 - shovel only. Additional hourly timing restrictions apply - see Clause H-140 of the contract for details.

ROADS: 81.09 stations of optional construction. 9.10 stations of optional reconstruction. 359.20 stations of required pre-haul maintenance. 12.45 stations of optional pre-haul maintenance. The hauling of forest products will not be permitted from 8 PM to 6 AM Monday through Friday, nor will it be allowed on weekends or on State recognized holidays unless authorized in writing by the Contract Administrator. Purchaser maintenance on all roads used. Rock haul, reconstruction, pre-haul maintenance and road construction will not be permitted from November 1 to April 30 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION



TIMBER NOTICE OF SALE

- CRUISE METHOD:** Sale area was 99.6% GPS'd and .4% estimated. Sale area was cruised using a variable plot sample with a BAF of 40.00F on a 264 x 330 foot grid in Unit #1, a BAF of 46.94F on a 330 x 396 foot grid in Units #2 and #4, and a BAF of 46.94F on a 264 x 330 foot grid for Unit #3. Unit #5 was 100% cruised. Units #6, #7, and #9 were ITS' d cruising every 3rd, 5th and 10th tree respectively. Units #8, #10, and #11 were cruised using a variable plot sample with a BAF of 33.61F on a 198 x 198 foot grid for Unit #8, a BAF of 20.00F on a 132 x 132 foot grid for Unit #10, and a BAF of 40.00F on a 132 x 132 foot grid.
- FEES:** Purchaser must pay Clallam County a total of \$360.00 for Road Approach Permits - see road plan for details. \$97,944.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.
- SPECIAL REMARKS:** There are locked gates on the J-1500, J-1800 and PA-L-3510 Roads. Contact the Olympic Region's Dispatch Center at 360-374-6131 to obtain a AA-1 key for the J-1800 and PA-L-3510 Roads and for the electronic combination to the J-1500 Road.

TIMBER SALE MAP

SALE NAME:	PALO ALTO SUBSTITUTE
AGREEMENT NO:	30-081663
TRUST(S):	Forest Board, Common School, Capitol


REGION: Olympic
COUNTY(S): Clallam



Drawn By: M. Helms
Date: December 6, 2007
Scale: 1" = 1000'

500 0 500 Feet

Elevation: 800-2000'



Map 1 of 3

TIMBER SALE MAP

SALE NAME:

PALO ALTO SUBSTITUTE

AGREEMENT NO:

30-081663

TRUST(S):


Forest Board, Common School, Capitol

REGION:

Olympic

COUNTY(S):


Clallam



Legend

- | | | | |
|-----------|---------------------------------------|-----|---------------------------------------------------------------|
| ~~~~~ | Timber Sale Boundary Tags | ➔ | Streams |
| ~ ~ ~ ~ ~ | Special Management Unit Boundary Tags | 3 | Stream Type |
| ~~~~~ | R/W Boundary Tags | * | Stream Type Break |
| ===== | Existing Road | ●—● | Gate |
| ----- | Optional Construction | ⊗ | Rock Pit |
| +++++ | Optional Reconstruction | ◆ | Survey Monument |
| | Ground | ▲ | Structure |
| | Cable | 🌲 | Leave Tree Area
(bounded by leave tree area boundary tags) |
| | RMZ | 🌊 | Wetland |


Drawn By: M. Helms
Date: December 6, 2007
Scale: 1" = 1000'
500 0 500 Feet
Elevation: 800-2000'



TIMBER SALE MAP

SALE NAME:	PALO ALTO SUBSTITUTE	REGION:	Olympic
AGREEMENT NO:	30-081663	COUNTY(S):	Clallam
TRUST(S):	Forest Board, Common School, Capitol		

Vicinity Map
Not to Scale



TIMBER NOTICE OF SALE

SALE NAME: RIFF RAFF

AGREEMENT NO: 30-081310

AUCTION: February 28, 2008 starting at 10:00 a.m., **COUNTY:** Cowlitz
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 25 miles east of Woodland, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees tagged out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags and pre-existing down timber greater than 36 inches in diameter, bounded by the following: timber sale boundary tags, private property line boundary (marked with white posts and red ringed trees; all timber up to and including the red painted trees is considered sale volume), reprod and the N-3040 road in Unit #1; timber sale boundary tags, reprod and the N-3040 road in Unit #2; all timber bounded by right-of-way boundary tags on part(s) of Sections 4, 5 and 8 all in Township 6 North, Range 4 East, W.M., containing 167 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	18.8	8	4,763				350		2,906	1,232	275	
Red alder	12		315						38	75	202	
Maple	16		131							61	70	
Hemlock	11.2	9	27						6	10	11	
Sale Total			5,236									

MINIMUM BID: \$1,152,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$115,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 35% and less during dry soil conditions. See clause H-140 and Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Ground Based Yarding will not be permitted from October 1 to May 31 unless authorized in writing by the Contract Administrator, this applies to tracked skidding only.

ROADS: 100.89 stations of optional construction. 14.78 stations of optional reconstruction. 27.98 stations of required pre-haul maintenance. 100.89 stations of road abandonment, if road is built. Rock for, construction, reconstruction, and/or pre-haul maintenance under this contract may be obtained at no cost to the Purchaser from the State N-3000 road pit located in Section 8, Township 6 North, Range 4 East. Purchaser shall obtain Jaw Run and Riprap rock from the N-3000 road pit. The Purchaser shall give the Contract Administrator 3 days notice prior to commencing any operations in the listed rock pits. 1¼ inch minus crushed rock specified in the ROCK LIST may be obtained at no cost to the Purchaser from an existing stockpile adjacent to the N-3000 road pit. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 20% ground-based and 80% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$12.70 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS: See driving map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: RIFF RAFF
AGREEMENT#: 30-081310
TRUST(S): State Forest Board Transfer (01) & Normal School (08)

REGION: Pacific Cascade
COUNTY(S): Cowlitz
ELEVATION RGE: 800ft. - 1,720ft.

Township 06 North, Range 04 East, W.M.




DRIVING MAP

SALE NAME: RIFF RAFF
AGREEMENT#: 30-081310
TRUST(S): State Forest Board Transfer (01) & Normal School (08)

REGION: Pacific Cascade
COUNTY(S): Cowlitz
ELEVATION RGE: 800ft. - 1,720ft.

Township 06 North, Range 04 East, W.M.



Highways

Haul Route

Milepost

Off Ramp

Distance Indicator

Gate (PCP 1-1)

Rock Pit

DRIVING DIRECTIONS:

From State Route 503 (milepost 33), turn North onto the N-2000 and follow for 0.3 miles
Turn right (north) onto the N-3000 and follow for 1.1 miles (Pit)
Continue on the N-3000 for 0.4 miles to Unit 2
Turn right (east) onto the N-3040 and follow for 0.3 miles to Unit 1

TIMBER NOTICE OF SALE

SALE NAME: GREEN POLSON

AGREEMENT NO: 30-074836

AUCTION: February 27, 2008 starting at 10:00 a.m., **COUNTY:** Grays Harbor
South Puget Sound Region Office, Enumclaw, WA

SALE LOCATION: Sale located approximately 19 miles north of Hoquiam, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags, the Polson Camp Road, the RY3201 Road, and logged areas, except trees marked with blue paint in Unit #1; all timber bounded by timber sale boundary tags, the PC-1100 Road, a property line and special management unit boundary tags, except trees marked with blue paint in Unit #2; all timber bounded by special management unit boundary tags, except trees marked with blue paint in Unit #3; all timber as defined in Schedule B, bounded by timber sale boundary tags and special management unit boundary tags, except trees marked with orange paint in Unit #4a and 4b; all timber as defined in Schedule B, bounded by timber sale boundary tags, the PC-1000 Road, and a logged area, except trees marked with orange paint in Unit #4c; all timber bounded by timber sale boundary tags, special management unit boundary tags and logged areas, except trees marked with blue paint in Unit #5; all timber bounded by timber sale boundary tags, special management unit boundary tags, and a logged area, except trees marked with blue paint in Unit #6; all timber bounded by logged areas, special management unit boundary tags and the RY-3200 Road, except trees marked with blue paint in Unit #7; all timber as defined in Schedule B, bounded by timber sale boundary tags, special management unit boundary tags, except trees marked with orange paint in Unit #8a, all timber as defined in Schedule B, bounded by timber sale boundary tags, special management unit boundary tags and a logged area, except trees marked with orange paint in Unit #8b; all timber as defined in Schedule B, bounded by timber sale boundary tags, special management unit boundary tags, and the RY-3200 Road, except trees marked with orange paint in Unit #8c; all timber as defined in Schedule B, bounded by timber sale boundary tags, special management unit boundary tags, the RY-3200 Road and a logged area, except trees marked with orange paint in Unit #8d; all timber bounded by right of way boundary tags on part(s) of Sections 36 all in Township 20 North, Range 10 West, W.M., containing 104 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								UT
						1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	13.3	5	1,037	7,355	\$18.20						187	637	213	
Hemlock	12.4	5	859	6,783	\$18.20						320	296	243	
Red alder	11.3		51	388	\$84.00						9	8	35	
Spruce	19.8		41	317	\$18.20						13	19	10	
Maple	8.8		17	143	\$6.00								17	
Sale Total			2,005	14,986										

MINIMUM BID: \$18.20/ton (est. value \$290,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$58,000.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Spruce, Hemlock and Douglas fir combined

BID DEPOSIT: \$29,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: 100% Ground methods. Tracked skidders limited to D-5 equivalent or less. No rubber tired equipment. Ground Based Yarding will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

ROADS: 26.65 stations of required construction. 23.97 stations of optional construction. 16.40 stations of required pre-haul maintenance and 54.15 stations of optional pre-haul maintenance. Purchaser maintenance on all new construction and reconstruction, and all existing roads used, except those identified as Designated Maintainer. Designated maintenance on the RY 3200 Road. Pre-haul maintenance, rock hauling and road construction will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION


TIMBER NOTICE OF SALE

- CRUISE METHOD:** Sale area was 100% GPS traversed. Sale area was cruised using a variable plot sample with a BAF of 40.00F on a 220 x 220 food grid for Units #1-3 and #5-8; Unit #4 was cruised using a variable plot sample with a BAF of 20.00F and a fixed 1/10 acre plots.
- FEES:** On day of sale, Purchaser must provide a cashier's check made payable to Rayonier Forest Resources, in the amount of \$397.00 for private right of way timber, and a cashier's check made payable to the Dept. of Natural Resources, in the amount of \$100.00 for reimbursement of a Road Approach Permit. \$26,600.00 is due on day of sale. \$1.20 per ton is due upon removal. These are in addition to the bid price.
- SPECIAL REMARKS:** There are 5 trees per acre in the thinning units which are to be cut and left. These trees are marked with orange paint. There are hazard abatement requirements in Unit #1.
NOTE: A PORTION OF THE PC-1002 AND RY-3200 ROADS ARE TO BE USED FOR VIEWING PURPOSES ONLY AND THEY SHALL NOT BE USED FOR TIMBER HAUL.

TIMBER SALE MAP

SALE NAME: GREEN POLSON
AGREEMENT NO: 30-074836
TRUST(S): Common School

REGION: Olympic
COUNTY(S): Grays Harbor



Legend

- | | | | |
|--------------------|---------------------------------------|-------------------|-----------------------|
| ~~~~~ | Timber Sale Boundary Tags | ➔ | Stream |
| ~~~~~ | Special Management Unit Boundary Tags | [3] | Stream Type |
| ~~~~~ | R/W Boundary Tags | * | Stream Type Break |
| ✕—✕ | Property Line | ◆ | Survey Monument |
| [Vertical Lines] | Clearcut | ≡ | Wetland |
| [Horizontal Lines] | Thinning | ===== | Required Construction |
| [Double Line] | Existing Road | ----- | Optional Construction |
| [Dashed Line] | Designated Skid Trail | [Horizontal Bars] | Hazard Abatement |

Unit Acres

- Unit 1 - 10 acres
Unit 2 - 14 acres
Unit 3 - 11 acres
Unit 4a&b - 27 acres
Unit 4c - 3 acres
Unit 5 - 5 acres
Unit 6 - 8 acres
Unit 7 - 6 acres
Unit 8a - 11 acres
Unit 8b - 2 acres
Unit 8c - 3 acres
Unit 8d - 3 acres

Drawn By: M. Helms
Date: March 6, 2007
Scale: 1" = 1000'





Elevation: 0 - 500'

TIMBER SALE MAP

SALE NAME: GREEN POLSON
AGREEMENT NO: 30-074836
TRUST(S): Common School

REGION: Olympic
COUNTY(S): Grays Harbor

Vicinity Map
Not to Scale



Drawn By: M. Helms
Date: March 6, 2007

TIMBER NOTICE OF SALE

SALE NAME: DOS

AGREEMENT NO: 30-081298

AUCTION: February 28, 2008 starting at 10:00 a.m., **COUNTY:** Grays Harbor, Lewis
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 5 miles west of Rochester, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees tagged out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags, pre-existing stumps and pre-existing down timber existing 2 years prior to the day of sale, bounded by the following: timber sale boundary tags, reprod, private property line marked by white posts and the I-2000 Road in Unit #1; timber sale boundary tags and private property line marked by white posts in Unit #2; timber sale boundary tags, reprod, private property line marked by white posts and the H-0100 road in Unit #3; timber sale boundary tags, reprod and private property line marked by white posts in Unit #4; all timber bounded by right-of-way tags on part(s) of Sections 9, 15, 16 and 18 all in Township 15 North, Range 4 West, W.M., containing 122 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	18.8	8	2,435				119		1,528	674	114	
Red alder	14.8		848					18	172	257	401	
Maple	15.1		588						182	152	254	
Grand fir	22.8		74						59	13	2	
Red cedar	21.5		8							8		
Sale Total			3,953									

MINIMUM BID: \$918,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$91,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and shovel harvesting equipment with shovel harvesting equipment being restricted to slopes of 35% and less during dry soil conditions. See clause H-140 AND Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Shovel Yarding will not be permitted from October 31 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 5.45 stations of required construction. 22.65 stations of required reconstruction. 57.21 stations of optional construction. 292.22 stations of required pre-haul maintenance. 1.75 stations of heavy road abandonment. Rock for construction, reconstruction, and pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 20% shovel and 80% cable harvesting.

FEES: \$50,000.00 is due on day of sale. \$9.45 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS: See driving map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: DOS
AGREEMENT#: 30-081298
TRUST(S): State Forest Board Transfer (01) & Common School (03)

REGION: Pacific Cascade
COUNTY(S): Lewis & Grays Harbor
ELEVATION RGE: 400ft. - 720ft.

Township 15 North, Range 04 West, W.M.




TIMBER SALE MAP

SALE NAME: DOS
AGREEMENT#: 30-081298
TRUST(S): State Forest Board Transfer (01) & Common School (03)

REGION: Pacific Cascade
COUNTY(S): Lewis & Grays Harbor
ELEVATION RGE: 400ft. - 720ft.

Township 15 North, Range 04 West, W.M.



Sale Area	Sale Boundary Tags	Required Abandonment
Leave Tree Area	Leave Tree Tags	Right of Way Boundary Tags
Riparian Mgt Zone	Property Line	Railroad
	Existing Road	Streams
	Required Pre-Haul Maintenance	Stream Type
	Required Construction	Leave Trees
	Required Reconstruction	Gate (PCP 1-1)
	Optional Construction	

DRIVING MAP

SALE NAME: DOS

AGREEMENT#: 30-081298


TRUST(S): State Forest Board Transfer (01) & Common School (03)

REGION: Pacific Cascade

COUNTY(S): Lewis & Grays Harbor

ELEVATION RGE: 400ft. - 720ft.

Township 15 North, Range 04 West, W.M.



- Highways
- Haul Route
- Milepost
- Off Ramp
- Distance Indicator
- Gate (PCP 1-1)

DRIVING DIRECTIONS:

From US Highway 12 (milepost 42), turn South onto Albany St SW and follow for 0.2 miles

Turn right (southwest) onto Marble St SW and follow for 1.0 mile

Turn right (west) onto Independence Rd and follow for 4.0 miles

Units 2-4: Turn right (north) onto Harris Road

Units 3-4: Follow Harris Road for 0.1 miles to the H-0100 on left (gate)

Unit 2: Follow Harris Road 0.4 miles to the H-LINE on right

Turn right (northeast) onto the H-LINE (gate), veering left at the H-1000. Follow H-LINE for 1.6 miles

At junction stay on H-LINE for <0.1 miles, then veer left onto the H-3000 for 0.5 miles

Unit 1: Continue on Independence Road another 2.0 miles

Turn right (northwest) onto the I-LINE (gate) and follow for 1.0 mile

Veer right staying on the I-LINE for 0.2 miles

Turn left onto the I-2000 and follow for 0.8 miles

TIMBER NOTICE OF SALE

SALE NAME: AMERICAN IDOL

AGREEMENT NO: 30-081457

AUCTION: February 28, 2008 starting at 10:00 a.m., **COUNTY:** Lewis
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 7 miles northeast of Silver Creek, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees marked with blue paint, pre-existing stumps and down timber existing four years prior to day of sale, bounded by the following: timber sale boundary tags and pink flagging along private property lines in Unit #1; timber sale boundary tags, pink flagging along private property lines and the H-6000 and H-6100 roads in Unit #2; all timber bounded by right-of-way boundary tags on part(s) of Sections 36 all in Township 13 North, Range 2 East, W.M., containing 75 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	16.7	9	1,953				100		924	776	153	
Hemlock	16.9	9	614						379	198	37	
Red cedar	20.7		40							36	4	
Maple	16.7		39							24	15	
Red alder	10.4		26							7	19	
Sale Total			2,672									

MINIMUM BID: \$578,000.00 **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$100,000.00 **SALE TYPE:** Lump Sum

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BID DEPOSIT: \$57,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 35% or less during dry soil conditions. See Clause H-140 and Schedule L for further Harvesting Specifications. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Ground Based Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 13.30 stations of required construction. 5.37 stations of required reconstruction. 33.39 stations of optional construction. 77.60 stations of required pre-haul maintenance. 17.02 stations of light road abandonment and 2.51 stations of medium road abandonment, if road is built. Rock is available at no cost to the Purchaser from the Flynn Road Quarry located on State land in Section 36, Township 13 North, Range 2 East. Rock for construction, reconstruction, or pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. The Purchaser shall stockpile an additional 1,000 cubic yards of 2 INCH MINUS rock at the Flynn Road Quarry by the termination of this contract. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 85% ground-based and 15% cable harvesting.

FEES: \$36,278.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Areas of root rot identified by the fallers or the Contract Administrator shall be marked around the perimeter by high stumping.

TIMBER SALE MAP

SALE NAME: AMERICAN IDOL
AGREEMENT#: 30-081457
TRUST(S): Common School (03)

REGION: Pacific Cascade
COUNTY(S): Lewis
ELEVATION RGE: 730ft. - 1,410ft.

Township 13 North, Range 02 East, W.M.



Sale Area	Existing Road	Fence
Riparian Mgt Zone	Required Pre-Haul Maintenance	Streams
Sale Boundary Tags	Required Construction	Stream Type
Right of Way Boundary Tags	Required Reconstruction	Stream Type Break
Property Line (Pink Flagging)	Optional Construction	Leave Trees
	Old Grade / Trail	Existing Rock Pit
		Gate (PCP 1-1)
		Monumented Corner




DRIVING MAP

SALE NAME: AMERICAN IDOL
AGREEMENT#: 30-081457
TRUST(S): Common School (03)

REGION: Pacific Cascade
COUNTY(S): Lewis
ELEVATION RGE: 730ft. - 1,410ft.

Township 13 North, Range 02 East, W.M.



Highways

Haul Route

Milepost

Off Ramp

Distance Indicator

Gate (PCP 1-1)

Rock Pit

DRIVING DIRECTIONS:

From State Route 122 (milepost 4.5), turn North onto Flynn Road for 1.5 miles
Turn left (north) onto Canyon Road and follow for 0.1 miles
Turn right (east) onto the H-6000 (gate) and follow for 0.2 miles
Unit 1: Turn left (north) onto the H-6003 and follow for 0.1 miles
Unit 2: Continue on the H-6000 for 0.7 miles (H-6100 jct)

Prepared By: Shawn B.

Date: October 16, 2007

TIMBER NOTICE OF SALE

SALE NAME: BELFAIR FIT SORTS

AGREEMENT NO: 30-080614

AUCTION: February 26, 2008 starting at 10:00 a.m.,
South Puget Sound Region Office, Enumclaw, WA

COUNTY: Mason

SALE LOCATION: Units 1 & 2 located approximately 2 miles northeast of Belfair, Unit 3 located approximately 9 miles northwest of Belfair and Units 4 -10 approximately 20 miles west of Belfair.

PRODUCTS SOLD AND SALE AREA: All timber as described in Schedule A bounded by pink flagging in Units 1, 7, 8 and 9; all timber as described in Schedule A bounded by pink flagging and private property lines marked with yellow flagging in Units 2 and 3; all timber as described in Schedule A bounded by pink flagging, private property lines marked with yellow flagging and WMZs marked with pink and blue flagging in Units 4, 5, 6 and 10 on parts of Section 16 Township 23 North, Range 1 West, W.M., Section 11 Township 23 North, Range 2 West, W.M., Sections 5, 8 and 17 Township 22 North, Range 3 West, W.M. and Section 33 Township 23 North, Range 3 West, W.M., containing 389 acres, more or less.

ESTIMATED SALE VOLUMES:

Agreement No.	Sort #	Sort Description Species / DBH	Estimated Volume		Minimum Bid Delivered Price		Total Appraised Value	Bid Deposit
			Tons	Mbf	\$/Tons	\$/Mbf		
30-080730	1	DF/5"+ saw log	2,334	322	\$54.20	N/A	\$126,503.00	\$12,650.00
30-080731	2	WH/5"+ saw log	643	78	\$36.90	N/A	\$23,727.00	\$2,373.00
30-080732	3	Utility 2"+	7,042	867	\$36.70	N/A	\$258,441.00	\$25,844.00
Total			10,019	1,267				

BID METHOD: Sealed Bids

UNIT OF MEASURE: Tonnage Scale

EXPIRATION DATE: Harvester-July 31, 2008
Purchaser-June 30, 2008

ALLOCATION: Export Restricted

PAYMENT SECURITY: To be determined by the State as outlined in Clause P-041 of the Purchaser's Contract.

BIDDING PROCEDURES: Bidding to be allowed on individual log sorts. A separate sealed bid and envelope must be submitted for each sort. Prospective Purchasers may bid on any or all sorts. Complete bidding procedures and auction information may be obtained from the South Puget Sound Region office in Enumclaw, WA or at (360) 825-1631.

HARVEST METHOD: Ground based equipment on slopes 35% and less. Yarding may be restricted during wet weather conditions if excessive rutting occurs in the opinion of the Contract Administrator.

SPECIAL REMARKS: The successful Purchaser(s) will be required to purchase logs from the sale area upon delivery to their location specified in the bid submitted. Logs will be delivered to the Purchaser's delivery location by the State's contract harvester. Purchaser must pay the Forest Excise Tax associated with the log sorts awarded to them per G-252 clause. The tax rate for this sale is 4.2 percent. Purchaser is also responsible for associated weighing costs (P-035). Actual volumes delivered may vary from the estimates. Loads will be weighed and/or scaled at State approved scaling locations. The State reserves the right to determine where logs are authorized to be scaled and weighed. On the day of sale the Purchaser must bring their bid deposit up to 10 percent of their bid price.

The contracts for these sorts will be effective beginning March 10, 2008. Final contract award is contingent upon the State's haul cost analysis. Allow up to 3 business days following bid opening for the State to announce the apparent high bidder. Each sort is subject to confirmation following announcement of the apparent high bidder. Should some sorts not sell, no sorts will be confirmed for sale until either all sorts are sold or a determination is made to withdraw the entire sale.

NOTE: Do to storm damage in December 2007 haul routes in and out of the Tahuya State Forest have changed. As we get closer to the auction date we anticipate the final haul route becoming definitive following bridge installations.

For more information regarding this individual log sort sale, visit our web site [www.wdnr.wa.gov/product sales](http://www.wdnr.wa.gov/product%20sales). If you have questions call Aileen Nichols (253) 732-1822 or Audrey Mainwaring (360) 802-7001 at South Puget Sound Region.

TIMBER SALE MAP

SALE NAME:

AGREEMENT NO:

TRUST(S):

BELFAIR FI SORTS

30-080614

FOREST BOARD TRANSFER (01) & COMMON SCHOOL (03)


REGION:

COUNTY(S):


SOUTH PUGET SOUND

MASON

MAP 1 OF 4 UNITS 1 & 2
TOWNSHIP 23 NORTH, RANGE 1 WEST, W.M.



UNIT 3
TOWNSHIP 23 NORTH, RANGE 2 WEST, W.M.



~~~~~

~~~~~

Boundary marked with pink flagging

Private property boundary marked with yellow flagging

Sale Area

RMZ/WMZ

Recreation Trail

Water Type Break

Wetlands

Water Type

Survey Corner

Locked Gate: Combo 0614

=====

=====

Existing Road

Required Construction

Railroad Tracks

Non-drivable road (may be used as skid trail)

Stream

Drawn By:

Date:


A. Mainwaring

December 18, 2006

TIMBER SALE MAP

SALE NAME:	BELFAIR FI SORTS	REGION:	SOUTH PUGET SOUND
AGREEMENT NO:	30-080614	COUNTY(S):	MASON
TRUST(S):	FOREST BOARD TRANSFER (01) & COMMON SCHOOL (03)		

MAP 2 OF 4 UNITS 5-10
TOWNSHIP 22 NORTH, RANGE 3 WEST, W.M.



LEGEND

~~~~~	Boundary marked with pink flagging		Sale Area		Stream
~~~~~	Private property line boundary marked with yellow flagging		RMZ/WMZ		Water Type Break
~~~~~	WMZ marked with blue and pink flagging		Non-drivable roads (may be used as skid trails)		Wetlands
=====	Existing Road				Water Type
					Survey Corner
					Locked Gate: 0614
					Not useable road

Drawn By: A. Mainwaring  
Date: December 19, 2006



## TIMBER SALE MAP


<b>SALE NAME:</b>	BELFAIR FI SORTS	<b>REGION:</b>	SOUTH PUGET SOUND
-------------------	------------------	----------------	-------------------

**AGREEMENT NO:** 30-080614 **COUNTY(S):** MASON

**TRUST(S):** FOREST BOARD TRANSFER (01) & COMMON SCHOOL (03)

MAP 3 OF 4      UNIT 4

TOWNSHIP 23 NORTH, RANGE 3 WEST, W.M.



ELEVATION RANGE: 440-470 feet

Scale: 1" = 1000'



## UNIT 4 LEGEND

- |       |                                                       |   |                         |
|-------|-------------------------------------------------------|---|-------------------------|
| ~~~~~ | Boundary marked with pink flagging                    | * | Water Type Break        |
| ~~~~~ | Private property boundary marked with yellow flagging |   | Wetlands                |
| ~~~~~ | WMZ boundary marked with pink & blue flagging         |   | Water Type              |
| ~~~~~ | Existing Road                                         |   | Stream                  |
|       |                                                       |   | Survey Corner           |
|       |                                                       |   | Sale Area               |
|       |                                                       |   | RMZ/WMZ                 |
|       |                                                       |   | Locked Gate: Combo 0614 |

Date: December 19, 2006  
Drawn By: A. Mainwaring


TIMBER SALE MAP

SALE NAME:  
AGREEMENT NO:  
TRUST(S):

BELFAIR FIT SORTS  
30-080614  
FOREST BOARD TRANSFER (01) & COMMON SCHOOL (03)

REGION:  
COUNTY(S):

SOUTH PUGET SOUND  
MASON



TIMBER NOTICE OF SALE

**SALE NAME:** *NORTHSIDER II*

**AGREEMENT NO:** 30-081272

**AUCTION:** February 28, 2008 starting at 10:00 a.m., **COUNTY:** Pacific  
Pacific Cascade Region Office, Castle Rock, WA

**SALE LOCATION:** Sale located approximately 7 miles west of Naselle, WA

**PRODUCTS SOLD AND SALE AREA:** All timber, except leave trees tagged out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags, pre-existing stumps and pre-existing down timber existing 3 years prior to the day of sale, bounded by the following: timber sale boundary tags and the A-3300 road in Unit #1; timber sale boundary tags and the A-5600 and Cowan Peak A-Line roads in Unit #2; timber sale boundary tags and the Middle Nemah A-Line road in Unit #3; timber sale boundary tags and the A-3900 road in Unit #4; timber sale boundary tags, rock pit, and the A-5600 and A-5695 roads in Unit #5; all timber bounded by right-of-way boundary tags on part(s) of Sections 8, 9, 10, 15, 16, 17, 21 and 22 all in Township 11 North, Range 9 West, W.M., containing 269 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								UT
						1P	2P	3P	SM	1S	2S	3S	4S	
Hemlock	13.3	8	8,951	65,990	\$4.50						2,448	5,277	1,226	
Douglas fir	13.9	8	635	4,361	\$11.50						186	342	107	
Spruce	13.9		577	3,573	\$4.50						230	281	66	
Silver fir	14.5		136	955	\$4.50						58	56	22	
Red cedar	11.9		61	565	\$18.00							24	37	
Red alder	12.7		51	503	\$29.00						2	14	35	
Sale Total			10,411	75,947										

**MINIMUM BID:** \$4.5/ton (est. value \$392,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$78,400.00 **SALE TYPE:** Tonnage Scale

**EXPIRATION DATE:** September 30, 2010 **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Spruce, Silver fir, Hemlock

**BID DEPOSIT:** \$39,200.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 40% and less during dry soil conditions. See clause H-140 and Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. All merchantable timber within Unit #5 must be removed by August 30, 2008. All timber shall be yarded and hauled within 60 days of being felled or seperated from the stump. Shovel Yarding will not be permitted from September 30 to March 31 unless authorized in writing by the Contract Administrator.

**ROADS:** 62.39 stations of required construction. 314.81 stations of required reconstruction. 50.77 stations of optional construction. 44.15 stations of optional reconstruction. 13.90 stations of medium road abandonment and 44.96 stations of light abandonment, if road is built. Rock for construction and/or reconstruction under this contract may be obtained at no cost to the Purchaser from the Radar Ridge Quarry located in Section 17, Township 11 North, Range 9 West, W.M. Purchaser shall manufacture 7,748 cubic yards truck measure of 2½ INCH MINUS CRUSHED rock, 20,297 cubic yards truck measure of 4 INCH MINUS CRUSHED rock, 11,689 cubic yards truck measure of PIT RUN rock, 180 cubic yards truck measure of LIGHT LOOSE RIPRAP rock and 103 cubic yards truck measure of QUARRY SPALLS rock. All rock source operations shall be conducted as directed by the Contract Administrator and in accordance with an approved development plan to be furnished by the Purchaser for the Northside Pit, located in Section 21, Township 11 North, Range 9 West, W.M. Purchaser shall construct and install a 16 foot by 40 foot steel bridge at station 56+54 on the Middle Nemah A-Line road, in accordance with BRIDGE INSTALLATION DETAIL in the Road Plan. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road work on the 5600, 5690, and 5695 shall be completed by August 30, 2008. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator along the A-5600,

**TIMBER NOTICE OF SALE**

---

Cowan A-Line and Nemah A-Line roads in Units #2, #3 and #4. Also, hauling is restricted from April 1 to August 31 along the C-Line road.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 42% ground-based and 58% cable harvesting.

**FEES:** \$50,000.00 is due on day of sale. \$1.23 per ton is due upon removal. These are in addition to the bid price.


**SPECIAL REMARKS:** There is blown down timber from the most recent storm event both in and outside the sale area. Timing restrictions for hauling on the C-Line road are described as no operation of heavy equipment within the critical marbled murrelet nesting season (April 1 to August 31) during the daily peak activity periods (one hour before official sunrise to two hours after official sunrise and one hour before and after official sunset).

TIMBER SALE MAP

SALE NAME: NORTHSIDER II  
AGREEMENT#: 30-081272  
TRUST(S): Common School (03) & University Transferred (05)

REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 520ft. - 1,720ft.

Township 11 North, Range 09 West, W.M.




Sale Area	Existing Road	Streams
Leave Tree Area	Required Construction	Stream Type
Riparian Mgt Zone	Required Reconstruction	Stream Type Break
Sale Boundary Tags	Optional Construction	Leave Trees
Leave Tree Tags	Optional Reconstruction	Bridge Installation
Right of Way Boundary Tags	Required Abandonment	Existing Rock Pit
		Potential Rock Source
		Monumented Corner

**TIMBER SALE MAP**

**SALE NAME:** NORTHSIDER II  
**AGREEMENT#:** 30-081272  
**TRUST(S):** Common School (03) & University Transferred (05)

**REGION:** Pacific Cascade  
**COUNTY(S):** Pacific  
**ELEVATION RGE:** 520ft. - 1,720ft.

**Township 11 North, Range 09 West, W.M.**





Sale Area	Existing Road	Streams
Leave Tree Area	Required Construction	Stream Type
Riparian Mgt Zone	Required Reconstruction	Stream Type Break
Sale Boundary Tags	Optional Construction	Leave Trees
Leave Tree Tags	Optional Reconstruction	Bridge Installation
Right of Way Boundary Tags	Required Abandonment	Existing Rock Pit
		Potential Rock Source
		Monumented Corner

**TIMBER SALE MAP**

**SALE NAME:** NORTHSIDER II  
**AGREEMENT#:** 30-081272  
**TRUST(S):** Common School (03) & University Transferred (05)

**REGION:** Pacific Cascade  
**COUNTY(S):** Pacific  
**ELEVATION RGE:** 520ft. - 1,720ft.

**Township 11 North, Range 09 West, W.M.**




**TIMBER SALE MAP**

**SALE NAME:** NORTHSIDER II  
**AGREEMENT#:** 30-081272  
**TRUST(S):** Common School (03) & University Transferred (05)

**REGION:** Pacific Cascade  
**COUNTY(S):** Pacific  
**ELEVATION RGE:** 520ft. - 1,720ft.

**Township 11 North, Range 09 West, W.M.**



Sale Area	Existing Road	Streams
Leave Tree Area	Required Construction	Stream Type
Riparian Mgt Zone	Required Reconstruction	Stream Type Break
Sale Boundary Tags	Optional Construction	Leave Trees
Leave Tree Tags	Optional Reconstruction	Bridge Installation
Right of Way Boundary Tags	Required Abandonment	Existing Rock Pit
		Potential Rock Source
		Monumented Corner




**TIMBER SALE MAP**

**SALE NAME:** NORTHSIDER II  
**AGREEMENT#:** 30-081272  
**TRUST(S):** Common School (03) & University Transferred (05)

**REGION:** Pacific Cascade  
**COUNTY(S):** Pacific  
**ELEVATION RGE:** 520ft. - 1,720ft.

**Township 11 North, Range 09 West, W.M.**




Sale Area	Existing Road	Streams
Leave Tree Area	Required Construction	Stream Type
Riparian Mgt Zone	Required Reconstruction	Stream Type Break
Sale Boundary Tags	Optional Construction	Leave Trees
Leave Tree Tags	Optional Reconstruction	Bridge Installation
Right of Way Boundary Tags	Required Abandonment	Existing Rock Pit
		Potential Rock Source
		Monumented Corner

DRIVING MAP

SALE NAME: NORTHSIDER II  
AGREEMENT#: 30-081272  
TRUST(S): Common School (03) & University Transferred (05)

REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 520ft. - 1,720ft.

Township 11 North, Range 09 West, W.M.



Highways

Haul Route

Milepost

Off Ramp

Distance Indicator

Rock Pit

**DRIVING DIRECTIONS:**

Units 1, 4, & 5: From US Highway 101 (milepost 29.4), turn East onto the C-LINE and follow for 1.0 miles  
Veer right (east) continuing on the C-LINE for 0.7 miles  
Unit 1 & 4 - Turn left (northeast) onto the C-1300 and follow for 1.0 miles  
Turn left (north) onto the E-LINE and follow for 0.3 miles  
Turn right (north) onto the A-3300 and follow for 0.4 miles to Unit 1  
Unit 4 - Continue on the A-3300 for 1.7 miles  
Turn right (east) onto the A-LINE and follow for 1.0 miles to Unit 4  
Unit 5 - Continue on the C-LINE for another 0.3 miles  
Turn left (northeast) onto the E-LINE and follow for 0.6 miles to Unit 5

Units 2 & 3: From State Route 4 (milepost 3), turn North onto the C-LINE and follow for 1.0 miles  
Turn right (northeast) onto Radar Rd for 0.4 miles  
Veer left (north) onto the C-4000 for 1.1 miles, then stay right (east) on the C-4000 for 0.9 miles  
Stay left (east) on the Middle Nemah A-LINE and follow for 1.1 miles to Unit 2  
Continue on the Middle Nemah A-LINE for 1.0 miles then turn right staying on the A-LINE for another 0.6 miles  
Veer left (north) staying on the Middle Nemah A-LINE for 0.7 miles to Unit 3

Prepared By: Shawn B.

Creation Date: December 18, 2007

TIMBER NOTICE OF SALE

**SALE NAME:** *P&E RIDGE BLOWDOWN*

**AGREEMENT NO:** *30-081559*

**AUCTION:** February 28, 2008 starting at 10:00 a.m., **COUNTY:** Pacific  
Pacific Cascade Region Office, Castle Rock, WA

**SALE LOCATION:** Sale located approximately 7 miles west of Menlo, WA

**PRODUCTS SOLD AND SALE AREA:** All timber as described in Schedule A, except snags and pre-existing down timber existing 5 years prior to the day of sale, bounded by the following: the P&E Mainline road with all other boundaries as described in Schedule A in Unit #1; timber sale boundary tags and the P&E Mainline in Unit #2; timber sale boundary tags and the MC 4000 and MC 4200 roads in Unit #5. All blown down timber as described in Schedule A bounded by timber sale boundary tags and the P&E Mainline and P&E 2900 roads in Unit #3; timber sale boundary tags and the RCP 100 road in Unit #4; all blown down timber marked with orange paint between Units #2 and #3 north of the P&E Mainline on part(s) of Sections 24 all in Township 13 North, Range 7 West, Sections 7, 19, 20, 21, 28, 29, 34 and 35 all in Township 13 North, Range 6 West, W.M., containing 136 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	15.6	6	3,216	\$88.00						1,863	1,132	221	
Douglas fir	20.8	6	982	\$191.00						779	174	29	
Red alder	14.9		115	\$361.00						16	60	39	
Spruce	18.6	5	81	\$80.00						45	31	5	
Red cedar	13.9		26	\$624.00							23	3	
Sale Total			4,420										

**MINIMUM BID:** \$88/MBF (est. value \$534,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** MBF Scale

**EXPIRATION DATE:** June 30, 2009 **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Hemlock

**BID DEPOSIT:** \$53,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable and shovel harvesting equipment with shovel harvesting equipment being restricted to slopes of 35% or less. See Clause H-140 and Schedule A for further Harvesting Specifications. Standing live trees or snags felled for safety reasons may only be removed with Contract Administrator approval. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Shovel Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

**ROADS:** 48.00 stations of optional construction to be located and marked by the Purchaser. 80.00 stations of required pre-haul maintenance. 3.00 stations of road abandonment, if road is built. Rock for construction and/or pre-haul maintenance under this contract may be obtained from three sources on State land at no charge to the Purchaser. The Upper Mill Ridge Quarry located in Section 21 and the Walville Quarry located in Section 23, both in Township 13 North, Range 6 West, and the P&E Ridge Quarry located in Section 24, Township 13 North, Range 7 West, W.M. Rock for construction and/or pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to July 1 unless authorized in writing by the Contract Administrator.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** The sale acres for Unit #1 were determined by aerial flight and photo delineation. The sale acres for Units #2 through #5 were determined by GPS. The sale area was cruised using a 1/20th fixed plot cruise method. Harvesting activities are estimated to be approximately 40% shovel and 60% cable harvesting.

**FEES:** \$50,000.00 is due on day of sale. \$10.94 per MBF is due upon removal. These are in addition to the bid price.

TIMBER NOTICE OF SALE



---

**SPECIAL REMARKS:** Purchaser shall, as part of the plan of operations, prepare an acceptable harvest plan, mark the boundaries for the RMZs in Units #1 and #4, leave trees in Units #2 and #5, roads and landings in Units #1, #2 and #5, and the down wood requirements for the owl areas (Special Management Area as shown on the timber sale map) in Units #1 and #4, as detailed in Schedule A. Gates shown on the driving map are open or are not locked.

TIMBER SALE MAP

SALE NAME: P&E RIDGE BLOWDOWN  
AGREEMENT#: 30-081559  
TRUST(S): SF Board Transfer (01), SF Board Purchase (02), Common School (03),  
Agricultural School (04), & Scientific School (10)  
Township 13 North, Range 06 West, W.M.



REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 840ft. - 1,880ft.



TIMBER SALE MAP

SALE NAME: P&E RIDGE BLOWDOWN  
AGREEMENT#: 30-081559  
TRUST(S): SF Board Transfer (01), SF Board Purchase (02), Common School (03),  
Agricultural School (04), & Scientific School (10)  
Township 13 North, Range 06 West, W.M.



REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 840ft. - 1,880ft.



TIMBER SALE MAP

SALE NAME: P&E RIDGE BLOWDOWN  
AGREEMENT#: 30-081559  
TRUST(S): SF Board Transfer (01), SF Board Purchase (02), Common School (03),  
Agricultural School (04), & Scientific School (10)  
Township 13 North, Range 06 West, W.M.



REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 840ft. - 1,880ft.



TIMBER SALE MAP

SALE NAME: P&E RIDGE BLOWDOWN  
AGREEMENT#: 30-081559  
TRUST(S): SF Board Transfer (01), SF Board Purchase (02), Common School (03),  
Agricultural School (04), & Scientific School (10)  
Township 13 North, Range 06 West, W.M.

REGION: Pacific Cascade  
COUNTY(S): Pacific  
ELEVATION RGE: 840ft. - 1,880ft.





DRIVING MAP

SALE NAME: P&E RIDGE BLOWDOWN

AGREEMENT#: 30-081559


TRUST(S): SF Board Transfer (01), SF Board Purchase (02), Common School (03),  
Agricultural School (04), Scientific School (10)

REGION: Pacific Cascade

COUNTY(S): Pacific

ELEVATION RGE: 840ft. - 1,880ft.

Township 13 North, Range 06 West, W.M.



Highways

Haul Route

Milepost

Off Ramp

Distance Indicator

Rock Pit

**DRIVING DIRECTIONS:**

Units 1-3: From State Route 6 (milepost 8.8), turn East onto Green Creek Road and follow for 1.5 miles  
Turn right (east) onto the P&E Mainline and follow for 6.9 miles to P&E Ridge Quarry  
Units on left (north) side of road up to junction of Mill Creek Mainline  
Unit 4: From State Route 6 (milepost 22.2), turn North onto the RCP Mainline and follow for 0.8 miles  
Turn left (north) onto the RCP-100 and follow for 1.6 miles to unit  
Unit 5: From State Route 6 (milepost 4.4), turn East onto Camp One Road and follow for 0.6 miles  
Turn right (east) onto Lilly Weaton Road and follow for 0.7 miles  
Turn left (east) onto Mill Creek County Road and follow for 6.5 miles  
Road name changes to Mill Creek Mainline - Follow for another 4.0 miles  
Turn left (north) onto the MC-4000 and follow for 1.3 miles



TIMBER NOTICE OF SALE

**SALE NAME:** WHISKERS PC

**AGREEMENT NO:** 30-077633

**AUCTION:** February 26, 2008 starting at 10:00 a.m., **COUNTY:** Pierce  
South Puget Sound Region Office, Enumclaw, WA

**SALE LOCATION:** Sale located approximately 5 miles northeast of Elbe

**PRODUCTS SOLD AND SALE AREA:** All timber except those trees described in Schedules B and C bounded by white timber sale boundary tags, blue special management tags, the 6 Road and those trees described in Schedule D in Unit #1; all timber except those trees described in Schedules B and C bounded by white timber sale boundary tags, the 6 and 65B Roads and those trees described in Schedule D in Unit #2; all timber except those trees described in Schedules B and C bounded by white timber sale boundary tags, the 6 Road and those trees described in Schedule D in Unit #3; all timber as described in Schedule E bounded by white timber sale boundary tags and blue special management unit boundary tags in Unit #4 the riparian thinning area, except those trees described in Schedules B and C; all timber bounded by orange right of way boundary tags, on part(s) of Sections 10, 11, 14 and 15 all in Township 15 North, Range 5 East, W.M., containing 213 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								UT
					1P	2P	3P	SM	1S	2S	3S	4S	
Hemlock	12.1	8	2,552	\$102.00						471	1,537	544	
Douglas fir	16.3	10	1,419	\$216.00			8	52		583	643	133	
Silver fir	20.1	8	898	\$92.00				79		453	290	76	
Red alder	12.9		310	\$458.00						52	163	95	
Red cedar	15.3		50	\$491.00							37	13	
Cottonwood	13		17	\$20.00									17
Noble fir	12.7		14	\$99.00							10	4	
Sale Total			5,260										

**MINIMUM BID:** \$102/MBF (est. value \$847,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$120,000.00 **SALE TYPE:** MBF Scale

**EXPIRATION DATE:** October 31, 2010 **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Hemlock

**BID DEPOSIT:** \$84,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Ground based on slopes 40 percent and less. Cable equipment on slopes 40 percent and greater. If Purchaser elects to shovel log, shovel logging shall be in accordance with the attached Schedule A, which is part of this contract. Shovel logging may be restricted during wet weather conditions if excessive rutting occurs in the opinion of the Contract Administrator.

**ROADS:** 5.52 stations of required reconstruction. 74.98 stations of optional construction. 51.95 stations of required prehaul maintenance. 16.26 stations of required abandonment. 6.75 stations of required deactivation. 54.30 stations of abandonment, if constructed. Cross section designs are available at the South Puget Sound Region office upon request. Purchaser maintenance on the 65B, 65B1, 65B2 and 65C Roads and Spurs 1, 87 and 871. Designated maintenance on all other roads used. Road construction will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator, nor at all on weekends or state recognized holidays. The hauling of forest products will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator, nor at all on weekends or state recognized holidays.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acreage was determined by traversing boundaries with GPS. Units were cruised using a variable plot sample with a BAF of 54.45 on a 200x400 foot grid. Right of Way and regeneration harvest areas were cruised using a variable plot sample with a BAF of 54.45.

**FEES:** \$71,179.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

**TIMBER NOTICE OF SALE**

**SPECIAL REMARKS:** NOTE - The cruised volume includes the regeneration harvest areas volume identified in Schedule D - Regeneration Harvest Areas: Comprising of approximately 21 acres of purchaser select regeneration harvest areas. There is approximately 332 mbf in Unit #1, 182 mbf in Unit #2 and 478 mbf in Unit #3 for a total of 992 mbf. These numbers are subject to change based on the harvest area selections. Factors that will influence the selection are 4 +- acres of Red Alder in Unit #1 and 4 +- acres of Red Alder and fingers of blowdown in Unit #3. These areas will be regeneration harvest openings by prescription and through removal of the blowdown timber. There may be no vehicle access due to weather conditions, however you will still be able to access the sale via a snowmobile and/or snowshoes.

TIMBER SALE MAP

SALE NAME:

Whiskers PC

AGREEMENT NO:

30-077633

TRUST(S):

Forest Board Transfer (01), CEP & RI (06)


REGION:

South Puget Sound

COUNTY(S):


Pierce

MAP 1 OF 2  
Township 15 North, Range 5 East, W.M.




LEGEND

- ~~~~~ White Timber Sale Boundary tags
- ~o~ Blue Special Management Unit Boundary tags
- ~~~~~ Orange Right of Way Tags
- Optional Construction
- ▬ Required Pre-haul Maintenance
- ⌋ Gate
- ⌘ Rock Pit
- Stream
- Horse Trail



Drawn By: D. Eide  
Date: July 12, 2007  
Scale: 1" = 1000'  
Elevation: 2,700 ft.



Note: All gates shown locked with combination lock #7633.

10 foot contours


**SALE NAME:** Whiskers PC  
**AGREEMENT NO:** 30-077633  
**TRUST(S):** Forest Board Transfer (01), CEP & RI (06)

**REGION:** *South Puget Sound*  
**COUNTY(S):** *Pierce*

# Whiskers PC Vicinity Map

## MAP 2 OF 2

Note: All gates shown locked with combination lock #7633, except the private gate on the Scott-Turner Road.



TIMBER NOTICE OF SALE

**SALE NAME:** *MEDIAN*

**AGREEMENT NO:** *30-080592*

**AUCTION:** February 25, 2008 starting at 10:00 a.m., **COUNTY:** Skagit  
Northwest Region Office, Sedro Woolley, WA

**SALE LOCATION:** Sale located approximately 4 miles southeast of Wickersham

**PRODUCTS SOLD AND SALE AREA:** All timber bounded by white timber sale boundary tags and young forest stands in Unit #1, except trees marked with yellow paint on the bole and at root collar, and forest products tagged out by yellow leave tree tags.

All timber bounded by white timber sale boundary tags and the SK-6422 road in Unit #2, except trees marked with yellow paint on the bole and at root collar, and forest products tagged out by yellow leave tree tags.

All timber bounded by white timber sale boundary tags in Unit #3, except trees marked with yellow paint on the bole and at root collar, and forest products tagged out by yellow leave tree tags. All timber bounded by orange right of way tags.

The above described timber products are located on part(s) of Sections 2, 11, 13 and 14 all in Township 36 North, Range 5 East, Sections 18 all in Township 37 North, Range 5 East, W.M., containing 121 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	23	6	3,207			48	399		1,858	808	93	
Hemlock	13	6	1,667				17		466	875	309	
Red cedar	14		576							501	74	
Red alder	16		377						114	150	113	
Maple	12		30							9	21	
Cottonwood	32		28	17					10		1	
Sale Total			5,885									

**MINIMUM BID:** \$1,310,000.00 **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** Lump Sum

**EXPIRATION DATE:** September 30, 2010 **ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$131,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel on slopes 25% or less. Ground Based Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED YARDING ONLY) to reduce soil damage and erosion.

**ROADS:** 49.76 stations of required construction. 115.18 stations of required reconstruction. 65.42 stations of optional construction. 26.50 stations of optional reconstruction. 65.42 stations of road to be abandoned if built.

Development of an existing gravel source (Section 2 Pit) at station 17+00 of the MD-03 Road will involve processing rock to generate gravel ballast. This rock is available at no cost on State land.

Development of an existing hardrock source (CT-51 Pit) at station 268+50 of the CT-ML Road will involve drilling, shooting, and processing rock to generate riprap and 3-inch-minus ballast. This rock is available at no cost on State land.

Development of an existing hardrock source (Extra Innings Hardrock Pit) at station 30+00 of the MJ-34 Road will involve drilling, shooting, and processing rock to generate riprap. This rock is available at no cost on State land.

Acquisition of approximately 30 cubic yards ¾-inch-minus crushed rock from a commercial rock source for use on the steel bridge deck and as a leveling course for the pre-cast concrete footings.

**TIMBER NOTICE OF SALE**

---

This project is estimated to use approximately 10,410 cubic yards of ballast and approximately 1,532 cubic yards of riprap.

Acquisition and installation of a 40 foot span, pre-constructed, modular type, painted steel bridge with pre-cast concrete footings on the CT-ML road.

Road construction, road reconstruction, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS and Hand traverse. 130 Acres gross. 8.2 acres deducted for leave tree area and 0.4 acres deducted for existing road surface. 121.4 acres net. Cruised using variable plot method. Expansion factor used is 54.45 for Unit #1, expansion factor of 46.95 for Unit #2, and an expansion factor of 62.50 for Unit #3. Sighting height is 4.5 feet. Grid size plot spacing is 300 X 300 feet for Unit#1, 300 X 150 feet for Unit #2, and 200 X 125 for Unit #3. The plot ratio cruise/count was 1:1 in Unit #1 for 36 plots, 19:7 for 26 plots in Unit #2, and all 5 plots were cruised in Unit #3, for a total of 67 plots.

**FEES:** (1) Purchaser shall furnish a check to the State made payable to Sierra Pacific Industries in the amount of \$500.00, on the day of sale for permit #55-081236. (2) \$52,978.25 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** From April 1 to August 31, in sub-units 1E, 1F, 1G, and 2C, no tree falling, yarding, or operation of any heavy equipment will be allowed from 1 hour before official sunrise to 2 hours after official sunrise and from 1 hour before official sunset to 1 hour after official sunset. This requirement can not be waived.



TIMBER SALE PROSPECTUS MAP



SALE NAME:  
AGREEMENT NO:  
TRUST(S):

Median Unit 1  
30-080592  
State Forest Board Transfer (01)

REGION:  
COUNTY(S):

Northwest  
Skagit

Township 36 North, Range 05 East, W.M.





# TIMBER SALE PROSPECTUS MAP

SALE NAME: Median Unit 2  
AGREEMENT NO: 30-080592  
TRUST(S): State Forest Board Transfer (01)

REGION: Northwest  
COUNTY(S): Skagit

Township 36 North, Range 05 East, W.M.



**Legend**



- Sale Area
- RMZ
- Tagged Leave Tree Areas
- Boundary Tags (White)
- Right of Way Tags (Orange)
- Existing Roads
- Required Construction
- Optional Reconstruction
- Creeks
- Water Types
- Dispersed Leave Trees
- Monumented Corner
- Gates
- Bridges
- Rockpits

# TIMBER SALE PROSPECTUS MAP

SALE NAME: Median Unit 3  
AGREEMENT NO: 30-080592  
TRUST(S): State Forest Board Transfer (01)

REGION: Northwest  
COUNTY(S): Whatcom

Township 37 North, Range 05 East, W.M.



## Legend

- /// Sale Area
- ▨ Tagged Leave Tree Areas
- ▤ RMZ
- ~~~~ Boundary Tags (White)
- == Existing Roads
- Creeks
- [4] Water Type
- 🌲 Dispersed Leave Trees
- Gates

Drawn By: C McDonald  
Date: August 31, 2007  
Elevation: 1000ft



TIMBER NOTICE OF SALE

**SALE NAME:** GINGERBREAD HARDWOOD

**AGREEMENT NO:** 30-080593

**AUCTION:** February 25, 2008 starting at 10:00 a.m.,  
Northwest Region Office, Sedro Woolley, WA

**COUNTY:** Skagit

**SALE LOCATION:** Sale located approximately 6 miles NE of Sedro Woolley

**PRODUCTS SOLD AND SALE AREA:** All timber bounded by white timber sale boundary tags, the CR-ML Road, the CR-33 Road, recently harvested areas and young stands, except trees marked with blue paint on the bole and root collar, and forest products tagged out by yellow leave tree area tags on part(s) of Sections 2 and 3 all in Township 35 North, Range 5 East, Sections 34 and 35 all in Township 36 North, Range 5 East, W.M., containing 55 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Red alder	15		879						316	165	397	
Red cedar	14		138							105	33	
Cottonwood	27		107	49				39	9		10	
Hemlock	11	5	49							26	24	
Douglas fir	12	5	10						5	2	3	
Maple	20		1								1	
Sale Total			1,184									

**MINIMUM BID:** \$481,000.00

**BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$96,200.00

**SALE TYPE:** Lump Sum

**EXPIRATION DATE:** September 30, 2008

**ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$48,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

**ROADS:** 1.00 stations of required reconstruction. 24.59 stations of optional construction. 24.59 stations of road to be abandoned if built.

Development of an existing gravel source (Section 2 Pit) at milepost 0.3 of the HO-2010 Road will involve processing rock to generate gravel ballast. This rock is available at no cost on State land in Sec. 2, T35N, R6E, W.M.

On site boulders excavated during road construction or reconstruction (CR-34, CR-3402, CR-35, and CR-38 road prisms) may be used as riprap for culvert inlets and outlets.

Total ballast and riprap needed for road work is estimated to be approximately 3,075 cubic yards of ballast and 51 cubic yards of riprap.

Road construction, road reconstruction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS traverse. 57.6 acres gross. 3.0 acres deducted for green tree retention clumps. 54.6 acres net. Cruised using variable plot method. Expansion factor used is 40.00. Sighting height is 4.5 feet. Grid size plot spacing is 234 x 200feet in the Unit. Plot ratio cruise count is 1:1 in the Unit. 50 plots were taken in the Unit.



**FEES:** \$15,697.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** None.

TIMBER SALE MAP

SALE NAME: Gingerbread  
AGREEMENT NO: 80593  
TRUST(S): State Forest Board Transfer (01)

REGION: Northwest  
COUNTY(S): Skagit



Legend

- Sale Area
- RMZ
- Type 1-5 Streams
- Sale Area Boundary Tags
- Non-Tagged Boundary (Cutline)
- Existing Roads
- Required Reconstruction
- Optional Construction
- Tagged Leave Tree Areas
- Scattered Leave Trees
- Property/Section Corners
- Rock Pit
- Landings
- Bridge
- Gate

Drawn By: C. McDonald  
Date: July 31, 2007  
Scale: 1" = 1000'  
Elevation: 1800 ft.  
Version: 1.3

TIMBER NOTICE OF SALE

**SALE NAME:** TREMBLE HARDWOOD

**AGREEMENT NO:** 30-080575

**AUCTION:** February 25, 2008 starting at 10:00 a.m.,  
Northwest Region Office, Sedro Woolley, WA

**COUNTY:** Snohomish

**SALE LOCATION:** Sale located approximately 9 miles northeast of Arlington

**PRODUCTS SOLD AND SALE AREA:** All timber bounded by white timber sale boundary tags, young plantations and property lines, except trees marked with blue paint, forest products tagged out with yellow leave tree tags, dead and downed cedar stumps, logs and snags, in Unit #1. All timber bounded by white timber sale boundary tags, young plantations, property lines and the EB-ML Road, except trees marked with blue paint, forest products tagged out with yellow leave tree tags, dead and downed cedar stumps, logs and snags, in Unit #2. All timber bounded by orange right of way tags. The above described products on part(s) of Sections 25, 26 and 35 all in Township 32 North, Range 6 East, W.M., containing 124 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Red alder	16		1,445						611	379	455	
Douglas fir	17	6	1,015						635	283	96	
Hemlock	13	6	667						282	280	105	
Maple	14		187						96	8	83	
Red cedar	13		116							86	31	
Birch	9		19								19	
Sale Total			3,449									

**MINIMUM BID:** \$1,117,000.00

**BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00

**SALE TYPE:** Lump Sum

**EXPIRATION DATE:** December 31, 2009

**ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$111,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel on slopes 25% or less. Ground Based Yarding will not be permitted from October 15 to May 1 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

**ROADS:** 44.01 stations of required construction. 70.34 stations of required reconstruction. 12.13 stations of optional reconstruction. 12.13 stations of new road to be abandoned if built.

Development of an existing hardrock source (EB-1106 Hardrock Pit) at station 30.11 of the EB-11 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 237 cubic yards of rip rap and approximately 11,469 cubic yards of 3-inch-minus ballast. This rock is available at no cost on State land.

Road construction, road reconstruction, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS traverse. 134.2 acres gross. 7.8 acres deducted for green tree retention clumps and 2.6 acres deducted for existing roads and rock pit. 123.8 acres net. Cruised using variable plot method. Expansion factor used is 46.95 in Units #1 and #2 and 20.00 in Right-Of-Way. Sighting height is 4.5 feet. Grid size plot spacing is 420 x 200 feet in Unit #1, 400 x 200 in Unit #2, and 550 feet apart in Right of Way. Plot ratio cruise count is 1:1. 43 plots were taken in Unit #1, 19 plots taken in Unit #2, and 5 plots were taken in the Right-Of-Way, for a total of 67 plots.


**FEES:** \$45,699.25 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** None.

TIMBER SALE MAP

SALE NAME: Tremble Hardwood  
AGREEMENT NO: 80575  
TRUST(S): 01 Forest Board Trust

REGION: Northwest  
COUNTY(S): Snohomish  
ELEVATION: 400' - 1,600'





TIMBER NOTICE OF SALE

**SALE NAME:** WHITEHORSE FLATS PC

**AGREEMENT NO:** 30-081416

**AUCTION:** February 25, 2008 starting at 10:00 a.m.,  
Northwest Region Office, Sedro Woolley, WA

**COUNTY:** Snohomish

**SALE LOCATION:** Sale located approximately 3 miles southwest of Darrington

**PRODUCTS SOLD AND SALE AREA:** All timber designated for removal as described in Schedule B bounded by white timber sale boundary tags, adjacent forest plantations, the AS-ML road, and the AS-21 road.

All timber bounded by orange right of way tags, except that title to the timber within the right of way tags of the corresponding road is not conveyed to the Purchaser unless the related road segment is actually constructed.

The above described products on part(s) of Sections 16, 17, 20, 21 and 28 all in Township 32 North, Range 9 East, W.M., containing 157 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								UT
						1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	14	6	778	5,166	\$21.55						302	341	135	
Hemlock	10	6	717	4,990	\$21.55						29	188	500	
Red alder	12		684	4,895	\$40.00						87	190	407	
Cottonwood	12		67	398	\$2.00						17		50	
Maple	13		38	349	\$40.00							25	13	
Red cedar	12		32	243	\$116.00							21	11	
Sale Total			2,316	16,041										

**MINIMUM BID:** \$21.55/ton (est. value \$405,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$81,000.00 **SALE TYPE:** Tonnage Scale

**EXPIRATION DATE:** September 30, 2009 **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Hemlock, Douglas fir combined.

**BID DEPOSIT:** \$40,500.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable, feller-buncher/harvester, forwarder and, use of tracked skidders (BUT tracked skidders shall be limited to pre-approved skid trails and only allowed during dry periods as authorized by the Contract Administrator) in ground-based harvest areas. No harvest activities shall occur from December 1 through March 31 due to wildlife habitat prime usage per the blacktail winter range critical habitat plan. No thinning/harvest or related activities (herbicide spraying, road maintenance, hauling) associated with this project are to occur from November 1 to March 15, per bald eagle management plan. Cutting and yarding will not be permitted during the bark slippage season, unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1 to July 15, but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season, the Purchaser will be required to provide a plan outlining mitigation measures. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

**ROADS:** 113.85 stations of optional construction. 113.85 stations of road to be abandoned if built.

Development of an existing gravel source (Barco Gravel Pit) at milepost 1.6 of the BO-ML Road will involve clearing, stripping, and processing rock to generate approximately 3,497 cubic yards gravel ballast. This rock is available at no cost on State land.

Development of an existing hardrock source (Montague Creek Hardrock Pit) at milepost 0.1 of the MG-4004 Road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 27 cubic yards riprap. This rock is available at no cost on State land.

Road construction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted

**TIMBER NOTICE OF SALE**

---

from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS traverse. 157 acres gross. 157 acres net. Cruised using variable plot method. Expansion factor used is 40.00. Sighting height is 4.5 feet. Grid size plot spacing is 400 x 400 feet in the Unit and 500 feet apart in right of way. Plot ratio cruise count is cruise all. 60 plots were taken in the Unit and 8 plots taken in right of way, for a total of 68 plots.

**FEES:** \$27,016.75 is due on day of sale. \$1.30 per ton is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** (1) Blue special management tags demarcate the beginning edge of the WMZ. Uplands and WMZ prescriptions are identical. (2) Utility price for P-024 Clause is \$2.00 per Ton. (3) WDFW, DNR and Stillaguamish tribal biologists will conduct roost observations throughout December 2007 and early January 2008. According to the original roost plan, the 1st and 2nd weeks of January are the peak activity periods for this roost. WDFW will arrive at a determination concerning roost activity within the proposed unit boundary by January 10, 2008. Changes to the unit boundary will be requested before or on January 10, 2008. If necessary, an amended Bald Eagle Management Plan will be issued on that date.

**Schedule B**  
**Whitehorse Flats PC Thinning Prescription**

Unit 1:

Cut all red alder

Cut bigleaf maple 6-14 inches dbh

Cut western hemlock 7-12 inches dbh

Cut Douglas-fir 6-14 inches dbh

Cut or girdle all black cottonwood*

*If black cottonwood is cut it must be yarded and hauled from site. If girdling, two bands to be cut from the bark, each two inches wide and fully circling the bole.

SPECIAL THINNING CONDITIONS: In areas where prescription trees do not exist, do not put in corridors. Harvested openings may not exceed 1/4 acre in conifer dominated stands.

Conifer trees meeting prescription shall not be removed if removal would create an opening greater than 1/20th acre.

CERTIFICATION OF FALLERS AND YARDER OPERATORS – SEE CLAUSE H-011 OF THE CONTRACT.

The Contract Administrator and Faller/Harvester Operator will jointly review the take tree selection criteria as outlined in Schedule B of the contract.

In conjunction with the Contract Administrator, the Faller/Harvester Operator will mark a designated area as a test plot within the sale area boundary. Satisfactory thinning of the test plot completes the certification process.

Certifications will be issued to individuals when they demonstrate to the contract Administrator their ability to perform within the requirements set forth in the contract.

COMPLIANCE:

Determination of damage will be calculated by comparing the percentage of damaged trees to the total number of standing trees. A 1/20 acre fixed radius plot (26.3 feet) will be measured to determine trees per acre. The number of trees in a plot will be multiplied by 20 to determine the trees per acre for that plot. The average of all plots in a unit will determine the trees per acre for that damage unit. Only trees greater than or equal to 6.5" DBH will be measured.

DAMAGE UNITS:

Unit divisions for assessment of damage per contract clauses H-012 and D-040 are delineated on the Damage Units Map - Schedule D.

ADDITIONAL CLAUSES:

1. If a road is not constructed, the right-of-way timber will NOT be cut.
2. BARK SLIPPAGE: Cutting and yarding will not be permitted during the bark slippage season, unless authorized in writing by the Contract Administrator. This season is estimated to run from April 1 to July 15, but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season, the Purchaser will be required to provide a plan outlining mitigation measures.
3. No tops or limbs will be allowed to accumulate on any landings. Tops and limbs will be redistributed in the unit to the satisfaction of the Contract Administrator.

4. Tracked skidder operation is allowed only during dry periods and their use will be limited to designated skid trails.

5. All equipment must operate on a mat of its own slash.

6. Cable Areas:

Landings will be located to provide for parallel yarding whenever possible. Corridors will be limited to 12 feet including rub trees. Corridors will be at least 100 feet apart when parallel as measured from the center of the corridors. Where possible, corridors should be located in a manner to minimize the damage to or removal of leave trees. When corridors are field located, only leave trees within 3-5 feet of the center to the corridor should be removed prior to yarding. Following completion of yarding of each corridor, damaged leave trees within 6 feet of the center of the corridor may be felled and yarded to the landing. It is not required to remove all leave trees from the 12-foot corridor. Additional corridors will not be permitted unless authorized in writing by the Contract Administrator.


7. Ground-Based Areas: Ground-based yarding corridors will be limited to 14 feet including rub trees and no less than 70 feet apart unless otherwise authorized in writing by the Contract Administrator.

8. WMZ thinning to take place behind blue Special Management Unit Boundary tags. This thinning follows the same prescription as the rest of the unit. No ground-based equipment is permitted behind the blue tags unless authorized in writing by the Contract Administrator.

TIMBER SALE MAP


SALE NAME: Whitehorse Flats PC  
AGREEMENT NO: 30-081416  
TRUST(S): Forest Transfer (01)

REGION: Northwest  
COUNTY(S): Snohomish  
ELEVATION: 550 - 850 feet



**Legend**

<b>Symbols</b>	<b>Streams</b>
* Water Type Break	➤ Type 1-5
⊙ Landing	⋯ RMZ/ WMZ
⏟ Wetlands	
⊠ Water Type	<b>Units</b>
◆ Survey Corner	~ ~ ~ Sale Boundary Tags
— Gate	~ ~ ~ Management Unit Boundary Tags
	~ ~ ~ R/W Boundary Tags
<b>Roads</b>	— Logged Area Boundary
— Existing Road	<b>Logging Methods</b>
- - - Optional Construction	/// Cable
	/// Shovel
	WMZ



Drawn By: D. Klingbiel  
Date: July 20, 2007



TIMBER NOTICE OF SALE

**SALE NAME:** EQUINOX

**AGREEMENT NO:** 30-081682

**AUCTION:** February 25, 2008 starting at 10:00 a.m., **COUNTY:** Snohomish  
Northwest Region Office, Sedro Woolley, WA

**SALE LOCATION:** Sale located approximately 2 miles Southeast of Monroe, Washington.

**PRODUCTS SOLD AND SALE AREA:** All timber bounded by white timber sale boundary tags, plantation edges, property boundaries, the PP-ML and PP-07 roads, except for trees marked with blue paint on the bole and root collar, dead cedar stumps, logs, and snags, forest products tagged out with yellow leave tree tags, and forest products tagged out with blue special management tags, in Unit #1.

All timber bounded by white timber sale boundary tags, plantation edges, property boundaries, and the HR-ML road, except for trees marked with blue paint on the bole and root collar, dead cedar stumps, logs, and snags, forest products tagged out with yellow leave tree tags, and forest products tagged out with blue special management tags, in Unit #2.

All timber as described for removal in Schedule B located in the WMZ areas tagged out by blue special management tags within Units #1 and #2. All timber bounded by orange right of way tags on part(s) of Sections 17 and 20 all in Township 27 North, Range 7 East, W.M., containing 98 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	22	5	3,572				495		2,182	737	158	
Hemlock	14	8	845						440	307	98	
Red cedar	18		310							278	32	
Red alder	11		68							17	51	
Cottonwood	25		39	27					10		2	
Maple	13		33							16	17	
Sale Total			4,867									

**MINIMUM BID:** \$1,390,000.00 **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** Lump Sum

**EXPIRATION DATE:** September 30, 2009 **ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$139,000.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel on slopes 25% or less. Ground based harvest operations beyond blue Special Management Unit Boundary tags will be allowed ONLY between June 1 and October 15. Cutting and yarding beyond blue Special Management Unit Boundary tags will not be permitted during the bark slippage season unless authorized in writing by the contract administrator. This season is estimated to run from April 1 to July 15 but will vary dependent on weather conditions. If permission is granted to operate during the bark slippage season the purchaser will be required to provide a plan outlining mitigation measures. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and erosion.

**ROADS:** 43.26 stations of required reconstruction. 62.89 stations of optional construction. 62.89 stations of optional construction to be abandoned after use. 28.13 stations of existing road to be abandoned.

Development of an existing hardrock source at station 7.00 of the PP-07 road will involve clearing, stripping, drilling, shooting, and processing rock to generate approximately 81 cubic yards of rip rap and approximately 4,160 cubic yards of 3-inch-minus ballast. This rock is available at no cost on State land.

Aquisition of aproximately 720 cubic yards of 1 ¼ inch minus crushed rock from a commercial rock source for reconstruction of the HR-ML will be necessary.

Development of a proposed hardrock source (Extra Innings Pit) at station 22+00 of the HO-2940 Road will involve clearing, stripping, drilling, shooting, and processing rock to

**TIMBER NOTICE OF SALE**

---

generate approximately 130 cubic yards of riprap and approximately 3,750 cubic yards of 3-inch-minus ballast rock. This rock is available at no cost on State land in Section 27, Township 36 North, Range 6 East, W.M.

Road construction, road reconstruction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. Road construction will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS traverse. 85.2 acres gross. 18.9 acres added for WMZ/RMZ management. 4.1 acres deducted for leave tree clumps. 2.1 acres deducted for existing road surface. 98 acres net. Cruised using variable plot method. Expansion factor used was 54.45 for units #1 and #2, while an expansion factor of 40 was used for WMZ. Sighting height is 4.5 feet. Grid spacing is 400' x 200'. 18 plots, cruised at a cruise/count ratio of 1:1, were taken in Unit #1. 22 plots, cruised at a cruise/count ratio of 14:8, were taken in Unit #2, and 10 plots, all cruised, were taken in the WMZ.

**FEES:** \$64,470.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.




**SPECIAL REMARKS:** Per the Road Plan, the Purchaser shall be required to install a gate provided by the State on the PP-ML road.



# TIMBER SALE MAP

SALE NAME: Equinox  
 AGREEMENT NO: 30-081682  
 TRUST(S): Forest Board Transfer (01)

REGION: Northwest  
 COUNTY(S): Snohomish  
 ELEVATION: 700' to 1,100'  
 TOWNSHIP/RANGE: T27N R7E W.M.



Harvest Area = 98 acres

Approximately:

Unit 1A = 19.1  
 Unit 1B = 15.7  
 WMZ A = 12.0  
 WMZ B = 5.2  
 Unit 2A = 2.2  
 Unit 2B = 41.6  
 WMZ C = 1.7  
 R/W = 0.5

Drawn By: Matt Leise  
 Date: October 3, 2007  
 Scale: 1" = 1000'  
 Version 1.2

500 0 500 1000 Feet



## Units

- ~~ Sale Boundary Tags
- ~ Special Management Unit Boundary Tags (1 per tree)
- Logged Area Boundary
- Streams / Wetlands
- > Type 1-5
- Wetland Boundary
- WMZ/RMZ


## Legend

### Roads

- Existing Road
- Required Reconstruction
- Required Construction
- Optional Construction
- Optional Reconstruction
- Logging Methods
- Cable
- Shovel

### Symbols

- Water Type Break
- Landing
- Wetlands
- Water Type
- Leave Tree Area
- Gate





TIMBER NOTICE OF SALE

**SALE NAME:** WIGTOWN

**AGREEMENT NO:** 30-081509

**AUCTION:** February 28, 2008 starting at 10:00 a.m., **COUNTY:** Thurston  
Pacific Cascade Region Office, Castle Rock, WA

**SALE LOCATION:** Sale located approximately 24 miles west of Olympia, WA

**PRODUCTS SOLD AND SALE AREA:** All timber, except leave trees bounded out with yellow leave tree area boundary tags, leave trees marked with blue paint, snags and down timber existing 3 years prior to the day of sale, bounded by timber sale boundary tags, reprod and the C-4000 and C-4600 roads in Unit #1 on part(s) of Sections 36 all in Township 18 North, Range 4 West, Sections 31 all in Township 18 North, Range 3 West, W.M., containing 52 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	15.4	8	1,474						789	560	125	
Hemlock	15	9	1,264						407	731	126	
Red cedar	14.6		15							6	9	
Red alder	16		13							11	2	
Sale Total			2,766									

**MINIMUM BID:** \$537,000.00 **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** Lump Sum

**EXPIRATION DATE:** June 30, 2009 **ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$53,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 35% and less during dry soil conditions. See Clause H-140 for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator.

**ROADS:** 3.12 stations of optional construction. 7.39 stations of optional reconstruction. 87.65 stations of required pre-haul maintenance. 3.12 stations of road abandonment, if road is built. Rock for construction under this contract may be obtained, at no cost to the Purchaser, from the Larch Pillar Quarry located in Section 2, Township 17 North, Range 4 West. Development and use shall be in accordance with the attached written "Development Plan" prepared by the State. Rock for construction or reconstruction or pre-haul maintenance is available at no cost to the Purchaser from existing stockpiles on State land; the Larch Pillar Quarry and the Low Bank Quarry located in Section 15, Township 17 North, Range 4 West. Purchaser shall remove no more than 500 cubic yards of 1½ INCH MINUS CRUSHED and 500 cubic yards of 3 INCH MINUS CRUSHED rock from the Low Bank Quarry. Rock for construction or reconstruction or pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator on the C-4000 road.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 100% cable harvesting.

**FEES:** \$36,649.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** Intermediate supports may be required to prevent soil rutting in Unit #1 off the C-4600 road.





TIMBER SALE MAP

SALE NAME: WIGTOWN  
AGREEMENT#: 30-081509  
TRUST(S): Common School (03), CEP&RI (06)

REGION: Pacific Cascade  
COUNTY(S): Thurston  
ELEVATION RGE: 1,240ft. - 1,675ft.


Township 18 North, Range 03 & 04 West, W.M.



DRIVING MAP

SALE NAME: WIGTOWN  
AGREEMENT#: 30-081509  
TRUST(S): Common School (03)

REGION: Pacific Cascade  
COUNTY(S): Thurston  
ELEVATION RGE: 1,240ft. - 1,675ft.



<ul style="list-style-type: none"><li>Highways</li><li>Haul Route</li><li>Milepost</li><li>Off Ramp</li><li>Distance Indicator</li><li>Rock Pit</li></ul>	<p><b>DRIVING DIRECTIONS:</b></p> <p>From State Route 8 (milepost 13), turn South onto the B-5200 and follow for 2.0 miles Keep left (south), staying on the B-5200 for 0.5 miles Turn left (southeast), onto the B-5000 for 0.2 miles Keepleft (east), on the B-5000 for 2.1 miles Turn right (southwest), onto the C-4000 and follow for 2.3 miles Veer left (southeast), staying on the C-4000 for 1.8 miles Veer right (southeast), staying on the C-4000 for 1.0 miles to Unit 1</p>
-----------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

**TIMBER NOTICE OF SALE**

**SALE NAME:** *HANGING CHAD BLOWDOWN*

**AGREEMENT NO:** *30-081336*

**AUCTION:** February 28, 2008 starting at 10:00 a.m., **COUNTY:** Wahkiakum  
Pacific Cascade Region Office, Castle Rock, WA

**SALE LOCATION:** Sale located approximately 15 miles northwest of Longview, WA

**PRODUCTS SOLD AND SALE AREA:** All timber, except eave trees marked with blue paint and pre-existing down timber existing 5 years prior to the day of sale, bounded by the following: timber sale boundary tags, special management boundary tags, reprod and the E-5000, E-5030 and E-5800 roads in Unit #1; timber sale boundary tags and the E-5000 road in Unit #5, timber sale boundary tags, special management boundary tags and the E-5000 road in Unit #6, special management boundary tags and the E-5000 road in Unit #7. All blown down and leaning timber bounded by the following: timber sale boundary tags and the E-5000 road in Unit #2; timber sale boundary tags and special management boundary tags in Unit #3, #9 and #10; timber sale boundary tags, special management boundary tags and the E-5800 road in Unit #4; timber sale boundary tags, special management boundary tags and the E-5000 road in Unit #8 on part(s) of Sections 13, 14 and 23 all in Township 9 North, Range 5 West, W.M., containing 188 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	17.1	6	3,359	\$87.10						2,237	999	123	
Douglas fir	25	6	461	\$175.00						330	123	8	
Sale Total			3,820										

**MINIMUM BID:** \$87.10/MBF (est. value \$373,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$74,600.00 **SALE TYPE:** MBF Scale

**EXPIRATION DATE:** October 31, 2009 **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Hemlock

**BID DEPOSIT:** \$37,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 35% and less. See Schedule L for further harvest requirements. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Harvesting restrictions are required in Unit 1 on the small area west of the E-5000 road and north of the E-5030 road from March 1st through August 31.

**ROADS:** 1.30 stations of required reconstruction. 34.32 stations of optional reconstruction. 10.86 stations of required pre-haul maintenance. 19.97 stations of road abandonment, if road is built. Rock is available at no cost to the Purchaser from the State E-7500 Road rock pit located in Section 1, Township 9 North, Range 5 West, W.M. Purchaser shall manufacture 2,012 cubic yards of 4 INCH MINUS rock. The Purchaser shall manufacture and stockpile 3,000 cubic yards of 1 ½ INCH MINUS CRUSHED rock at the E-7508 junction in accordance with the written development plan in the Road Plan. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Pre-haul maintenance on the E-5030 road will be restricted from March 1st through August 31. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 80% ground-based and 20% cable harvesting.

**FEES:** \$50,000.00 is due on day of sale. \$9.16 per MBF is due upon removal. These are in addition to the bid price.



**SPECIAL REMARKS:** See driving map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

**TIMBER SALE MAP**

**SALE NAME:** HANGING CHAD BLOWDOWN  
**AGREEMENT#:** 30-081336  
**TRUST(S):** Capitol Grant (07) & Scientific School (10)

**REGION:** Pacific Cascade  
**COUNTY(S):** Wahkiakum  
**ELEVATION RGE:** 800ft. - 1,200ft.

**Township 09 North, Range 05 West, W.M.**







TIMBER SALE MAP

SALE NAME: HANGING CHAD BLOWDOWN  
AGREEMENT#: 30-081336  
TRUST(S): Capitol Grant (07) & Scientific School (10)

REGION: Pacific Cascade  
COUNTY(S): Wahkiakum  
ELEVATION RGE: 800ft. - 1,200ft.


Township 09 North, Range 05 West, W.M.



DRIVING MAP

SALE NAME: HANGING CHAD BLOWDOWN  
AGREEMENT#: 30-081336  
TRUST(S): Capitol Grant (07) & Scientific School (10)

REGION: Pacific Cascade  
COUNTY(S): Wahkiakum  
ELEVATION RGE: 800ft. - 1,200ft.



<ul style="list-style-type: none"><li>Highways</li><li>Haul Route</li><li>Milepost</li><li>Off Ramp</li><li>Distance Indicator</li><li>Gate (PCP 1-1)</li><li>Rock Pit</li></ul>	<p><b>DRIVING DIRECTIONS:</b></p> <p>From State Route 4 (milepost 47.7), turn North onto Mill Creek Road and follow for 1.0 mile Turn left (west) onto Spruce Creek Road and follow for 0.6 miles Turn right (north) onto Cathlamet County Road and follow for 4.2 miles Turn right (north) onto the E-5000 and follow for 1.8 miles Continue on the E-5000 (through gate) for 1.4 miles to Unit 10 Continue on the E-5000 for 1.4 miles to Unit 1</p>
----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

TIMBER NOTICE OF SALE

**SALE NAME:** *APPLE PIE*

**AGREEMENT NO:** *30-080579*

**AUCTION:** February 25, 2008 starting at 10:00 a.m., **COUNTY:** Whatcom  
Northwest Region Office, Sedro Woolley, WA

**SALE LOCATION:** Sale located approximately 3 miles southwest of Acme, WA

**PRODUCTS SOLD AND SALE AREA:** All timber bounded by white timber sale boundary tags, adjacent young stands and the CC-14 Road, except trees marked with blue paint on the bole and root collar and forest products tagged out by yellow leave tree area tags, in Unit #1.

All timber bounded by adjacent young stands and the CC-1411 Road, except trees marked with blue paint on the bole and root collar, in Unit 2.

All timber bounded by white timber sale boundary tags and adjacent young stands, except trees marked with blue paint on the bole and root collar and forest products tagged out by yellow leave tree area tags, in Units #3 and 4.

All timber bounded by orange right of way tags. The above described products on part(s) of Sections 11 and 13 all in Township 37 North, Range 4 East, Sections 7 and 18 all in Township 37 North, Range 5 East, W.M., containing 68 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	22	8	1,560			181	407		638	279	55	
Hemlock	13	8	1,117						403	524	190	
Red cedar	13		267							215	52	
Red alder	16		212						64	62	86	
Cottonwood	28		63	35				11	11		6	
Maple	15		60						15	20	25	
Silver fir	13		23							20	3	
Sale Total			3,302									

**MINIMUM BID:** \$977,000.00 **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** Lump Sum

**EXPIRATION DATE:** September 30, 2009 **ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$97,700.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

**ROADS:** 8.88 stations of required construction. 47.48 stations of optional construction. 47.48 stations of road to be abandoned if built.

Development of an existing hardrock source (CC-2001 Pit) at station 4+75 of the CC-20 Road will involve drilling, shooting, and processing rock to generate riprap, shot rock subgrade ballast, and 3-inch minus ballast. This rock is available at no cost on State land.

Use of an existing 3-inch-minus surfacing rock stockpile within the Christie Hardrock Pit at station 182+85 of the CT-ML Road. This rock is available at no cost on State land.

This project is estimated to utilize approximately 158 cubic yards of riprap, approximately 710 cubic yards of shot rock subgrade ballast, and 3,795 cubic yards of 3-inch minus ballast.

Road construction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**TIMBER NOTICE OF SALE**

---

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS traverse. 110.5 acres gross. 2.9 acres deducted for green tree retention clumps, 35.5 acres deducted for RMZ/WMZ areas, 5 acres deducted for existing road surface. 67.6 acres net. Cruised using variable plot method. Expansion factor used is 54.45 for Units #1, #2, and #3; and 40.00 used for Unit #4. Sighting height is 4.5 feet. Grid size plot spacing is 320 x 200 feet in Units #1, #2, and #4; and 200 x 200 feet in Unit #3. Plot ratio cruise count is 1:1 in Units #1, #3, and #4; and Cruised All in Unit #2. 18 plots were taken in Unit #1, 4 plots taken in Unit #2, 12 plots taken in Unit #3, and 14 plots taken in Unit #4, for a total of 48 plots.

**FEES:** \$43,751.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


**SPECIAL REMARKS:** None.

# TIMBER SALE MAP

Page 1 of 3

SALE NAME: Apple Pie  
 AGREEMENT NO: 30-80579  
 TRUST(S): State Forest Board Transfer (01), Common School (03)  
 Township 37 North, Range 4 East, W.M.  
 Township 37 North, Range 5 East, W.M.

REGION: Northwest  
 COUNTY(S): Whatcom



## Legend

- |  |                    |  |                            |
|--|--------------------|--|----------------------------|
|  | Sale area          |  | Sale Boundary Tags (White) |
|  | Leave Tree Area    |  | Sale Boundary (Reprod)     |
|  | RMZ                |  | Existing Roads             |
|  | Wetland            |  | Required Construction      |
|  | Gate               |  | Optional Construction      |
|  | Rock Pit           |  | RightofWay                 |
|  | Stream Type Change |  | Skid Trail                 |
|  |                    |  | Streams                    |
|  |                    |  | Water Type 1 - 5           |

Drawn By: Bud Westcott  
 Date: June 19, 2007  
 Scale: 1" = 1000'  
 Elevation: 1400-2700ft.


# TIMBER SALE MAP

Page 2 of 3

SALE NAME: Apple Pie  
 AGREEMENT NO: 30-80579  
 TRUST(S): State Forest Board Transfer (01), Common School (03)

REGION: Northwest  
 COUNTY(S): Whatcom

Township 37 North, Range 4 East, W.M.  
 Township 37 North, Range 5 East, W.M.



Harvest Area = 68 acres  
 Approximately:  
 Unit 1 - 27.4  
 Unit 2 - 4.9  
 Unit 3 + R/W - 16.6  
 Unit 4 + R/W - 18.7

## Legend

- |  |                    |  |                            |
|--|--------------------|--|----------------------------|
|  | Sale area          |  | Sale Boundary Tags (White) |
|  | Leave Tree Area    |  | Sale Boundary (Reprod)     |
|  | RMZ                |  | Existing Roads             |
|  | Wetland            |  | Required Construction      |
|  | Gate               |  | Optional Construction      |
|  | Rock Pit           |  | RightofWay                 |
|  | Stream Type Change |  | Skid Trail                 |
|  |                    |  | Streams                    |
|  |                    |  | Water Type 1 - 5           |

Drawn By: Bud Westcott  
 Date: June 19, 2007  
 Scale: 1" = 1000'  
 Elevation: 1400-2700ft.


# TIMBER SALE MAP

Page 3 of 3

SALE NAME: Apple Pie  
 AGREEMENT NO: 30-80579  
 TRUST(S): State Forest Board Transfer (01), Common School (03)

REGION: Northwest  
 COUNTY(S): Whatcom

Township 37 North, Range 4 East, W.M.  
 Township 37 North, Range 5 East



## Legend

- Sale Area
- Roads
- X

 Rock Pit
- Gate

Drawn by: Bud Westcott  
 Date: June 19, 2007  
 Scale: none





TIMBER NOTICE OF SALE

**SALE NAME:** LOOK NORTH

**AGREEMENT NO:** 30-080923

**AUCTION:** February 25, 2008 starting at 10:00 a.m., **COUNTY:** Whatcom  
Northwest Region Office, Sedro Woolley, WA

**SALE LOCATION:** Sale located approximately 3 miles southwest of Bellingham

**PRODUCTS SOLD AND SALE AREA:** All timber, except trees marked with blue paint on the bole and root collar and forest products tagged out by yellow leave tree area tags, bounded by white timber sale boundary tags and existing harvested areas. All timber bounded by orange right-of-way tags. The above described products on part(s) of Sections 1, 11 and 12 all in Township 37 North, Range 3 East, W.M., containing 47 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	23	8	1,558				399		849	247	63	
Hemlock	12	6	552						172	244	136	
Red cedar	16		183							143	40	
Red alder	17		113						60	21	32	
Maple	22		53						21	22	10	
Cottonwood	28		15	9				5			1	
Sale Total			2,474									

**MINIMUM BID:** \$678,000.00 **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$100,000.00 **SALE TYPE:** Lump Sum

**EXPIRATION DATE:** September 30, 2008 **ALLOCATION:** Export Restricted

**BID DEPOSIT:** \$67,800.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable; cable or shovel or forwarder and, if approved, use of tracked skidders (tracked skidders will be limited to designated skid trails) on slopes 25% or less. Falling and Yarding will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator (THIS PERTAINS TO GROUND-BASED EQUIPMENT ONLY) to reduce soil damage and erosion.

**ROADS:** 11.73 stations of required construction. 39.85 stations of required reconstruction. 31.54 stations of optional construction. 32.03 stations of optional reconstruction. 27.68 stations of road to be abandoned if built.

Development of an existing hardrock source (Alger Hardrock Pit) at station 195+50 of the AL-ML Road will involve drilling, shooting, and processing rock to generate approximately 149 cubic yards of riprap, approximately 5,759 cubic yards of 3-inch-minus ballast rock, and approximately 685 cubic yards of 2-inch-minus surfacing rock. This rock is available at no cost on State land in Section 3, Township 36 North, Range 4 East. W.M..

Use of existing 2-inch-minus surfacing stockpile in the pit at station 195.50 of the AL-ML Road.

Road construction, road reconstruction, road abandonment, and the hauling of rock will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation. The hauling of forest products will not be permitted from November 1 to March 31 unless authorized in writing by the Contract Administrator to reduce soil damage and siltation.

**ACREAGE DETERMINATION**

**CRUISE METHOD:** Acres determined by GPS and Hand traverse. 49.0 acres gross. 1.7 acres deducted for green tree retention clumps and for exclusion areas. 47.3 acres net. Cruised using variable plot method. Expansion factor used is 54.45. Sighting height is 4.5 feet. Grid size plot spacing is 240 x 200 feet. Plot ratio cruise count is cruised DF and WH on every third plot and all other species were cruised on all plots. 42 plots were taken.

**FEES:** \$32,780.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.




TIMBER NOTICE OF SALE

**SPECIAL REMARKS:** The BZ-ML Road has a large volume of recreational use, safe speed of vehicle traffic is encouraged.

TIMBER SALE MAP

SALE NAME: Look North  
AGREEMENT#: 80923  
TOWNSHIP(S): Township 37 North, Range 3 East  
TRUST(S): Forest Transfer - 01

REGION: Northwest  
COUNTY(S): Whatcom  
ELEVATION RGE: 938-1319



Road Construction Types

- Existing Road
- Required Reconstruction
- Optional Reconstruction
- Optional Construction
- Required Construction

Unit Tags

- Sale Boundary Tags
- Right of Way Tags

Special Mgt Areas

- Wetland Mgt Zone
- Riparian Mgt Zone
- Leave Trees

- Sale Area
- Public Land Survey Sections
- DNR Managed Lands
- Wetland
- Streams
- Open Water



Prepared By: tkle490


Creation Date: 9/17/2007

Modification Date: 11/13/2007

# DRIVING MAP

**SALE NAME:** Look North  
**AGREEMENT#:** 80923  
**TOWNSHIP(S):** Township 37 North, Range 03 East  
**TRUST(S):** State Forest Transfer - 01

**REGION:** Northwest Region  
**COUNTY(S):** Whatcom  
**ELEVATION RGE:** 938-1319



**Legend:**

- Timber Sale Unit
- Other Route
- Highways
- Open Water

## DRIVING DIRECTIONS:

The proposal area is located approximately 3 miles southwest of Bellingham. From the I-5/Lakeway junction in Bellingham, travel 3.4 miles east on Lakeway Drive. Turn right (south) onto Lake Louise Road, and travel 2.3 miles. Turn right (west) onto the BZ-ML mainline and travel 0.8 miles. This will be the beginning of the reconstruction of the BZ-08 road.

Prepared By: tkle490

Creation Date: 9/21/2007

Modification Date: 11/2/2007



TIMBER NOTICE OF SALE

**SALE NAME:** READE MY LIPS THINNING

**AGREEMENT NO:** 30-079364

**AUCTION:** February 27, 2008 starting at 10:00 a.m.,  
Olympic Region Office, Forks, WA

**COUNTY:** Clallam

**SALE LOCATION:** Sale located approximately 2 miles southwest of Forks, WA for Units 1 & 2, 8 miles north of Forks, WA for Unit 3

**PRODUCTS SOLD AND SALE AREA:** All timber as described in Schedule B bounded by timber sale boundary tags, F-1000 Road, F-1000.1 Road, F-1010 Road, and a logged area in Unit #1; all timber as described in Schedule B bounded by timber sale boundary tags and the F-1010 Road in Unit #2; all timber as described in Schedule B bounded by timber sale boundary tags, T-1000 Road, T-1200 Road, and a property line in Unit #3; on part(s) of Sections 14, 15 and 23 all in Township 28 North, Range 13 West, Sections 4 all in Township 29 North, Range 13 West, Sections 33 all in Township 30 North, Range 13 West, W.M., containing 175 acres, more or less.

**ESTIMATED SALE VOLUMES AND QUALITY:**

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								UT
						1P	2P	3P	SM	1S	2S	3S	4S	
Hemlock	15	7	1,687	12,501	\$8.20						366	1,123	198	
Silver fir	11.4		132	916	\$8.20						54	34	44	
Douglas fir	9.4	4	20	178	\$8.20								20	
Sale Total			1,839	13,595										

**MINIMUM BID:** \$8.20/ton (est. value \$111,000.00)      **BID METHOD:** Sealed Bids

**PERFORMANCE SECURITY:** \$22,200.00      **SALE TYPE:** Tonnage Scale

**EXPIRATION DATE:** October 31, 2009      **ALLOCATION:** Export Restricted

**BIDDABLE SPECIES:** Bidding to be allowed on all species combined.

**BID DEPOSIT:** \$11,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

**HARVEST METHOD:** Cable methods for Units 1, 2 and 3. Ground methods for part of Unit 1. Yarding will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

**ROADS:** 10.84 stations of optional construction. 162.84 stations of required pre-haul maintenance. 66.07 stations of optional pre-haul maintenance. Purchaser maintenance on all new construction, the F-1000, F-1010, and T-1040 Roads. Designated maintenance on all roads not covered by purchaser maintenance. Road construction will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

**ACREAGE DETERMINATION CRUISE METHOD:** Sale area was 100% GPS'd. Sale units were cruised using a variable plot method with a BAF of 62.50F on a 660 x 660 foot grid for Units #1 and #3; a BAF of 40.00F & 62.50F on a 660 x 660 foot grid for Units #2.



**FEES:** \$24,367.00 is due on day of sale. \$1.22 per ton is due upon removal. These are in addition to the bid price.

**SPECIAL REMARKS:** There are locked gates located on the F-1000 Road, and at the Loop Tavern and Mary Clark Pits - contact the Olympic Region Dispatch Center at 360-374-6131 to obtain a AA-1 key. Ignore all blue painted trees.

TIMBER SALE MAP

SALE NAME: READE MY LIPS THINNING  
AGREEMENT NO: 30-079364  
TRUST(S): 01, 07, 08

REGION: Olympic  
COUNTY(S): Clallam



Drawn By: M. Helms  
Date: September 12, 2007  
Scale: 1" = 1000'

500 0 500 Feet


Elevation: 0 - 500'

Legend

~~~~~	Timber Sale Boundary Tags	➔	Streams
-x-x-	Property Line	[3]	Stream Type
	Ground	*	Stream Type Break
	Cable Only	◆	Survey Monument
	Cable or Ground	⊗	Rock Pit
=====	Existing Road	●—●	Gate
		----	Optional Construction

TIMBER SALE MAP

SALE NAME:	READE MY LIPS THINNING	REGION:	Olympic
AGREEMENT NO:	30-079364	COUNTY(S):	Clallam
TRUST(S):	01, 07, 08		




Drawn By: M. Helms
Date: September 12, 2007
Scale: 1'' = 1000'

500 0 500 Feet

Elevation: 0 - 500'

TIMBER SALE MAP

SALE NAME:	READE MY LIPS THINNING	REGION:	Olympic
AGREEMENT NO:	30-079364	COUNTY(S):	Clallam
TRUST(S):	01, 07, 08		



Drawn By: M. Helms
Date: September 13, 2007

TIMBER NOTICE OF SALE

SALE NAME: HAPPE MAX

AGREEMENT NO: 30-081047

AUCTION: February 27, 2008 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Clallam

SALE LOCATION: Sale located approximately 11 miles southwest of Forks, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags, except trees marked with blue paint in Units #1 and #3; all timber bounded by right of way boundary tags on part(s) of Sections 30 and 31 all in Township 28 North, Range 13 West, W.M., containing 90 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	17.5	4	846						171	582	94	
Hemlock	11.2	4	796							575	221	
Spruce	14.6	4	218						90	110	18	
Red alder	9.3		79							19	60	
Red cedar	8.6		51								51	
Sale Total			1,990									

MINIMUM BID: \$206,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY: \$41,200.00

SALE TYPE: Lump Sum

EXPIRATION DATE: October 31, 2008

ALLOCATION: Export Restricted

BID DEPOSIT: \$20,600.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and shovel methods. Due to wet soil conditions, no dozers or skidders will be allowed. This proposal will be yarded by approximately 70% cable methods and 30% shovel methods. Falling and Yarding will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator for Unit #1 and Unit #3 is restricted from October 1 to May 31.

ROADS: 13.68 stations of optional construction. 117.26 stations of optional reconstruction. Purchaser maintenance on the G-2000 Road. Designated maintenance on all other roads used. Purchaser must replace existing bridge with a minimum 50 foot single span portable bridge - see road plan for details. Work on or around the new bridge site will not be permitted from September 15 to May 15. The hauling of forest products will not be permitted from October 15 to April 15 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 100% GPS'd. Sale area was cruised using a variable plot sample with a BAF of 46.94F on a 330 x 200 foot grid for Units #1 & #3 and a BAF of 54.45H with a plot every 1000' for the right of way.



FEES: \$25,877.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There is a locked gate on the G-2000 Road - contact the Olympic Region Dispatch Center at 360-374-6131, to obtain a AA-1 key. Units #2 and #4 have been removed from the original proposal. ****Approximately 37 mbf of the red cedar volume is downed cedar salvage located in Unit #1.****

TIMBER SALE MAP

SALE NAME: HAPPE MAX
AGREEMENT NO: 30-081047
TRUST(S): Capitol Grant

REGION: Olympic
COUNTY(S): Clallam




Drawn By: M. Helms
Date: November 15, 2007
Scale: 1" = 1000'
500 0 500 Feet
Elevation: 0 - 500'

Legend

~~~~~	Timber Sale Boundary Tags	=====	Existing Road
~~~~~.	R/W Boundary Tags		Optional Reconstruction
////	Shovel	----	Optional Construction
=====	Cable	➔	Streams
.....	RMZ	3	Stream Type
◆	Survey Monument	*	Stream Type Break
●—●	Gate	⌵	Rock Pit

TIMBER SALE MAP

SALE NAME:	HAPPE MAX	REGION:	Olympic
AGREEMENT NO:	30-081047	COUNTY(S):	Clallam
TRUST(S):	Capitol Grant		



Drawn By: M. Helms
Date: November 16, 2007

TIMBER NOTICE OF SALE

SALE NAME: *LYRE RAIL COMMERCIAL THINNING* **AGREEMENT NO:** *30-081049*

AUCTION: February 27, 2008 starting at 10:00 a.m., **COUNTY:** Clallam
Olympic Region Office, Forks, WA

SALE LOCATION: Sale located approximately 15 miles west of Port Angeles, WA

**PRODUCTS SOLD
AND SALE AREA:** All timber as described in Schedule D, bounded by timber sale boundary tags,
management lines, property lines, the PA-J-3000 and the PA-J-3010 Roads in Units 1 and
2 on part(s) of Sections 34 and 35 all in Township 31 North, Range 9 West, W.M.,
containing 142 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total Tons	Price \$/Ton	MBF by Grade								UT
						1P	2P	3P	SM	1S	2S	3S	4S	
Douglas fir	10.7	7	749	5,153	\$12.00							301	448	
Spruce	10.8	6	242	1,453	\$7.00							137	106	
Hemlock	10.7	7	38	278	\$7.00							9	29	
Red alder	7.9	7	21	125	\$81.00							9	12	
Sale Total			1,050	7,009										

MINIMUM BID: \$12.00/ton (est. value \$84,000.00) **BID METHOD:** Sealed Bids

**PERFORMANCE
SECURITY:** \$16,800.00 **SALE TYPE:** Tonnage Scale

EXPIRATION DATE: October 31, 2009 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$8,400.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: 100% ground methods. Ground based yarding equipment restricted tracked skidder with grapple with one end fully suspended. Falling and Yarding will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. All activities are restricted between one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31.

ROADS: 6.61 stations of required construction. 105.97 stations of required pre-haul maintenance. Purchaser maintenance on the PA-J-3000, PA-J-3100 and PA-J-3101 roads and all new construction. Designated maintenance on any other roads used. Road construction and maintenance shall not commence prior to notification of the Crescent Water Association and the BPA - see road plan for details. No road construction activities on weekends or State recognized holidays. Purchaser is required to install a temporary 3 foot diameter culvert - see road plan for details. Road construction will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. The hauling of forest products will not be permitted from November 1 to May 31 unless authorized in writing by the Contract Administrator. All activities are restricted between one hour before to two hours after official sunrise and from one hour before to one hour after official sunset between April 1 and August 31.

ACREAGE DETERMINATION

CRUISE METHOD: Sale area was 90% photo traversed and 10% GPS'd. Units were cruised using a variable plot sample with a BAF of 20 on a 300' grid.

FEES: \$13,913.00 is due on day of sale. \$1.35 per ton is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There are locked gates on the PA-J-3000 Road and the PA-I-2600 (Place Road Pit); contact the Olympic Region Dispatch Center at 360-374-6131 to obtain a AA-1 key. Purchaser must notify the Crescent Water Association and the BPA prior to beginning operations - see the road plan for details.

TIMBER SALE MAP

SALE NAME:

LYRE RAIL COMMERCIAL THINNING

REGION:

Olympic

AGREEMENT NO:



30-081049

COUNTY(S):

Clallam

TRUST(S):

Forest Board Transfer



N

Drawn By: M. Helms

Date: July 31, 2007

Scale: 1" = 1000'

500 0 500 Feet

Elevation: 0 - 500'

~~~~~

Timber Sale Boundary Tags

~~~~~

Management Lines (no tags)

Streams

Stream Type

Stream Type Break

Crescent Waterline

Rock Pit

Gate

=====

Existing Road

Required Construction

Cable/Forwarder/Processor

Survey Monument

Wetland

Thin to 75 TPA

TIMBER NOTICE OF SALE

SALE NAME: SCOTCH

AGREEMENT NO: 30-081556

AUCTION: February 27, 2008 starting at 10:00 a.m.,
Olympic Region Office, Forks, WA

COUNTY: Clallam

SALE LOCATION: Sale located approximately 10 miles northwest of Forks, WA

PRODUCTS SOLD AND SALE AREA: All timber bounded by timber sale boundary tags and the Mina Smith Road, except trees marked with blue paint in Unit #1; all timber bounded by timber sale boundary tags, a property line, and the D-1000 Road, except trees marked with blue paint in Unit #2 on part(s) of Sections 5 all in Township 28 North, Range 14 West, Sections 31 and 32 all in Township 29 North, Range 14 West, W.M., containing 56 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	MBF by Grade								UT
				1P	2P	3P	SM	1S	2S	3S	4S	
Hemlock	14.3	4	722				6		182	411	123	
Douglas fir	18.4	4	523						221	252	50	
Spruce	18.9		355						182	131	42	
Red alder	9.4		19								19	
Sale Total			1,619									

MINIMUM BID: \$211,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY: \$42,200.00

SALE TYPE: Lump Sum

EXPIRATION DATE: October 31, 2009

ALLOCATION: Export Restricted

BID DEPOSIT: \$21,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and shovel methods. Shovel yarding is allowed only on slopes less than 35% slope. This sale can be harvested with approximately 50% cable methods and 50% shovel methods.

ROADS: 2.01 stations of optional construction. 58.03 stations of optional pre-haul maintenance. Purchaser maintenance on the D-1000 Road. Designated maintenance on all other roads used.

ACREAGE DETERMINATION

CRUISE METHOD: Sale was 100% GPS'd. Sale area was cruised using a variable plot sample with a BAF of 46.94F on a 220 x 180 foot grid for Unit #1 and a BAF of 40.00F on a 220 x 180 foot grid for Unit #2.



FEES: \$21,452.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.

SPECIAL REMARKS: There are locked gates in Unit #1 and at the Mora Pit - contact the Olympic Region Dispatch Center at 360-374-6131, to obtain a AA-1 key. There are hazard abatement requirements in Unit #1.

TIMBER SALE MAP

SALE NAME: SCOTCH
AGREEMENT NO: 30-081556
TRUST(S): Forest Board Transfer

REGION: Olympic
COUNTY(S): Clallam



Drawn By: M. Helms
Date: November 7, 2007
Scale: 1" = 1000'




Elevation: 0 - 500'

TIMBER SALE MAP

SALE NAME:	SCOTCH	REGION:	Olympic
AGREEMENT NO:	30-081556	COUNTY(S):	Clallam
TRUST(S):	Forest Board Transfer		

Vicinity Map
Not to Scale



Drawn By: M. Helms
Date: November 8, 2007

TIMBER NOTICE OF SALE

SALE NAME: *INSTANT KARMA BD*

AGREEMENT NO: *30-081414*

AUCTION: February 28, 2008 starting at 10:00 a.m., **COUNTY:** Lewis
Pacific Cascade Region Office, Castle Rock, WA

SALE LOCATION: Sale located approximately 4 miles northeast of Doty, WA

PRODUCTS SOLD AND SALE AREA: All timber, except leave trees bounded with yellow leave tree area tags, leave trees marked with blue paint, snags, pre-existing stumps and pre-existing down timber existing 2 years prior to the day of sale, bounded by timber sale boundary tags and the N-1015 road in Unit #1 on part(s) of Sections 17 all in Township 13 North, Range 5 West, W.M., containing 27 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg DBH	Ring Count	Total MBF	Total \$/MBF	MBF by Grade								
					1P	2P	3P	SM	1S	2S	3S	4S	UT
Hemlock	19.5	8	341	\$100.00						154	168	19	
Red alder	15.2		199	\$617.00					37	53	52	57	
Douglas fir	24.5	8	165	\$209.00						125	31	9	
Maple	14.3		25	\$20.00						3	3	19	
Sale Total			730										

MINIMUM BID: \$209/MBF (est. value \$191,000.00) **BID METHOD:** Sealed Bids

PERFORMANCE SECURITY: \$38,200.00 **SALE TYPE:** MBF Scale

EXPIRATION DATE: December 31, 2008 **ALLOCATION:** Export Restricted

BIDDABLE SPECIES: Douglas fir

BID DEPOSIT: \$19,100.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Cable and ground-based harvesting equipment with ground-based harvesting equipment being restricted to slopes of 40% or less during dry soil conditions. See Clause H-140 and Schedule L for further Harvesting Specifications. A detailed felling and yarding plan shall be required prior to any harvest activities and approved in writing by the Contract Administrator. Shovel Yarding will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ROADS: 25.20 stations of required pre-haul maintenance. Rock for pre-haul maintenance under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator. Any damage to any road resulting from any harvest operations will be repaired at the Purchasers expense unless authorized by the Contract Administrator. Road construction will not be permitted from September 30 to May 1 unless authorized in writing by the Contract Administrator.

ACREAGE DETERMINATION

CRUISE METHOD: The sale acres were determined by GPS. The sale area was cruised using a variable plot cruise method. Harvesting activities are estimated to be approximately 10% ground-based and 90% cable harvesting.

FEES: \$9,672.50 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.



SPECIAL REMARKS: Purchaser shall abate dust along the privately owned portion of the N-1000 road. See driving map for gate locations. Gate keys may be obtained from the Pacific Cascade Region office.

TIMBER SALE MAP

SALE NAME: INSTANT KARMA BLOWDOWN
AGREEMENT#: 30-081414
TRUST(S): Common School (03)

REGION: Pacific Cascade
COUNTY(S): Lewis
ELEVATION RGE: 550ft. - 920ft.

Township 13 North, Range 05 West, W.M.



DRIVING MAP

SALE NAME: INSTANT KARMA BLOWDOWN

AGREEMENT#: 30-081414


TRUST(S): Common School (03)

REGION: Pacific Cascade

COUNTY(S): Lewis

ELEVATION RGE: 550ft. - 920ft.

Township 13 North, Range 05 West, W.M.



Highways

Haul Route

Milepost

Off Ramp

Distance Indicator

Gate (PCP 1-1)

DRIVING DIRECTIONS:

From State Route 6 (milepost 33 @ Doty), turn North onto Stevens Road
Follow Stevens Road for 0.3 miles
Turn left (west) onto Elk Creek Road and follow for 2.0 miles
Turn left (south) onto the N-1000 (gate)
Follow the N-1000 for 1.4 miles (through second gate)
Turn left (south) onto the N-1015 and follow for 0.1 miles to Unit

Prepared By: Shawn B. & Angela S.

Creation Date: October 9, 2007

TIMBER NOTICE OF SALE

SALE NAME: PALMER VIEW

AGREEMENT NO: 30-080956

AUCTION: February 26, 2008 starting at 10:00 a.m.,
Northeast Region Office, Colville, WA

COUNTY: Okanogan

SALE LOCATION: Sale located approximately 8 miles southwest of Loomis, WA

PRODUCTS SOLD AND SALE AREA: All green western larch and ponderosa pine less than 28 inches in diameter at breast height banded with purple paint within Units #1, #2, and #3 bounded by white timber sale boundary tags and red ribbon; all green Douglas fir less than 28 inches in diameter at breast height and Engelmann spruce not banded with purple paint within Units #1, #2, and #3 bounded by white timber sale boundary tags and red ribbon; and all timber bounded by right of way boundary tags on part(s) of Sections 2, 3 and 10 all in Township 38 North, Range 25 East, W.M., containing 174 acres, more or less.

ESTIMATED SALE VOLUMES AND QUALITY:

Species	Avg Ring DBH	Total MBF	MBF by Grade								
			P	SM	1S	2S	3S	4S	5S	6S	UT
Douglas fir	11	1,357				175	200	982			
Ponderosa pine	14.6	47						24	23		
Larch	14	6					2	4			
Spruce	14.2	3					1	2			
Sale Total		1,413									

MINIMUM BID: \$153,000.00

BID METHOD: Sealed Bids

PERFORMANCE SECURITY:

\$30,600.00

SALE TYPE: Lump Sum

EXPIRATION DATE: July 31, 2010

ALLOCATION: Export Restricted

BID DEPOSIT: \$15,300.00 or Bid Bond. Said deposit shall constitute an opening bid at the appraised price.

HARVEST METHOD: Forwarder, Rubber tired skidder and Track skidder. Harvest operations shall be completed by January 31, 2010. Falling and Yarding will not be permitted from March 15 to June 1 unless authorized in writing by the Contract Administrator due to Spring breakup. Falling and yarding restricted from February 15 to July 15 in Unit #2 due to Golden Eagle restrictions.

ROADS: 74.50 stations of required construction. 34.78 stations of required reconstruction. 119.00 stations of prehaul maintenance required. Road construction will not be permitted from March 15 to June 1 unless authorized in writing by the Contract Administrator due to Spring breakup. Road construction restricted from February 15 to July 15 in Unit #2 due to Golden Eagle Restrictions. The hauling of forest products will not be permitted from March 15 to June 1 unless authorized in writing by the Contract Administrator due to Spring breakup. Hauling restricted from February 15 to July 15 in Unit #2 due to Golden Eagle Restrictions.

ACREAGE DETERMINATION

CRUISE METHOD: Acreage determined using GPS methods. Acreage shown above is net harvest acres in harvest units and external road right of ways. There are 177 gross acres which includes other existing road right of ways. All species, except ponderosa pine, 7.0 - 17.5 inches dbh cruised to a 4.6 inch dib top. Ponderosa pine 8.0 - 17.5 inches dbh cruised to 5.6 inch dib top. All species 17.6 inches dbh and greater cruised to 40% of dob at 16 feet.

FEES: \$18,725.00 is due on day of sale. \$9.00 per MBF is due upon removal. These are in addition to the bid price.


SPECIAL REMARKS: Within Unit #2, no activities will occur from February 15 to July 15 due to Golden Eagle nesting restrictions. Purchaser's contractor shall thoroughly clean all skidding, falling, harvesting, and loading equipment prior to entry onto State land to remove contaminated soils and noxious weed seed. Equipment shall be cleaned at a location approved by the Contract Administrator. Timber sale documents are available at the DNR Product Sales website: http://www.dnr.wa.gov/htdocs/fr/sales/appraisalpackets/mth_sum.html

Timber Sale Map

SALE NAME: Palmer View
AGREEMENT NO.: 30-080956
TRUST(S): Indemnity

REGION: NORTHEAST
COUNTY: Okanogan

Township 38 North, Range 25 East, W. M.



	Ground Skidding
	Timber Sale Boundary Tags
	Existing Road
	Required Construction
	Required Reconstruction
	Prehaul Maintenance
	R/W Tags
	Section/Property Line

Sale Area

1.7 Mi.
E382515B

6 Mi.
E382515B

3.2 Mi.

2.1 Mi.

SINLAHEKIN COUNTY RD

Loomis



Scale: 1" = 1000'
Drawn By: S. M.
DATE: 11/20/2007